



Environment and Social Impact Assessment (ESIA)

Transport Corridor Project - Road No. 2 - in Kurdistan

Segment 2 - Batil - Gersheen



إدارة ومتابعة المشاريع
Project Management and Control LLC

Executive Summary

Introduction

The Environmental and Social Impacts Assessment (ESIA) report is prepared for 13km long segment 2 Batil – Gersheen of Road No. 2 in Kurdistan. The Report follows the Terms of Reference for the Environmental and Social Impact Assessment (ESIA) and Resettlement Action Plan (RAP) for segments 2 and 3 of Road No. 2 in Kurdistan issued by the General Directorate of Roads and Bridges (GDRB) of Duhok.

The main goal of the study is to provide the decision-makers with a comprehensive tool that will allow them to implement the road upgrading in a way that is the least detrimental to the environment, population and businesses in the vicinity of the road alignment.

Project Description

Segment 2: Batil – Gersheen, 13km long (comprising 8km as part of TC and 5km connecting TC to Gersheen tunnel) is proposed to be upgraded from 1 lane both directions (single carriageway) to 3 lanes both directions (dual carriageway).

Segment 2 is a part of the 65km KRG Transport Corridor (KRG TC). The project is located in Duhok Governorate of the Northern autonomous region of Iraq – Kurdistan. The Duhok Governorate is the most northern district of Kurdistan and borders with Turkey from the North and Syria from the West. The TC is connecting the city of Duhok with the Ibrahim Al Khalil border with Turkey. The map of the TC with Segment 2 highlighted in blue on it is presented in the Figure 0-1.




Figure 0-1: Segment 2: Batil - Gersheen

The project has been under construction since July 2014. The expected completion date is April 2017. The rate of completion as of October 2015 is 41%. The breakdown of activities completed is presented in Annex 5.

Segment 2 of TC comprises expansion of the current road alignment from 1 lane both directions (single carriageway) to 3 lanes both directions (dual carriageway). A Right of Way (ROW) for road construction of 100 m has been adopted for land acquisition and approved by GDRB.

The proposed design speed for this road is 100 km/h. The horizontal and vertical alignments of the Road are designed taking into consideration type of terrain, design speed, the proposed cross section and planned Right of Way (ROW).

There is a directional interchange Smail Ava Interchange designed to a high standard allowing fast interchange in each direction. Sixteen box drainage culverts are provided at low points generally defined by shallow wadis. Three road underpasses are provided for livestock and wild animals crossing. Truck lay-bys are proposed on each direction of the road. The road will be furnished with the road signs (directional, warning, etc.), lighting, guardrail, Jersey barriers, and road markings.

Materials used for road construction include soils (possible re-use of cut materials), aggregates, Portland cement mixes, asphalt mixes, geo-synthetics, composites, and metals including steel and aluminum, wood materials. Significant water consumption is anticipated for the project.

The staffing requirements for the project implementation are estimated about 90 persons including the administrative, technical staff, construction crew and miscellaneous unskilled labor.

The summary of the road construction activities is presented in Table 0-1:

Table 0-1: Duration of Construction Activities

#	Activity	Duration (man days)
1	Construction of temporary detour routes: <ul style="list-style-type: none"> from station 22+100 to station 22+700 from station 17+000 to station 18+000 from station 22+100 to station 22+700 from station 22+700 to station 28+100 	
1.1	Clearance and surveying	15
1.2	Cut and fill works	15
1.3	Curbstone works	22
1.4	Aggregate sub-layer	36
1.5	Paving	17
1.6	Traffic signs installation	5

#	Activity	Duration (man days)
1.7	Setting up construction camp	10
2	Main road works	
2.1	Clearance	55
2.2	Cut/excavation	75
2.3	Fill operations	85
2.4	Curbstone works	70
2.5	Base sub-layer	80
2.6	Base layer	50
2.7	Tiling	50
2.8	Bridges and culverts works	170
2.9	Utilities installation	80
2.10	Installing reinforced concrete structures	130
2.11	Installing road lighting equipment	90
2.12	Paving	60
2.13	Installation of guardrails and barriers	60
2.14	Traffic signs installation and road markings	30

The project has been under construction since July 2014. The works completion rate as of 25.10.2015 was 41%.

Policy, Legal and Institutional Framework

The desk study on legal and institutional framework was conducted in order to assess the relevant existing legislation, policies and role of the different institutions in the project. The most applicable World Bank safeguard policies were also assessed and compared to the national legislation.

Policies and Strategies:

- National Development Plan of Iraq 2011 -2014
- Kurdistan Regional Government's Economic Development Strategy
- Iraqi Transport Master Plan

Legal National Framework:

- The Law for the Protection and Improvement of Environment No. 27, 2009
- The Forestry Law No. 30, 2009
- The Law on the Protection of Wild Animals and Birds No. 17, 2010
- Public Health Law No. 89, 1981
- The Law of Antiquities and Heritage No. 55, 2002

- Regulation for the Provision of Water Resources, No. 2, 2001
- Law of Environmental Protection and Improvement in Iraqi Kurdistan Region No.8, 2008
- Law on Public Roads No. 35, 2002
- Law of Land Acquisition No. 12, 1981

According to the World Bank definition the project is categorized as **Category A**. The policies that are viewed as most relevant to the scope of the present study are:

- Environmental Assessment (OP/BP 4.01)
- Involuntary Resettlement (OP/BP 4.12)
- OP/BP 4.11 – Physical Cultural Resources
- BP 17.50 Disclosure Policies

Institutional and Administrative Framework

The role of environmental protection is divided between different governmental institutions, which are responsible for specific aspects of environmental management. Also, some NGOs and scientific centers and universities are contributing to the nature protection in the Kurdistan Region.

- The Ministry of Natural Resources of the Kurdistan Regional Government;
- Ministry of Agriculture and Water Resources;
- Ministry of Environment/Environmental Protection and Improvement Board is the major governmental agency responsible for environmental conservation and protection.
- Ministry of Construction and Housing;
- Ministry of Municipalities and Tourism/Archeological Directorate of Duhok;
- Municipalities;
- NGO - Farasheen Organization for Environmental Protection (FOEP);
- Duhok Farmers Union;
- University of Dohuk.

A number of international donor organizations are active in the Kurdistan Region and are implementing projects designed to improve the livelihoods of the population.

Despite the fact that quite a number of institutions are involved in environmental protection and conservation, the institutional framework of the Kurdistan Region is characterized with a number of deficiencies:

- Dispersion of authorities and low level of coordination between different institutions;
- Overlap of jurisdiction, which might lead to overlooking the significant issues;
- Lengthy and bureaucratic process of obtaining permits for different kind of activities.

As authorized by KRG, DGRB bears primary official responsibility for ensuring that land acquisition and resettlement associated with the new road alignment are planned and implemented in a manner consistent with the laws and regulations of Kurdistan Region, and in a manner consistent with the principles and procedures of World Bank OP 4.12.

Effective implementation of resettlement program requires coordination with the Duhok governorate along with their subordinate district governments, and with local councils and village committees functioning at the village or settlement level.

Public Consultation

Public participation makes a positive contribution to the project in terms of minimizing and avoiding potential public controversy and in identification of priorities of assessment.

Stakeholders' identification and analysis was conducted according to the World Bank categorization of the stakeholders according to their interest and influence in the present study.

The key stakeholders identified include:

- GDRB
- Directorate of Agriculture of Duhok
- Directorate of Water of Duhok
- Directorate of Antiquities of Duhok
- Farmers' Association of Duhok
- Directorate for Environmental Protection and Improvement Board of Duhok
- Local administration
- Farmers
- Business entities
- Duhok University
- Zakho University
- Al Farasheen Environmental NGO

Public awareness was achieved through:

- Consultation Session on July 17, 2013 attended by 40 participants;
- Consultations with PAPs;
- Interviews with the governmental officials;
- Negotiations of Compensation Committee with individual PAPs on the size of the land acquisition and proposed compensation.

Based on the main issues of concern expressed by the stakeholders throughout the consultations the criteria and requirements for project acceptance are described in Chapter 5.6.

The Grievance Redress Mechanism is prepared according to the OP 4.12 on *Involuntary Land Acquisition and Resettlements* described in Chapter 5.7.

The main findings of the public consultations:

- Overall, the project is perceived as beneficial for economic development of the area and received support and approval of the different level of stakeholders;
- Main issues of concern:
 - The effect of land acquisition on livelihood levels of the PAPs;
 - Availability of equitable compensation for the loss of land
 - Provision of safety measures for the road users;
 - Conservation of archeological sites and sites of cultural and religious importance.
 - Conservation of natural resources: water, soils and wildlife;
 - Minimization of the air pollution.

Baseline Conditions

Physical Environment

The road alignment is located in the area, which is characterized as sub-humid upland and mountain region with semi-arid Mediterranean climatic conditions, which includes the Zagros Mountains and valleys as well as a part of the foothills. The main annual rainfall ranges between 400 mm and 1 100 mm. The mean minimum in July is about 22°C. In winter the mean monthly minimum in January is 10°C and the lowest minimum is -11°C.

The prevailing wind direction at the project area is South-East and sometimes tends to South-West and North-West. Wind speed is generally of light to moderate value with wind speeds between 0.74 m/sec at times in November and 1.20 m/sec at other times April to July.

Segment 2 is located in the area that is characterized as undulating terrain: a transitional area between low plains and the mountainous region in the north and northeast.

The road is located at the foot of the Zagros Mountains and comprises of hills 500 to 1 000 meters high. It consists of beds of gravel, conglomerate and sandstones. The gravel and conglomerate layers alternate with thin layers of reddish loam and clay. The main soil types are calcic and gypsum xerosols.

A regional stratigraphic column shows the presence of a thick Jurassic and Cretaceous succession composed of carbonates, shale and anhydrites. At its type locality within Iraqi Kurdistan, the formation is composed of thin-bedded, black bituminous limestone, dolomitic limestone and black papery shale with streaks of thin black chert in the upper part.

The groundwater resources are identified as a shallow aquifer belonging to the Zakho Basin. The Zakho Basin stretches across the border between Iraq and Turkey. In Iraq, the Zakho Basin has a catchment area of about 1,107 km². In the early 1980s an estimated total of 24.3 MCM of good-quality (<700 mg/L TDS) water had been abstracted (9.5 MCM from deep wells and 12.3 MCM as spring discharge).

There are no wells in the vicinity of Segment 2 of the road. It is estimated that there are 1958 licensed wells and about 62 illegal wells in the Duhok Governorate. The city of Duhok depends on the water supply from Tigris River, but other localities in the Governorate depend to some extent on the groundwater abstraction for the water supply.

Surface water resources comprise seasonal runoff valleys. Generally, all the seasonal streams drain towards the Tigris River. The drainage area is characterized as undeveloped cultivated land with the catchment slopes ranging from 0.09 to 0.15 %. The catchment area is estimated as ranging from 1, 7 to 2.1 km². The peak runoff for 25 years period is evaluated as approximately 1.8 - 4.3 m³/sec.

Ambient air quality monitoring and noise monitoring has not been performed previously in the project area. The main sources of the air pollution in the area are the traffic emissions and dust generated by agricultural plowing.

Biological Environment

The area has been subjected to diverse human induced impacts over the millennia such as rain-fed cultivation. Therefore, natural habitats have suffered the significant level of degradation over the past several hundred years. The terrestrial ecosystem within the vicinity of the Segment 2 is characterized as Middle East Steppe eco-system. The conservation status is defined as vulnerable.

Vegetation reflects the Mesopotamian province of the Irano-Turanian eco-region. It is characterized by the dominance of the drought-tolerant low shrubs with a variety of grasses and legumes.

The area of the project is located in a general area identified as a fly-way route for migratory birds from Eastern Europe and West Siberia to Mesopotamia and Africa.

The project area does not contain any globally important habitats or ecosystems. There are no Nature Reserves or other legally protected areas in the vicinity of the project or in a close proximity. No conservation practices are exercised in the project area apart from the control of hunting to the extent they are controlled and monitored throughout the country.

The globally important mammalian species include the Euphrates Jerboa, defined by IUCN as nearly threatened and Harrison's Gerbil, defined as endangered.

Bird species identified as regionally or globally important are:

Finsch's Wheatear	<i>Oenanthe finschii</i>	Winter visitor	Regionally threatened species
Corncrake	<i>Crex Crex</i>	Passage migrant	Globally threatened species

The flora and fauna species that can be found in the project area are listed in the section 6.2

Main Land Use Patterns

The prevalent land use in the project area is agricultural, composed of the rain-fed cultivation of cereals and livestock grazing. There are no residential settlements in the project area. Industrial and commercial activities in the project area are presented in Table 0-2:

Table 0-2: Business Entities within Segment 2 Alignment

#	Name of Business Entity	Location Coordinates
1	Evin Gas Oil Station	E: 42,652088 N: 36,978423
2	Junk Yard	E: 42,651081 N: 36,979785
3	Gersheen Company and Fuel Station	E: 42,640558 N: 36,994753
4	Efor Company	E: 42,645086N: 36,957745
5	Bawer Fuel Station	E: 42,645028N: 36,967908
6	Aveen Tires and Repair Shop	E: 42,651098 N: 36,979775
7	Azra Company	E: 42,652551N: 36,977560
8	Arcelik Company	E: 42,654433 N: 36,974378

In addition to the business entities in the project area, there are a number of fixed assets that are likely to be affected by the ROW and are subject to land acquisition:

- Fence at the abandoned private ceremonial building, commonly known as “Marriage Hall”;
- BRC/Fence of Company for trade in Ceramics;
- Fence around uncultivated land;
- Sign post of the Bawer Fuel Station;
- Sign post of Efor Company;
- Sign post of Evil Gas Station.

In total of 568,698 m² of land are to be acquired permanently for the project, 565,615 m² are used for cultivation and grazing activities.

The permanent land to be acquired includes all land needed for the right of way, servicing areas, underpass and culverts.

Baseline Socio-Economic Conditions

The total population of Duhok Governorate is approximately 1.5 million people. The population growth rate is estimated as 2.23% for the year 2014. However, due to the political situation in the region the area witnessed the influx of refugees and IDPs from the neighboring regions over the past year, amounting approximately to 1.2 million people.

According to the official statistics, the ratio of males to females shows a close number of the two genders. The economically active population, between the ages 16-64 constitutes about 36 % of the total population of Duhok Governorate.

On average the household in the study area is composed of 7.1 members with almost equal distribution between males and females of whom 2.6 are young people aged between 0 and 15 years and 3.5 are adults.

The households receive income from the different sources, such as wages, social benefits, property income, etc. Overall, households receive 45.3% of their income from wages and salaries; 25.0% from self-employment and employer income; 19.8% from property income; 5.2% from social payments; 4.7% from “transfers” from outside the country. Additionally, under the food rationing system (Public Distribution System – PDS which replaced Food for Oil Program), each Iraqi is entitled to a monthly food basket for a nominal fee of 250 Iraqi dinars (\$0.21). Also, government subsidizes heating/cooling of the dwellings, additional electricity supply of the dwellings by distributing fuel to households.

The main features of the PAPs households in the project area are as following:

- The household size is quite large, ranging from 6 to 9 people on average.
- Most of the households depend almost exclusively on the income from the agricultural activities.

The unemployment rate in Duhok Governorate reaches almost 17%, which is slightly higher than the average of the Kurdistan Region.

Sewage disposal: the main method of sewage disposal are cesspits. Only 5.5 % of households are connected to the sewage network. The condition of the cesspits is questionable, and the collected sewage is literally dumped into the streams that discharge into the River Tigris without any kind of treatment.

Solid waste disposal: solid waste collection from houses in residential areas in Duhok district stands at 79 %. As much as 40% of the collected solid waste is dumped in open unauthorized sites. The only authorized dumping site is located at about 7 km west to the road alignment.

Water Supply: 88 % of households in Duhok receive drinking water from the public water network. The main source of the drinking water is the treated water from the River Tigris. The wells as source of potable water are used mainly in the smaller villages and towns.

Electricity: The percentages of functioning electricity supply system are of 70.3% in the urban areas, 89.5% in the collective towns, and 79.7% in the rural area. The electricity blackouts in Duhok Governorate are reported to be from 6-15 hours per week.

Health Care: In the governorate of Duhok there is one hospital or health center in use for every 10,168 residents in the urban area, one for every 7,781 in the collective town, and one for every 5,421 in the rural area.

Education: about 30% of the population is illiterate, education of almost 47% of population is limited to the primary level of “read and write” only, about 10% - level of intermediate education, about 8% - secondary education and vocational training, and only about 5% have higher education.

Roads and Transportation

The following table shows the distributions of key attributes from the road inventory survey, in terms of the length of the road network with different characteristics and by road type.

Land Use	Duhok (km)		
	Highway	Secondary	Total
Agriculture	48.2	132.2	176.9
Commerce	0.0	0.0	0.0
Industry	7.3	0.6	8.5
Residential	77.2	119.0	196.1
Vacant	426.9	593.4	1023.7
Mixed use	0.0	1.2	1.1
N/A	0.0	6.0	5.7
Grand Total	559.6	852.4	1412.0

More information on roads and transportation in the project area is presented in Section 6.6.6.

Impact Assessment

The scoping of anticipated impacts was conducted using the Leopold Matrix. This matrix has: on the horizontal axis, the actions, which cause environmental impact; and on the vertical axis, the existing environmental conditions, which may be affected by those actions. This provides a format

for comprehensive review of the interactions between proposed anthropogenic actions and environmental factors.

The project activities with the highest number of identified negative impacts during the construction phase are:

- Potential alteration of surface watercourses.
- Generation and disposal of construction waste.
- Operations of the construction camp.
- Operation of asphalt plant;
- Excavation works and fill works;
- Construction of access roads, embankment, culverts and underpass;
- Paving and operation of asphalt plant.
- Movement of construction machines and vehicles.
- Land acquisition.

The most significant environmental and social impacts identified for the construction phase of the project are:

- Soil erosion and contamination caused by construction works;
- Air pollution (dust) caused by construction works;
- Disturbance to movement of livestock;
- Noise caused by construction vehicles and machines;
- Health and safety of project workers;
- Land acquisition from PAPs without legal rights to agricultural land;
- Crop loss and reduced income level of local farmers;
- Disturbance to business activities due to restriction of access during construction.

The most significant environmental and social impacts anticipated for the operational phase of the project are:

- Air pollution (NO_x, CO, HC, PM, benzene, formaldehyde, ozone) caused by traffic;
- Noise caused by traffic;
- Soil contamination;
- Habitats fragmentation;
- Disruption of livelihoods;
- Health and safety.

The negative environmental and social impacts of the construction activities of the project are expected to be relatively minor to moderate and short-term. None of the identified negative impacts of individual construction activities were found particularly significant. The impacts during the operational phase of the Project are fewer and less significant than during the construction phase.

Indirect Impacts

Indirect impacts are defined as “caused by the action and are later in time or farther removed in distance, but are still reasonably foreseeable”. The main indirect impacts are:

- Potential contamination of the groundwater;
- Minor changes in land use pattern – from predominantly agricultural to increase of low density commercial/industrial development.

Cumulative Impacts

Cumulative impact is defined as “the impact on the environment which results from the incremental impact of the action when added to other past, present, and reasonably foreseeable future actions”.

The main cumulative impacts are:

- Increases in impervious surface might have a potential impact on water quality downstream.
- Land use and farmland conversion.
- Incremental effect of construction waste disposal on waste management in the area.
- Incremental impact on habitat fragmentation.

Irreversible Impacts

Although, the road will induce the economic development in the area, the unplanned urban expansion and encroachment on agricultural lands might result in the loss of the fertile top soil and have long-term adverse impacts on the shallow aquifer.

Relatively minor impacts would occur to previously disturbed habitats, non-native vegetation communities and agricultural lands. These environmental changes are considered irreversible, but not significant.

The approved alignment alternative would result in the permanent acquisition of approximately 568,698 m² of land. Within the acquired lands there are relatively small remnants of natural and semi-natural habitats. Additionally, the long-term use of the road will have the impact on air quality and noise.

The irreversible (residual) impacts are considered minor and include:

- Change of land use pattern;
- Impact on air quality and noise.

Chapter 7 provides comprehensive description of the anticipated impacts during construction and operational and maintenance phases.

Mitigation Measures

The negative environmental and social impacts identified can be prevented or minimized by applying mitigation measures. The key mitigation measures of the construction phase of the Project include (see table A and chapter 8 for details):

- Collection and transportation of wastes to the designated disposal sites;
- Provision of sixteen culverts of adequate size;
- Placement of drains to avoid cascading and soil erosion;
- All operations other than piling shall be restricted to the hours of 07.00 – 20.00;
- Piling operations should be restricted to the hours 08.00 – 19.00 and not undertaken during public and religious holidays;
- Regular and adequate maintenance of vehicles and equipment to ensure there are no excessive exhaust emissions or leakages;
- Water spraying of conveyors, stockpiles, roads and earth works during windy dry periods to prevent dust emissions;
- Covering all vehicles transporting materials likely to give off excessive dust;
- Stop the construction activities in the area of the chance find;
- Adequate signage should be provided for motorists and pedestrians;
- Provision of underpass for livestock and wild animals crossing;
- Provide training to workers on potential risks and hazards of construction;
- Provide the PPE and enforce its use;
- Cash compensation for the loss of crops.

Examples of key mitigation measures of the operational and maintenance phase of the Project include (see table B and chapter 8 for details):

- Maintaining the roads drainage systems;
- Apply emergency measures for neutralization of chemicals and if necessary remove and replace the contaminated soil - in case of the accidents involving the spill of hazardous chemicals and vehicle fuel;
- Maintenance and clearance of debris in the underpass for livestock and wild animal crossing;
- Planting and maintenance of trees and bushes to form green belt along the motorway.
- Provision of directional and warning road signage;
- Provision of street lighting to reduce accidents at night and at times of reduced visibility.

Environmental and Social Management Plan (ESMP)

Summaries of the Environmental and Social Management Plan (ESMP) for both construction and operational phases of the Project are presented in following tables A and B. The ESMP contains interlinked impacts, project activities, mitigation measures, monitoring, and estimated costs of mitigation and monitoring. ESMP monitoring is presented as monitoring parameters, frequency of monitoring and monitoring responsibilities.

Part of the mitigation measures included into the Environmental and Social Management Plan are imbedded into the project design and therefore do not require additional investment. These are:

- Provision of the PPE for working personnel (responsibility of the contractor);
- Provision of warning signs for public safety;
- Provision of safe crossings for pedestrians;
- Provision of waste collection and disposal.
- Provision of monetary compensation for loss of income from agriculture.

The estimated costs of mitigation measures during the construction phase of the project reach 2,735,000 US \$. The mitigation measures during the operational phase of the project are limited to standard maintenance activities. Therefore, they are not specifically priced.

The ESMP monitoring costs during the construction phase are estimated at 75,500 US \$. They consist of the cost of environmental monitoring specialist, and the cost of tests.

The annual cost of monitoring during operational phase is estimated at 11,800 US \$. The cost include 3,800 US \$ for testing, and 8,000 US \$ cost of environmental monitor input.

The responsibility for safeguards monitoring during the construction phase lies primarily with the GDRB and the Contractor. During the operational phase, the GDRB will be responsible for monitoring.

Table A: ESMP – Construction Phase

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
Land Acquisition	Loss of crops (approximately 138 tons of cereals).	Expansion of the ROW. Land acquisition for underpasses, intersections, lay-byes, culverts.	Monetary compensation for loss of crops At 800 US \$ per ton.	<ul style="list-style-type: none"> • Compliance with the land acquisition plan and disbursement of compensation. • Restoration of access to the resources. • Sufficiet provision of the compensation budget. • Disbursement of transitional and other allowances as identified. • Registration of records of grievance issues. • Records of communication with the local community. 	<ul style="list-style-type: none"> • First three months – once a week. • Following four months – bi-weekly. • The rest of construction period – monthly. 	PMT at GDRB. Compensation Committee.	Market value at the time of survey – 110,000 US \$	No additional environmental and social monitoring cost for the Contractor.
	Business relocation (Aveen Tire Shop – 167.5 m ²).		Allowance to cover relocation of equipment, fixtures and inventory.				11,000 US \$	
	Fixed assets acquisition (total 1,897.5 m of fences).		<ul style="list-style-type: none"> • Compensation at replacement cost. • A combination of cash compensation at replacement cost and land-for-land replacement with a total value equivalent to the total valuation of the land to be acquired. 				103,164 US \$	
	Loss of agricultural land (total 568,615 m ²)		No monetary compensation – the land is state owned.				N/A	
	Livelihood disruption.		Monetary compensation for loss of crops at 800 US \$ per ton for the year after land				Individual financial assistance to be reviewed case by case by GDRB.	

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
			Additional financial assistance to vulnerable PAPS.					
	Disruption of Services.	Relocation of four electric poles.	Restoration of services. Consider upgrading of infrastructure.				2 000 US \$	
Water Resources	Local alteration of water flow and drainage at locations: 1. N: 36.997206 E: 42.639803 2. N: 37.037690 E: 42.645715 3. N: 37.024310 E: 42.645715	<ul style="list-style-type: none"> Excavation. Disposal of construction debris in surface water courses. Uncontrolled run-off in ditches. 	<ul style="list-style-type: none"> Placement of excavated material and debris should be avoided in the areas of the runoff routes. Provision of sixteen adequate size culverts. Disconnecting road sediment sources to watercourses through use of rolling dips, water weirs and filter strips. Use of sufficient drainage structures to minimize run-off in inside ditches. 	Changes of water courses, placement of excavated materials, culverts compliance with design.	Bi-weekly during rainy season.	GDRB – monitoring and supervision.	1 970 705 US \$ for culverts construction.	No additional environmental monitoring cost for the Contractor.
	Potential contamination of surface water (same locations as the point above).	Leakage of hazardous fluids from construction machinery.	Vehicle used during construction/ maintenance phases should be well maintained to	Visual observations of vehicle conditions, storage of materials, inspection of	One time prior to construction to establish baseline.	GDRB: monitoring and supervision.	No additional cost.	GDRB: 500 US \$ per test, total 6 water quality tests – 3 000 US \$

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
		<ul style="list-style-type: none"> Accidental spills of oils and petrol. Wash off of construction materials during rain events. Inadequate storage of construction materials. Inadequate disposal of liquid and solid waste at construction camp site. 	<ul style="list-style-type: none"> reduce emissions, be free of leaking fluids and be covered to reduce/prevent spills. Removing or minimizing side casts. Applying upgraded surfacing. Applying time restrictions during rain events. Heaps and stockpiles of aggregate, fill and spoil should be located at sites that do not permit direct runoff into watercourses and are on land sloping at less than 1.5 %. Avoid storage of surplus materials on site and provide for regular disposal of all surplus materials. 	logbook, photographic evidence. Water quality parameters: pH, Turbidity, Electrical Conductivity (EC), Color, Total Suspended Solids (TSS), Total Dissolved Solids (TDS), Chemical Oxygen Demand (COD), Biological Oxygen Demand (BOD), Polychlorinated Biphenyls (PCBs).	One time during construction during rainy season for each seasonal run-off			No additional environmental monitoring costs for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
			<ul style="list-style-type: none"> Emergency response for accidental spills of hazardous materials. 					
Soils	Soil erosion (along the road alignment).	<ul style="list-style-type: none"> Site clearance Excavation/Cut operations. Inadequate drainage. 	<ul style="list-style-type: none"> Placement of drains to avoid cascading. Localized lining of receiving channels. Construction of sufficient discharge points. Avoid site clearance well in advance of construction. Reinstatement and after-use. 	<ul style="list-style-type: none"> Alteration of natural drainage systems and/or additional drainage channels observed, photographic evidence. 	Bi-weekly during the rainy season, and after sporadic rains. Duration between the site clearance and start of construction activities not to exceed three weeks.	GDRB: monitoring and supervision.	Cost of drainage systems (as specified above)	No additional environmental monitoring costs for the Contractor.
	Soil Contamination near the temporary storage site of fuel and liquid waste, and near the construction camp).	<ul style="list-style-type: none"> Accidental spills of hazardous materials. Leakage from construction machinery and stored construction materials. Inadequate disposal of liquid and solid waste at 	Same measures as for prevention of surface water contamination.	Visual observation of spillages and leakages, photographic evidence, inspection of logbook. Soil parameters: pH, temperature, organic content, poly-aromatic hydrocarbons	Random soil test along the road alignment to establish the baseline. Soil tests immediately after any spillages of fuel and liquid waste. One random soil test after	GDRB: monitoring. Directorate of MAW of Duhok: supervision.	No additional costs.	GDRB: soil tests: 1,500 US \$ total. No addition environmental monitoring costs for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
		construction camp.		(PAHs); Faecal coliforms and Total coliforms.	completion of works at locations of temporary storage of fuel and waste.			
	Loss of productive fertile soil (along the road alignment).	<ul style="list-style-type: none"> Site clearance. Excavation. 	<ul style="list-style-type: none"> Clearance procedures that separate topsoil. Transport and store topsoil and possible transport to the re-use site should be adopted 	<ul style="list-style-type: none"> Conditions of soil in the temporary prism storage. Approach to re-use of soil. 	Monthly	GDRB: monitoring and supervision.	No additional cost.	No additional monitoring costs for the Contractor.
Ecology and Biodiversity	Habitat fragmentation	<ul style="list-style-type: none"> Site clearance; Landscape alteration Inadequate disposal of solid waste and construction debris; Excavation. 	<ul style="list-style-type: none"> Avoid works on or near watercourses during rainy seasons. Provision of three underpasses for livestock and wild animals. Using only defined and approved liquid and solid waste disposal sites. Importing gravel and other materials only from approved sites. 	<ul style="list-style-type: none"> Habitat disruption due to construction activities. Number of animal kills. Provision of training for the workers on habitat fragmentation. Site restoration after work completion. Inspection of logbook, 	Monthly	GDRB: monitoring. Directorate of Environment of Duhok: supervision.	538,525 US \$ for underpasses construction.	No additional environmental monitoring costs for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
	Loss of trees and plant species.	<ul style="list-style-type: none"> Vehicle movements beyond ROW. Cutting down the trees and bushes to be used for fuel and burning. 	<ul style="list-style-type: none"> Providing the workers camp with the fuel for heating and cooking to avoid cutting of wood. Replanting of removed trees. Confine traffic to defined routes. 	photographic evidence.				
	Loss of fauna species.	<ul style="list-style-type: none"> Destruction of dens, burrows and nests, clearance of feeding grounds. Increased traffic kills. Possible illegal hunting by off-duty construction workers. 	<ul style="list-style-type: none"> Limiting construction noise and vibration to day time hours. Provision of underpasses for wild animals and livestock. Training for construction crew on the impact of disturbance and damage to habitats. Avoid works along watercourses during rainy season. 					

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
	Dust nuisance.	<ul style="list-style-type: none"> • Movement of vehicles on unpaved surfaces. • Excavation. • Transporting of cut materials and aggregate materials. 	<ul style="list-style-type: none"> • Water spraying of sites and not paved access roads. • Water troughs at entry and exit points to prevent carryover of dust emissions from sites. • Establishing speed restrictions for all vehicles • Covering all vehicles transporting materials likely to give off excessive dust. • Construction sequencing and disturbing only small areas at a time. 	<ul style="list-style-type: none"> • Dust abatement approach (visual observations, photographic evidence, logbook inspections). • Air quality parameters: PM10, PM2.5, SO2, TSP, NOx, CO, Ozone and HC 	Weekly monitoring of implementing of dust abatement measures. Air quality testing: <ul style="list-style-type: none"> • One time prior to construction to establish the baseline; • One time during construction (during dry season). 	GDRB: monitoring and supervision. Contractor – internal monitoring.	Cost of regular vehicles maintenance. Cost of water spraying of unpaved surfaces.	GDRB: outsourcing of air quality testing: 6 000 US \$ No additional environmental monitoring costs for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
Ambient Air Quality	Air pollution from emissions.	<ul style="list-style-type: none"> • Inadequate condition of construction machinery and vehicles. • Burning of combustible materials. • Burning of the vegetation from clearance. 	<ul style="list-style-type: none"> • Regular maintenance of vehicles and equipment to ensure there are no excessive exhaust emissions. • Burning of materials from clearance of trees, bushes and other combustible matter should be prohibited. • Ensure the machinery operating intermittently is shut down during idle periods. 					

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
Noise and Vibration	Increased noise levels that are potentially detrimental to human health.	Operating of construction machinery and equipment.	<ul style="list-style-type: none"> The contractor shall ensure that his equipment is fitted with noise muffing devices. Ensure machinery operated intermittently is shut down or throttled down during idle periods. Time restrictions of activities to the day-time working hours. Provision of PPE. 	<ul style="list-style-type: none"> Level of occupational noise. Operating conditions of vehicles and machines. Use of muffling and switching off machines during idle periods. Use of protective gear. Inspection of logbook. 	Bi-weekly	Contractor – internal monitoring. GDRB: monitoring and supervision.	Cost of PPE	GDRB: cost of noise level monitoring: 1,000 US \$ No additional environmental monitoring cost for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
Construction Camp	<ul style="list-style-type: none"> Potential soil contamination and consequent contamination of shallow aquifer. Temporary land acquisition. 	<ul style="list-style-type: none"> Storage of construction materials. Inadequate disposal of discarded and surplus materials. Inadequate disposal of construction debris. Spillage of machinery oils. Leakage of domestic sewage from septic tank. 	<ul style="list-style-type: none"> Location of the camp should be agreed with the local beneficiaries. Provision of septic tank for sewage collection and temporary storage. Regular disposal of sewage. Regular disposal of solid waste. Provision of collection tanks for collection of used machinery oils. Regular vehicle maintenance. Transporting wastes to the designated disposal sites. 	<ul style="list-style-type: none"> Disposal method of sewage and solid waste. Approach to storage of construction materials. Vehicle maintenance. Contaminants in soil as specified above. Inspection of logbook. 	Bi-weekly	Contractor – internal monitoring. GDRB: monitoring and supervision.	No additional costs	No additional environmental monitoring costs for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
Waste Management	Potential soil contamination and consequent contamination of shallow aquifer.	<p><u>Liquid waste:</u></p> <ul style="list-style-type: none"> • Sewage from construction camp. • Oils, chemical fluids, grease and de-greasing solvents. <p><u>Solid waste:</u></p> <ul style="list-style-type: none"> • Construction debris; • Discarded and surplus construction activities. 	<ul style="list-style-type: none"> • Hazardous liquid and solid waste should be stored in sealed containers. • Regular disposal of liquid and solid waste at designated sites. • Avoid placing of construction camp and construction material storage areas in close proximity to aquifer recharge areas. 	<ul style="list-style-type: none"> • Approach to temporary storage of benign construction waste prior to final disposal. • Use of designated waste disposal sites. • Inspection of logbook. 	Weekly	GDRB: monitoring and supervision.	Cost of transporting the waste.	No additional environmental monitoring costs for the Contractor.

Public Health and Safety	Increased risk of accidents.	<ul style="list-style-type: none"> • Movement of construction machinery. • Movement of transport vehicles. • Borrow pits. 	<ul style="list-style-type: none"> • Construction vehicles shall be appropriately marked and carry adequate visual and audio warning systems. • Speed limitations on the work site vehicles. • Adequate signage should be provided for motorists and pedestrians. • Designate clearly marked areas for livestock crossing. • Mark and fence the areas of active borrow pits. • Provision of barriers at construction sites. • Access control: restriction of turning movements to approved access points to and from existing highways. • Construction traffic prohibited outside specified hours. 	Presence of fencing/barriers and warning signs, and traffic speed limitations, inspection of logbook, photographic evidence.	Bi-weekly	GDRB: monitoring. Traffic Department of Duhok: supervision.	Cost of provision of warning signs and fencing.	No additional environmental monitoring costs for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
			<ul style="list-style-type: none"> • Timing restrictions for transportation of abnormal loads. • Provision of safe crossings for pedestrians and livestock 					
	Health hazards for construction workers.	<ul style="list-style-type: none"> • Operating the equipment. • Noise and dust generation from construction equipment. • Vehicles movement. 	<ul style="list-style-type: none"> • Provide training on First Aid Procedures. • Provide training on potential risks and hazards of construction. • Provide the PPE and enforce its use • Provide warning signs. 	<ul style="list-style-type: none"> • Use of PPE and presence of warning signs. • Application of the noise abatement and dust abatement measures. • Inspection of logbook. 	Weekly	Contractor – internal monitoring. GDRB: supervision.	Cost of PPE. Cost of dust abatement measures. Regular cost of vehicles and equipment maintenance.	No additional environmental monitoring costs for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
Disruption of Local Settings	Restricted access to the business entities: • Evin Gas Station; • Girsheen Gas Station; • Bawer Gas station.	• Excavation. • Traffic diversion. • Paving.	• Provide temporary exit and entry ramps. • Restore access upon completion of construction works. • Provide gaps for entry/exit in road barriers. • Advance warning of the start of works.	• Provision of temporary access points to business entities. • Provision of information in local media on scheduled works. • Warning signs.	Bi-weekly	GDRB: monitoring and supervision.	Cost of entry/exit ramps.	No additional environmental monitoring costs for the Contractor.
	Disruption of utilities.	Relocation of electric poles.	• Advanced public warning of the start of works. • Restoration of utilities provision in a shortest time possible.	Restoration of service provision.	Monthly			
	Visual and Aesthetic Impact.	• Landscape damage due to the piles of excavated materials, construction debris and discarded materials.	• All trees, native shrubbery and vegetation should be preserved and protected from damage. • Movement of crews and equipment should avoid damage to property, productive lands and known sites of	Approach to landscape restoration, visual observations, photographic evidence.	Monthly			

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
		<ul style="list-style-type: none"> • Clearance and trees and shrubs removal. 	<ul style="list-style-type: none"> historical and archeological importance. • Restoration of the landscape to the original state. • Upon completion of the works, all surplus equipment and materials to be removed and all work areas smoothed and graded to conform to the natural appearance of the surrounding landscape. 					
Heritage sites	Accidental damage to the sites of historical, cultural and religious significance.	<ul style="list-style-type: none"> • Excavations along the alignment. • Borrow pits. 	In case of chance find the cultural resources procedure should be applied.	Inspection for presence of artifacts in excavated material, inspection of logbook.	Bi-monthly	Contractor – internal monitoring. Directorate of Antiquities	N/A	No additional environmental monitoring costs for the Contractor.
Estimated costs:							2,735,334US\$	75,500 US \$ (11,500 US \$ plus 64,000 US \$ input of environmental monitor)

Table B: ESMP – Operation and Maintenance Phase

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Annual Cost of Mitigation	Annual Cost of Monitoring
Water resources	<ul style="list-style-type: none"> Flooding of drainage channels and alteration of discharge patterns. Water resources contamination. 	<ul style="list-style-type: none"> Blockage of drainage systems and culverts due to the accumulation of debris. Accidental spillage of hazardous materials. Road maintenance. 	<ul style="list-style-type: none"> Regular cleaning of roadsides;. Clearing of debris after the raining season. Emergency response for accidental spills. Regular maintenance of culverts and drainage channels. 	<ul style="list-style-type: none"> Condition of the drainage channels and culverts, photographic evidence. <p><u>Water quality parameters:</u></p> <ul style="list-style-type: none"> pH, Turbidity, Electrical Conductivity (EC), Color, Total Suspended Solids (TSS), Total Dissolved Solids (TDS), Chemical Oxygen Demand (COD), Biological Oxygen Demand (BOD), Polychlorinated Biphenyls (PCBs). 	<p><u>Surveillance:</u></p> <ul style="list-style-type: none"> Bi-weekly during the rainy season Bi-monthly during the dry season. <p><u>Water testing</u> Once per year during rainy season.</p>	GDRB	Cost of regular cleaning and maintenance.	500 US \$ for testing. No additional cost of environmental monitoring.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Annual Cost of Mitigation	Annual Cost of Monitoring
Soils	<ul style="list-style-type: none"> • Soil erosion. • Soil contamination. 	<ul style="list-style-type: none"> • Alteration of water courses due to debris accumulation. • Accidental spills of hazardous materials. • Accumulation of pollutants from traffic emissions. • Road maintenance. 	<ul style="list-style-type: none"> • Same measures to be applied as for the mitigation of impacts on water resources. • Additionally, provision of protective zone of vegetation. 	<ul style="list-style-type: none"> • Condition of the drainage channels and culverts, photographic evidence. <p><u>Soil parameters:</u> pH, temperature, organic content, poly-aromatic hydrocarbons (PAHs).</p>	<p><u>Surveillance:</u></p> <ul style="list-style-type: none"> • Bi-weekly during the rainy season • Bi-monthly during the dry season. <p><u>Soil testing</u> Once per year during rainy season.</p>	GDRB	<ul style="list-style-type: none"> • Cost of regular cleaning and maintenance. • Cost of trees. 	300 US \$ for testing No additional cost of environmental monitoring.
Biodiversity	Habitat fragmentation Incidents of road kill of wild animals.	Physical separation by road structure.	Ensure the culverts and underpasses are clear .	Condition of culverts and underpasses.	<p><u>Surveillance:</u></p> <ul style="list-style-type: none"> • Bi-weekly during the rainy season • Monthly during the dry season. 	GDRB	Cost of regular cleaning and maintenance.	No additional cost of environmental monitoring.
Ambient Air Quality	Air pollution	<ul style="list-style-type: none"> • Traffic movement. • Traffic congestion due to accidents. • Transporting of the dust generating materials. 	<ul style="list-style-type: none"> • Provision of row of trees alongside of the road alignment. • Ensure all the dust generating materials are transported by covered vehicles. • Monitor vehicles condition. 	<ul style="list-style-type: none"> • Air quality parameters: PM10, PM2.5, SO2, TSP, NOx, CO, Ozone and HC. 	<p>Once a year during dry season – air quality testing.</p> <p>Regular monitoring of traffic movement.</p>	<p>Air quality monitoring – GDRB.</p> <p>Regulating vehicles movement – traffic police.</p>	Cost of trees planting	3 000 US \$ for air quality testing.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Annual Cost of Mitigation	Annual Cost of Monitoring
Public Health and safety	Risk of accidents related to traffic.	Traffic movement	<ul style="list-style-type: none"> • Provision of a median concrete barrier, a New Jersey barrier that will run the full length of the road mainline. • Provision of street lighting to reduce accidents at night and at times of reduced visibility. • Provision of directional and warning road signage. • Provision of the underpass for livestock crossing. • Adequate delineation and demarcation of the road. • Enforcement of proper driver's behavior. • Guardrails barriers on curves and intersections. 	<ul style="list-style-type: none"> • Condition of road signage and markings. • Condition of road lighting. • Regular maintenance of pedestrian crossings and livestock underpasses. • Photographic evidence. 	Bi-weekly	GDRB Traffic Police	Cost of road maintenance.	No additional costs of environmental monitoring.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Annual Cost of Mitigation	Annual Cost of Monitoring
	<ul style="list-style-type: none"> • Soil pollution. • Traffic accidents. 	<ul style="list-style-type: none"> • Use of chemicals for landscape maintenance. • Traffic congestion at areas of highway maintenance. • Increased possibility of traffic accidents. 	<ul style="list-style-type: none"> • Effective advance information and warning signs. • Effective material handling, storage and use. • Provision of fencing in high risk areas. • Site supervision. 	<ul style="list-style-type: none"> • Condition of road signage and markings. • Adequate lighting of the road. • Handling of materials. 	Weekly during maintenance.	GDRB	Cost of fencing and warning signage.	No additional cost of environmental monitoring.
Estimated costs per annum:							None (standard maintenance costs).	11,800 US \$ (3,800 US \$ cost of tests, and 8,000 US \$ input of environmental monitor).

TABLE OF CONTENTS

EXECUTIVE SUMMARY	1
INTRODUCTION.....	1
PROJECT DESCRIPTION	1
POLICY, LEGAL AND INSTITUTIONAL FRAMEWORK.....	3
<i>Policies and Strategies:</i>	3
<i>Legal National Framework:</i>	3
<i>Institutional and Administrative Framework</i>	4
PUBLIC CONSULTATION	5
BASELINE CONDITIONS	6
<i>Physical Environment</i>	6
<i>Biological Environment</i>	7
<i>Main Land Use Patterns</i>	8
<i>Baseline Socio-Economic Conditions</i>	9
MITIGATION MEASURES.....	13
ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN (ESMP)	14
1 INTRODUCTION.....	44
1.1 ESIA OBJECTIVES AND SCOPE	44
2 PROJECT DESCRIPTION	46
2.1 GENERAL	46
2.2 PROJECT LOCATION.....	47
2.3 PROJECT BACKGROUND AND OBJECTIVES	49
2.4 MAIN ROAD ALIGNMENT FEATURES.....	53
2.5 EQUIPMENT AND MATERIALS.....	57
2.6 PROJECT FACILITIES.....	59
2.7 ESTIMATE OF THE STAFFING REQUIREMENTS.....	60
2.8 DURATION OF CONSTRUCTION ACTIVITIES	60
2.9 ANTICIPATED OPERATIONAL ACTIVITIES	61
2.10 MAIN LAND USE PATTERNS	62
2.11 ESTIMATES OF LAND ACQUISITION	63
2.12 ESTIMATE OF FINANCIAL REQUIREMENTS FOR RAP	65
3 METHODOLOGY AND APPROACH	71
3.1 LITERATURE REVIEW AND ANALYSIS	71
3.2 RECONNAISSANCE VISITS	71
3.3 ANTICIPATED IMPACTS IDENTIFICATION	72
3.4 IMPACT MITIGATION.....	73
3.5 AIR QUALITY AND NOISE MODELING.....	73
3.6 SOCIAL ASSESSMENT	74
3.7 PUBLIC HEARINGS AND CONSULTATION	74
3.8 ESMP.....	75

4	POLICY, LEGAL AND INSTITUTIONAL FRAMEWORK	76
4.1	RELEVANT STRATEGIES AND POLICIES	76
4.1.1	<i>National Development Plan 2011 -2014.....</i>	76
4.1.2	<i>Kurdistan Regional Government’s Economic Development Strategy</i>	78
4.1.3	<i>Iraqi Transport Master Plan</i>	78
4.2	LEGISLATIVE FRAMEWORK.....	78
4.2.1	<i>National Legislation.....</i>	78
4.2.2	<i>International Conventions and Treaties Signed by Iraq.....</i>	82
4.2.3	<i>ESIA Requirements in National Legislation</i>	83
4.2.4	<i>Contractual Obligations.....</i>	84
4.2.5	<i>Land Acquisition and Resettlement Provisions</i>	85
4.2.6	<i>World Bank Safeguard Operational Policies.....</i>	86
4.2.7	<i>Differences between the WB Safeguard Policies and National Legislation</i>	90
4.3	INSTITUTIONAL FRAMEWORK	93
4.4	ADMINISTRATIVE FRAMEWORK FOR LAND ACQUISITION	97
5	PUBLIC CONSULTATIONS.....	99
5.1	STAKEHOLDERS IDENTIFICATION AND ANALYSIS	99
5.2	PUBLIC AWARENESS.....	101
5.3	CONSULTATION SESSION.....	101
5.3.1	<i>Objectives of the Consultation Session</i>	102
5.3.2	<i>Consultation Session Proceedings</i>	102
5.3.3	<i>Main Results of the Consultation Session</i>	103
5.4	CONSULTATION WITH PAPs	104
5.5	MEETINGS WITH STAKEHOLDERS	104
5.6	PROJECT ACCEPTANCE.....	105
5.7	GRIEVANCE REDRESS MECHANISM	107
6	BASELINE ENVIRONMENTAL AND SOCIO-ECONOMIC CONDITIONS.....	109
6.1	PHYSICAL ENVIRONMENT	109
6.1.1	<i>Climate.....</i>	109
6.1.2	<i>Topography</i>	111
6.1.3	<i>Geology and Soils</i>	112
6.1.3.1	<i>Soils</i>	112
6.1.3.2	<i>Geology.....</i>	114
6.1.4	<i>Water resources</i>	118
6.1.4.1	<i>Groundwater Resources</i>	118
6.1.4.2	<i>Wells.....</i>	119
6.1.4.3	<i>Surface Water Resources.....</i>	120
6.1.5	<i>Ambient Air Quality</i>	121
6.1.6	<i>Noise.....</i>	122
6.2	BIOLOGICAL ENVIRONMENT.....	123
6.2.1	<i>Flora.....</i>	123
6.2.2	<i>Fauna.....</i>	125
6.2.2.1	<i>Birds.....</i>	125

6.2.2.2	Mammals	126
6.2.2.3	Amphibians and Reptiles	127
6.2.3	Seasonal Water Bodies Habitats	128
6.2.4	Status of Habitats	128
6.2.4.1	Globally, Regionally, Nationally and Local Habitats	128
6.2.4.2	Legal Status of Habitats	128
6.2.4.3	Status of Species	129
6.3	BASELINE SOCIO-ECONOMIC CONDITIONS	129
6.4	DEMOGRAPHICS	129
6.4.1	Population Numbers	129
6.4.2	Age and Gender Distribution	131
6.4.3	Household Structure	132
6.4.4	Household Income and Expenditure	133
6.4.5	Household Characteristics of PAPs	134
6.5	EMPLOYMENT	138
6.6	INFRASTRUCTURE AND UTILITIES	139
6.6.1	Waste Disposal	139
6.6.2	Utilities Supply	140
6.6.3	Health Care	140
6.6.4	Education	140
6.6.5	Cultural, Religious and Historic Facilities and Amenities	141
6.6.6	Roads and Transportation	142
6.7	MAIN LAND USE PATTERNS	144
6.8	PROJECT AREA ACTIVITY PATTERNS	145
6.8.1	Agricultural Activity Pattern	145
6.8.2	Business Activities	146
6.8.3	Anticipated Development in the Area	152
7	PROJECT IMPACT ASSESSMENT	153
7.1	IMPACTS SCOPING	153
7.2	ANTICIPATED IMPACTS OF LAND ACQUISITION	155
7.3	ANTICIPATED IMPACTS DURING CONSTRUCTION PHASE	156
7.3.1	Anticipated Impacts on Water Resources	156
7.3.2	Anticipated Impacts on Soil	157
7.3.3	Damage to Landscape	157
7.3.4	Anticipated Impacts on Traffic	158
7.3.5	Anticipated Impacts on Biodiversity	158
7.3.6	Anticipated Impacts on Air Quality	158
7.3.7	Noise Impacts	159
7.3.8	Waste Generation and Disposal	161
7.3.9	Resources Use	161
7.3.10	Construction Camp Impacts	162
7.3.11	Impacts on Cultural, Religious and Historic Heritage Sites	162
7.3.12	Public Safety	162
7.3.13	Worker's Safety	163

7.3.14	<i>Disturbance to Local Settings</i>	163
7.4	ANTICIPATED ADVERSE IMPACTS DURING OPERATIONAL AND MAINTENANCE PHASE	163
7.4.1	<i>Air Quality</i>	163
7.4.2	<i>Noise and Vibration</i>	167
7.4.3	<i>Impacts on Water Resources</i>	168
7.4.4	<i>Impacts on Biodiversity</i>	168
7.4.5	<i>Public Safety</i>	168
7.4.6	<i>Landscape Maintenance</i>	169
7.4.7	<i>Highway Maintenance</i>	169
7.5	POTENTIAL BENEFITS/POSITIVE IMPACTS	169
7.6	INDIRECT AND CUMULATIVE IMPACTS.....	170
7.6.1	<i>Indirect Impacts</i>	170
7.6.2	<i>Cumulative Impacts</i>	171
7.7	IRREVERSIBLE IMPACTS	171
7.8	ALTERNATIVES EVALUATION	172
8	MITIGATION MEASURES	175
8.1	DESIGN FEATURES	175
8.2	MITIGATION OF LAND ACQUISITION IMPACTS	175
8.3	CONSTRUCTION IMPACTS MITIGATION	176
8.3.1	<i>Damage to Landscape</i>	176
8.3.2	<i>Mitigation of Impacts on Biodiversity</i>	176
8.3.3	<i>Mitigation of Impacts on Water resources</i>	176
8.3.4	<i>Mitigation of Impacts on Soil</i>	177
8.3.5	<i>Abatement of Noise</i>	178
8.3.6	<i>Abatement of Air Pollution</i>	178
8.3.7	<i>Waste and Sewage Management</i>	178
8.3.8	<i>Mitigation of Construction Camp Impacts</i>	179
8.3.9	<i>Mitigation of Construction Materials Transporting</i>	179
8.3.10	<i>Mitigation of Impact on Cultural Resources</i>	179
8.3.11	<i>Mitigation of Traffic Impacts</i>	180
8.3.12	<i>Public Safety</i>	180
8.3.13	<i>Workers Safety</i>	181
8.3.14	<i>Mitigation of the Impacts on Local Settings</i>	181
8.4	MITIGATION OF IMPACTS DURING OPERATIONAL AND MAINTENANCE PHASE.....	181
8.4.1	<i>Mitigation of Impacts on Water Resources and Soil</i>	181
8.4.2	<i>Mitigation of Noise</i>	181
8.4.3	<i>Mitigation of Impacts on Air Quality</i>	182
8.4.4	<i>Mitigation of Impacts on Biodiversity</i>	182
8.4.5	<i>Mitigation of Landscape Maintenance Impacts</i>	183
8.4.6	<i>Mitigation of Potential Impacts on Public Safety</i>	183
8.5	RESIDUAL POST-MITIGATION IMPACTS	183
8.5.1	<i>Noise and Vibration</i>	183
8.5.2	<i>Landscape and Visual Impact</i>	184
8.5.3	<i>Ecology</i>	184

8.5.4	<i>Soils and geology</i>	184
8.5.5	<i>Water Resources</i>	184
8.5.6	<i>Air Quality</i>	184
9	ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN	185
9.1	ENVIRONMENTAL MANAGEMENT PRINCIPLES	205
9.2	ENVIRONMENTAL MONITORING STRUCTURE.....	206
9.3	MONITORING BUDGET CONSIDERATIONS	207
ANNEXES	208
ANNEX 1:	ROAD DESIGN	209
ANNEX 2:	CONSTRUCTION MATERIALS.....	213
ANNEX 3:	EPA EMISSIONS STANDARDS	228
ANNEX 4:	LIST OF ATTENDEES	233
ANNEX 5:	RATE OF CONSTRUCTION COMPLETION	238
ANNEX 6:	REFERENCES	239

TABLE OF TABLES

TABLE 0-1: DURATION OF CONSTRUCTION ACTIVITIES	2
TABLE 0-2: BUSINESS ENTITIES WITHIN SEGMENT 2 ALIGNMENT	8
Table A: ESMP - Construction Phase.....	15
Table B: ESMP - Operation and Maintenance Phase.....	30
TABLE 2-1: SUMMARY INFORMATION ON SEGMENT 2: BATIL - GERSHEEN	52
TABLE 2-2: MAIN GEOMETRIC DESIGN CRITERIA	53
TABLE 2-3: LIST AND CHARACTERISTICS OF CULVERTS	54
TABLE 2-4: MACHINERY AND EQUIPMENT.....	58
TABLE 2-5: ESTIMATE OF STAFFING REQUIREMENTS	60
TABLE 2-6: DURATION OF CONSTRUCTION ACTIVITIES	61
TABLE 2-7: TRAFFIC DATA.....	61
TABLE 2-8: COMMERCIAL AND INDUSTRIAL ESTABLISHMENTS	62
TABLE 2-9: ELECTRIC POLES TO BE RELOCATED	63
TABLE 2-10: AGRICULTURAL LAND ACQUISITION FOR SEGMENT 2: BATIL – GERSHEEN INTERCHANGE	63
TABLE 2-11: ACQUISITION OF FIXED ASSETS	64
TABLE 2-12: COMPENSATION RATES FOR CROPS.....	66
TABLE 2-13: SUMMARY OF CASH COMPENSATIONS FOR AGRICULTURAL LANDS	67
TABLE 2-14: CASH COMPENSATION FOR FIXED ASSETS.....	70
TABLE 4-1: NATIONAL LEGISLATION	78
TABLE 4-2: INTERNATIONAL CONVENTIONS AND TREATIES	82
TABLE 4-3: DIFFERENCES BETWEEN NATIONAL LEGISLATION AND WB POLICIES	90
TABLE 5-1: ANALYSIS OF STAKEHOLDERS.....	100
TABLE 5-2: SUMMARY OF MEETINGS WITH KEY STAKEHOLDERS.....	104
TABLE 5-3: PROJECT ACCEPTANCE	106
TABLE 5-4: GRM PROCEDURE.....	107
TABLE 6-1: AVAILABLE CHEMICAL CHARACTERISTICS OF WATER IN WELLS, DUHOK GOVERNORATE	120
TABLE 6-2: JORDANIAN STANDARDS FOR MAXIMUM L_{eq} (1997).....	122
TABLE 6-3: TYPICAL IRANO-TURANIAN STEPPE VEGETATION.....	123
TABLE 6-4: BIRD SPECIES RECORDED IN THE VICINITY OF THE PROJECT.....	126
TABLE 6-5: MAMMALS IN THE VICINITY OF THE PROJECT	127
TABLE 6-6: AMPHIBIANS AND REPTILES RECORDED IN THE PROJECT AREA	127
TABLE 6-7: TYPICAL RIPARIAN VEGETATION IN THE PROJECT AREA.....	128
TABLE 6-8: REGIONALLY AND GLOBALLY IMPORTANT BIRD SPECIES.....	129
TABLE 6-9: AGGREGATE POPULATION OF DUHOK GOVERNORATE (2009)	129
TABLE 6-10: AGE DISTRIBUTION IN IRAQ (ESTIMATES FOR THE YEAR 2011).....	132
TABLE 6-11: AGE DISTRIBUTION IN DUHOK DISTRICT FOR THE YEAR 2009.....	132
TABLE 6-12: HOUSEHOLD INCOME BY INCOME SOURCE (ID 000/MONTH)	133
TABLE 6-13: AVERAGE HOUSEHOLD EXPENDITURE FOR DUHOK GOVERNORATE	134
TABLE 6-14: SOCIAL PROFILE OF PAPs.....	136
TABLE 6-15: UNEMPLOYMENT RATE BY GOVERNORATE, AREA & SEX FOR THE YEAR 2008	138
TABLE 6-16: EMPLOYMENT PATTERNS OF THE HEADS OF THE HOUSEHOLD FOR DUHOK GOVERNORATE FOR 2007	138
TABLE 6-17: EDUCATIONAL LEVEL OF HOUSEHOLD MEMBERS >10 YEARS OF AGE	141
TABLE 6-18: LENGTH OF TRANSPORT NETWORK IN KURDISTAN.....	142

TABLE 6-19: DISTRIBUTION OF ROAD LENGTH ACCORDING TO LAND USE	143
TABLE 6-20: NUMBER OF PUBLIC TRANSPORT VEHICLES OPERATING IN DUHOK.....	144
TABLE 6-21: BREAKDOWN OF LAND USE UNDER BATIL AGRICULTURAL DEPARTMENT MANDATE	146
TABLE 6-22: BUSINESS ENTITIES	147
TABLE 7-1: IMPACTS SCOPING AND EVALUATION MATRIX.....	154
TABLE 7-2: EPA MAXIMUM ACCEPTABLE L_{eq} (2005)	159
TABLE 7-3: NOISE EMISSION LEVELS dB(A).....	160
TABLE 7-4: NOISE EMISSION LEVELS dB(A) OF CONSTRUCTION EQUIPMENT	160
TABLE 7-5: TRAFFIC DATA.....	164
TABLE 7-6: VEHICLE TYPES.....	164
TABLE 7-7: SCENARIO 1.....	165
TABLE 7-8: SCENARIO 2.....	166
TABLE 7-9: SCENARIO 3.....	166
TABLE 7-10: CRITERIA FOR IMPACTS EVALUATION	172
TABLE 7-11: ALTERNATIVES EVALUATION	174
TABLE 9-1: ESMP - CONSTRUCTION PHASE	186
TABLE 9-2: ESMP – OPERATIONAL AND MAINTENANCE PHASE	201
TABLE 9-3: MONITORING BUDGET FOR CONSTRUCTION PHASE.....	207
TABLE 9-4: MONITORING BUDGET PER YEAR – OPERATIONAL PHASE.....	207

TABLE OF FIGURES

FIGURE 0-1: SEGMENT 2: BATIL - GERSHEEN	1
FIGURE 2-1: IRAQ, IRAQI-KURDISTAN BORDER CROSSING POINTS.....	47
FIGURE 2-2: SIEMEL SUB-DISTRICT	48
FIGURE 2-3: SEGMENT 2: BATIL - GERSHEEN	49
FIGURE 2-4: IRAQ GDP IN BILLION US \$ 2004 -2012	50
FIGURE 2-5: IRAQI-KURDISTAN GDP (BILLION ID) 2004-2011	50
FIGURE 2-6: MOTORIZATION GROWTH RATES BY VEHICLE TYPES FOR DUHOK AND KURDISTAN (2005 -2008).....	51
FIGURE 2-7: TYPICAL CROSS SECTION.....	54
FIGURE 2-8: SMAIL AVA INTERCHANGE	54
FIGURE 2-9: SINGLE CELL BOX CULVERT – TYPICAL SECTION.....	55
FIGURE 2-10: TYPICAL LAY BY GEOMETRY	56
FIGURE 2-11: TYPICAL MEDIAN PLACED HIGHWAY LIGHTING POLE.....	57
FIGURE 4-1: HIERARCHY OF LOCAL ADMINISTRATION	98
FIGURE 5-1: STAKEHOLDER CATEGORIES	99
FIGURE 5-2: CONSULTATION SESSION	102
FIGURE 5-3: CONSULTATIONS WITH PAPs	104
FIGURE 6-1: PRECIPITATION MAP OF IRAQ.....	110
FIGURE 6-2: MEAN MONTHLY RAINFALL FOR ZAKHO WEATHER STATION (2003 – 2012).....	110
FIGURE 6-3: AVERAGE TEMPERATURES FOR ZAKHO WEATHER STATION (2003 – 2012)	111
FIGURE 6-4: TOPOGRAPHIC MAP OF IRAQ.....	112
FIGURE 6-5: SOIL MAP OF IRAQ.....	114
FIGURE 6-6: GEOLOGICAL FORMATIONS IN THE PROJECT AREA	115
FIGURE 6-7: REGIONAL STRATIGRAPHIC COLUMN.....	117
FIGURE 6-8: OVERVIEW MAP OF THE ZAKHO BASIN	119
FIGURE 6-9: SEASONAL RUN OFF VALLEYS AND THE CULVERTS IN THE VICINITY OF SEGMENT 2	121
FIGURE 6-10: ARTEMISIA HERBA-ALBA	124
FIGURE 6-11: ASPHODELUS AESTIVUS	124
FIGURE 6-12: CNICUS SPP.....	125
FIGURE 6-13: AGE PYRAMID IN IRAQ	131
FIGURE 6-14: WASTE DISPOSAL SITE	139
FIGURE 6-15: SITES OF CULTURAL IMPORTANCE IN THE VICINITY OF SEGMENT 2 ROW	142
FIGURE 6-16: MAP OF COUNTIES IN PROJECT AREA.....	145
FIGURE 6-17: EVIN OIL GAS STATION	150
FIGURE 6-18: JUNK YARDS.....	150
FIGURE 6-19: GERSHEEN COMPANY AND FUEL STATION.....	150
FIGURE 6-20: EFOR COMMERCIAL COMPANY	151
FIGURE 6-21: BAWER FUEL STATION	151
FIGURE 6-22: AVEEN TIRES AND REPAIR SHOP.....	151
FIGURE 6-23: MASTER PLAN OF DUHOK.....	152
FIGURE 9-1: ENVIRONMENTAL MONITORING DURING CONSTRUCTION PHASE.....	206

ABBREVIATIONS AND ACRONYMS

BOD	Biological Oxygen Demand
BRC	Boxed Reinforced Concrete
CC	Compensation Committee
COD	Chemical Oxygen Demand
EC	Electric Conductivity
ESIA	Environmental and Social Impact Assessment
GDRB	General Directorate of Roads and Bridges
GRM	Grievance Redress Mechanism
Ha	Hectare
ID	Iraqi Dinar
Km	Kilometer
KRG	Kurdistan Regional Government
MAWR	Ministry of Agriculture and Water Resources
MoCH	Ministry of Construction and Housing
M&E	Monitoring and Evaluation
NGO	Non-Governmental Organization
OP	Operational Procedure
PAP	Project Affected Person
PCB	Polychlorinated Biphenyls
PMT	Project Management Team
RAP	Resettlement Action Plan
SA	Social Assessment
TDS	Total Dissolved Solids
TSS	Total Suspended Solids
TSP	Total Suspended Particles
TOR	Terms of Reference
WB	World Bank

1 Introduction

This Environmental and Social Impacts Assessment (ESIA) report is prepared in accordance to the Terms of Reference for the Environmental and Social Impact Assessment (ESIA) and Resettlement Action Plan (RAP) for two segments of Road No. 2 in Kurdistan, Iraq: Batil – Gersheen (segment 2) and Gersheen – Suhaila (segment 3) issued by the Duhok General Directorate of Roads and Bridges (GDRB) and pertains to the 13 km stretch of the Segment 2: Batil – Gersheen Intersection. According to the World Bank environmental safeguards policy OP 4.01 the project is classified as **Category A**.

The MoCH/General Directorate of Roads and Bridges Duhok operates, as the core mandate for KRG, in the management, development, rehabilitation and maintenance of roads within the Duhok Governorate.

Project Management and Control, WLL, Company of Kuwait (PMC WLL¹) possessing the necessary qualifications and experience has undertaken to conduct the Environmental and Social Impact Assessment Study and Resettlement Action Plan for the Segment 2; Batil - Gersheen Intersection of Road 2 in Kurdistan. PMC's experience portfolio is represented by more than three million square-meters of built-up space and in excess of \$ 4 billion in construction volume, with projects completed within Europe and the MENA region.

1.1 ESIA Objectives and Scope

The main goal of the study is to provide the decision-makers with a comprehensive tool that will allow them to implement the expansion of the road in a way that is economically feasible and the least detrimental to the environment and population and businesses in the vicinity of the road.

The objectives of the ESIA study are:

- Identification of the baseline environmental and social conditions;
- Identification of the potential adverse impacts during the construction and operational phases of the project related to the specific project activities;
- Propose mitigation measures in order to minimize the adverse impacts identified;
- Prepare the ESMP that will allow the adequate implementation of the proposed mitigation measures.

The scope of the study encompasses the following:

- Detailed description of the project, including diagrams, maps, tables, and descriptive text based on existing information, and alternatives evaluation;

¹ WLL – With Limited Liability

- Detailed description of institutional and administrative framework relevant to the project;
- Review of applicable existing legislation including the WB operational procedures and guidelines;
- Detailed description of existing environmental and social baseline conditions based on the existing literature sources and conducted surveys;
- Results and findings of the public hearings;
- Scoping of the anticipated impacts and detailed description of the most significant adverse impacts during construction and operational phases;
- Description of positive, beneficial impacts, such as induced secondary development;
- Detailed Environmental and Social Management Plan (ESMP) for the construction and operational phases;
- Monitoring requirements and monitoring plan for the implementation of ESMP;
- Institutional arrangements for the project implementation;
- Budgetary consideration for the implementation of the ESMP.

2 Project Description

2.1 General

Segment 2: Batil – Gersheen, 13km in length is proposed to be upgraded from 1 lane both directions (single carriageway) to 3 lanes both directions (dual carriageway). Segment 2 is a part of the 65 km KRG Transport Corridor (KRG TC).

The road is divided into four segments:

- Siemel – Batil Segment (Segment 1): 15km in length. Currently under construction to upgrade it from 2 lanes both directions (double carriageway) to 3 lanes both directions (double carriageway).
- Batil – Gersheen (Segment 2): 13km in length. Currently under construction to be upgraded from 2 lanes both directions (double carriageway) to 3 lanes both directions (double carriageway)
- Gersheen – Suhaila Interchange (Segment 3): The final alignment is approved and designed. The cross section will be 3 lanes both directions (double carriageway). Approximately 23 km in length.
- Suhaila intersection – Ibrahim Al Khalil (segment 4): 14km in length. Currently under upgrading from 2 lane both directions (double carriageway) to 3 lanes both directions (double carriageway)
- Additionally, 3 Interchanges will be constructed along the road at Gersheen South, Gersheen North, and Suhaila.

The KRG TC is a vital trade link for the Kurdistan Region. At present, the existing road presents a 2-lane, winding, poorly cambered, and highly dangerous road, which originally was not designed to accommodate the current heavy road usage by vehicles of all types including significant numbers of large freight trucks. About 3,000 heavy freight trucks enter Kurdistan/Iraq daily at Ibrahim al Khalil border crossing with Turkey, transporting goods to Iraq and also transit of cargo to Gulf Region.

Traffic congestion and consequently increased time to travel combined with a high rate of accidents results in increased cost of transportation and economic losses. Improving road and safety conditions along the KRG transport corridor is thus an urgent priority for both economic and safety reasons.

2.2 Project Location

The project is located in Duhok Governorate of the Northern autonomous region of Iraq – Kurdistan. The Duhok Governorate is the most northern district of Kurdistan and borders with Turkey from the North and Syria from the West. The TC is connecting the city of Duhok with the Ibrahim Al Khalil border with Turkey.




Figure 2-1: Iraq, Iraqi-Kurdistan Border Crossing Points

The project is located in the administrative sub-district of Siemel in the jurisdiction of the Batil Municipality.



Figure 2-2: Siemel Sub-District

The map of Segment 2 highlighted in blue is presented in Figure 2-3:





Figure 2-3: Segment 2: Batil - Gersheen

2.3 Project Background and Objectives

It is estimated that the three governorates of Duhok, Erbil and Sulaymaniyah have a population of 5.2 million in 2009, which constitutes almost 14 % of the total population of Iraq. Also, the recent statistical data suggests that the population growth rate in Kurdistan is higher than the average population growth rate in Iraq.

The Region has a young and growing population, with 36% aged 0-14 years, and only 4% aged over 63. The median age in Kurdistan is just over 20 (50% of population are less than 20 years old). The Kurdistan region's economy is based on oil industry, agriculture and tourism. Due to relative peace in the region it has a more developed economy in comparison to other parts of Iraq. In 2004, the per capita income was 25% higher than in the rest of Iraq. Kurdistan is experiencing economic and construction boom thus increasing the demand for sound, efficient of transportation system.

According to the World Bank, the Gross Domestic Product (GDP) in Iraq in 2011 estimated to mount up to 115.39 billion US dollars. The GDP value of Iraq is roughly equivalent to 0.19 % of the world economy. Kurdistan Region GDP is estimated to be 23.6 billion US dollars, which constitutes 20% of Iraq GDP. The average growth rate over 2004-2012 is 33%, which is half what is reported in Iraqi-Kurdistan during 2004-2011 (77%).




Figure 2-4: Iraq GDP in Billion US \$ 2004 -2012²




Figure 2-5: Iraqi-Kurdistan GDP (billion ID) 2004-2011³

Statistics of 2007 reveal that sectors' contribution rates in 2007 were as follows: transportation, telecommunications, and storage (57%); social and personal development services (22.7%); wholesale and retail (8%); tourism and hotels services (7%); Agriculture, Forestry, Fishing and

²Source: <http://data.worldbank.org/indicator/NY.GDP.MKTP.CD> | The World Bank Group

³Source: Regional Development Strategy for Kurdistan Region 2012-2016

Hunting (5.6%); building and construction (4%); finance and insurance (1.5%); and mining and quarries (0.1%). Services (30.1%), Public services (20.6%), Agriculture (17.5%), Trade & Aviation Service (13.5%), Mining & Manufacturing (9.4%), Construction (7.6%), Banks & Insurance (1.3%).

Transport infrastructure and operations are a key element in the Kurdistan economy, contributing for about 28 % of GDP at current prices for the year 2009. International trade is one of the major foreign exchange earners through provision of overland transshipment services to the Gulf area.

The historical data for Motor vehicles (per 1,000 people) showed that it was 180 vehicles per 1,000 people in 2009 in Kurdistan compared to 76 vehicles per 1,000 people in Duhok. Private cars in Kurdistan compose the highest proportion of vehicle fleet (55%). Goods vehicles (all sort of trucks) compose one-third of vehicle fleet. The total number of registered vehicles in the region in 2009 is 430,600. The degree of motorization for passenger cars grows at average rate of 3 % in Duhok, which is slightly lower than the rate reported in the region (4% on average). Trucks are growing at higher rate in the region (10% on average), compared with relatively high rate in Duhok (7%).




Figure 2-6: Motorization Growth Rates by Vehicle Types for Duhok and Kurdistan (2005 - 2008)⁴

Despite the importance of the transport sector to the national economy, the provision of appropriate infrastructure has not kept pace with economic growth. This deficiency now constrains future

⁴Source: Kurdistan Transport Master Plan, 2010

operation and expansion of the sector and it is vital that these issues are addressed. Of particular importance are the following:

- The rapidly growing population;
- The increasing size of the labor force and increasing rate of unemployment, requiring substantial job creation;
- Constrains in the transport sector undermine trucking industry and its national and international freight operations;
- The lack of adequate road infrastructure to support growing overland import, export and transit traffic.

Taking into consideration all the above-mentioned factors the primary objectives of the TC upgrading and constructions are as follows:

- To improve the safety of travel for the users of the road;
- To establish conditions for improved performance of the trucking industry;
- To provide opportunities for continued economic growth to reduce unemployment;
- To facilitate the movement of transit traffic;
- To enhance economic efficiency and minimize economic losses through reduction of the time to travel.

The Government of Iraq through the Kurdistan Regional Government is financing the upgrading of three segments of this Transport Corridor (segments 1, 2 and 4) and has asked the World Bank to co-finance the upgrading of segment 3 from Gersheen-Suhaila Intersection which is approximately 24 kilometers in long.

The project will be implemented under the supervision of the Ministry of Construction and Housing, General Directorate of Roads and Bridges of Dohuk.

The project has been under construction since July 2014. The works completion rate as of 25.10.2015 was 41%. The breakdown of construction activities up-to-date concluded is presented in Annex 5. Table 2-1 presents summary information on the segment's lengths, financing source, and timelines.

Table 2-1: Summary Information on Segment 2: Batil - Gersheen

Segment	Length (km)	Funding Source	Estimated Cost (US\$ million)	Construction Start Date	Expected Construction End date
Batil – Gersheen North	13	KRG	27	July, 2014	April, 2017

2.4 Main Road Alignment Features

Segment 2 of TC comprises expansion of the current road alignment from 1 lane both directions (single carriageway) to 3 lanes both directions (dual carriageway). A Right of Way (ROW) for road construction of 100 m has been adopted for land acquisition and approved by GDRB.

The proposed design speed for this road is 100 km/h. The horizontal and vertical alignments of the Road are designed taking into consideration type of terrain, design speed, the proposed cross section and planned Right of Way (ROW).

All Geometric Design Standards were based on AASHTO "A Policy in Geometric Design of Highways and Streets", 2004 edition. The General Geometric Design Criteria are summarized in table 2-2.

Table 2-2: Main Geometric Design Criteria

Feature	Design Criteria
Design speed (V)	V= 100 km /h
Minimum Radius (R)	R = 440 m
Maximum Super-elevation	$e_{\max} = 6.0\%$
Maximum Grade	6.0% mountainous terrain (critical length =220 m) 4.0% rolling terrain (critical length =350 m)
Minimum Grade	0.30%
Lane width (m)	3.75 m
Shoulder Width (m)	Right 3.0 m and Left 1.2m(taken from median width)
Median Width (m)	3.0 m

The proposed Road is a dual carriageway highway consisting of three-lanes each direction. The proposed typical cross section is presented in the Figure 2-7.



The road is located in generally open flat agricultural terrain with little physical constraint. Design geometry is of a high standard comprising flat gradients and large radius horizontal curves. Embankment heights are governed by drainage requirements and generally 1.5 – 2.5 m. Service/diversion roads are provided along the first third of the road length.

Plan view of the Smail AVA Interchange. The drawing shows a horizontal alignment with stationing from 19+400 to 20+300. Key features include:

- Match Lines:**
 - Left Match Line: Station 19+400.00, labeled "MATCH LINE - 19+400.00" and "PREVIOUS SHEET NUMBER: 11".
 - Right Match Line: Station 20+300.00, labeled "MATCH LINE - 20+300.00" and "NEXT SHEET NUMBER: 12".
- Interchange Structure:** Labeled "SMAIL AVA INTERCHANGE". It shows a main horizontal alignment with two side roads crossing it at right angles.
- Stationing and Elevation:**
 - Stationing is marked every 20 meters from 19+400 to 20+300.
 - Elevations are provided at specific stations: 19+470.0 (19.47), 19+500.0 (19.50), 19+530.0 (19.53), 19+560.0 (19.56), 19+590.0 (19.59), 19+620.0 (19.62), 19+650.0 (19.65), 19+680.0 (19.68), 19+710.0 (19.71), 19+740.0 (19.74), 19+770.0 (19.77), 19+800.0 (19.80), 19+830.0 (19.83), 19+860.0 (19.86), 19+890.0 (19.89), 19+920.0 (19.92), 19+950.0 (19.95), 19+980.0 (19.98), 20+010.0 (20.01), 20+040.0 (20.04), 20+070.0 (20.07), 20+100.0 (20.10), 20+130.0 (20.13), 20+160.0 (20.16), 20+190.0 (20.19), 20+220.0 (20.22), 20+250.0 (20.25), 20+280.0 (20.28), 20+310.0 (20.31).
- Slope Information:**
 - Vertical curve segments are labeled "B.C. (1*1) m" and "Min Slope 1%".
 - These segments are located at stations 19+470.0, 19+500.0, 19+530.0, 19+560.0, 19+590.0, 19+620.0, 19+650.0, 19+680.0, 19+710.0, 19+740.0, 19+770.0, 19+800.0, 19+830.0, 19+860.0, 19+890.0, 19+920.0, 19+950.0, 19+980.0, 20+010.0, 20+040.0, 20+070.0, 20+100.0, 20+130.0, 20+160.0, 20+190.0, 20+220.0, 20+250.0, 20+280.0, and 20+310.0.
- Other Labels:**
 - "19+400.00" and "19+470.0" are labeled on the left side of the drawing.
 - "20+300.00" and "20+280.0" are labeled on the right side of the drawing.

Beyond the interchange the three-lane dual carriage way runs on relatively low embankment within the 100 m of the ROW over open unconstrained agricultural land with localized shallow cut sections between. Sixteen box culverts will be provided at low points generally defined by shallow wadis (see Table 2-3 and Figure 2-9).

Table 2-3: List and Characteristics of Culverts

No. of culvert	Location of culvert	Size of culvert [m]	Length of culvert [m]
1	15+320	1.5x1.5	62
2	16+070	2 (1.5x1.5)	51
3	17+080	2 (1.5x1.5)	150
4	17+840	3x3	75
5	19+240	1.5x1.5	58
6	20+270	1.5x1.5	59
7	20+650	1.5x1.5	45
8	21+140	2x3	64
9	22+200	2 (1.5x1.5)	68
10	23+270	2(1.5x1.5)	64
11	23+900	2 (1.5x1.5)	82
12	25+040	1x1	48
13	25+960	1x1	45
14	26+300	1x1	51
15	27+110	1x1	46
16	27+790	3x2	61




Figure 2-9: Single Cell Box Culvert – Typical Section

Three road box underpasses of 3x3m size for livestock and wild animals crossing are provided as follows:

1. Location: 15+260, length: 90m;

2. Location: 17+740, length: 81m;
3. Location: 22+240, length: 48m.

Truck lay-bys are proposed on each direction of the road. Lay-bys are important for drivers needing to stop for a short time to rest or for maintenance purposes.

The proposed lay-bys have a 6.0m width and 100m length enough for more than 4 large trucks (see Figure 2-10). Tapers and auxiliary lanes (acceleration and deceleration) at both ends were provided to ensure the smoothness and safety for merging and diverging traffic in addition to proper marking and signs.




Figure 2-10: Typical Lay By Geometry

The road will be furnished with the road signs (directional, warning, etc.), guardrail, Jersey barriers, and road markings. The details on these items are presented in Annex 2.

The road will be furnished with the street lighting. The suggested design is that the lighting poles will be placed in the median, protected by the Jersey barriers (see Figure 2-11).



Figure 2-11: Typical Median Placed Highway Lighting Pole

Two temporary detour roads within the ROW are proposed to facilitate traffic diversion and construction machinery movement during construction stage. The detour roads will be decommissioned at the end of the construction phase:

- from station 22+100 to station 22+700;
- from station 17+000 to station 18+000.

The service road consists of two lane carriageways with verges on each side and vertical alignment that closely follows the existing finished levels of the adjacent land parcels. The design speed is 60 km/h, exceptionally 40 km/h in difficult topography.

2.5 Equipment and Materials

Equipment can be divided into machinery for six major construction purposes: clearing, earthmoving, shaping, and compacting the natural formation; installing underground drainage; producing and handling the road-making aggregate; manufacturing asphalt and concrete; placing and compacting the pavement layers; and constructing bridges and culverts.

For clearing vegetation and undesirable materials from the roadway, the bulldozer is employed. The construction of rock cuts is commonly done with shovels, draglines, and mobile drills. Shaping the formation and moving earth from cuttings to embankments is accomplished with bulldozers, graders, hauling scrapers, elevating graders, loaders, and large dump trucks. The material is placed in layers, brought to the proper moisture content, and compacted to the required density. Compaction is accomplished with tamping, sheep-foot, grid, steel-wheeled, vibrating, and pneumatic-tired rollers. Backhoes, back actors, and trenchers are used for drainage work.

In order to avoid high haulage costs, the materials used for base course construction are preferably located near the construction site; it is not feasible to use expensive materials for long lengths of road construction. The excavation process is the same as for rock cuts, although rippers may be used for obtaining lower-grade material. Crushers, screens, and washers produce stone of the right size, shape, and cleanliness.

The placement of paving material involves a paving machine for distributing the aggregate, asphalt, or concrete uniformly and to the required thickness, shape, and width. The paving machine can slip-form the edges of the course. As it progresses down the road, it applies some preliminary compaction and also screeds and finishes the pavement surface.

In producing a spray-and-chip seal surface (or a bituminous surface treatment), a porous existing surface is covered with a film of hot, fluid bitumen that is sprayed in sufficient quantity to fill voids, cracks, and crevices without leaving excess bitumen on the surface. The surface is then sprayed with more viscous hot bitumen, which is immediately covered with a layer of uniform-size stone chips spread from a dump truck. The roadway is then rolled to seat the stone in the sticky bitumen, and excess stone is later cleared by a rotary broom.

The typical equipment and machinery is presented in Table 2-4.

Table 2-4: Machinery and Equipment

Activity	Machinery and Equipment
Clearing	Bulldozer
	Front End Loader
	Jack Hammer
	Crane with Ball
Excavation & Earth Moving	Bulldozer
	Backhoe
	Front End Loader
	Dump truck
	Jack Hammer
	Scraper
Structure Construction	Crane

Activity	Machinery and Equipment
	Welding Generator
	Concrete Mixer
	Concrete Pump
	Concrete Vibrator
	Air Compressor
	Pneumatic Tools
	Bulldozer
	Cement and Dump Trucks
	Front End Loader
	Dump truck
	Paver
Grading and Compacting	Grader
Landscaping & Clean-Up	Bulldozer

Materials used for road construction include soils (possible re-use of cut materials), aggregates, Portland cement mixes, asphalt mixes, geo-synthetics, composites, and metals including steel and aluminum, wood materials. The description and materials requirements are presented in the Annex 3. Significant water consumption is anticipated for the project for the following:

- Concrete batching plant with capacity of 400 m³/day requires around 100 m³/day of water;
- Compaction of fill – approximately 22 m³/m of the new road;
- Spraying for prevention of dust generation;
- Human consumption.

Water is available from groundwater wells located outside of the study area. The aquifer has high water capacity.

2.6 Project Facilities

For the execution of the works on Segment 2 the following types of construction camps are likely to be required:

- A Main Camp, the operational center, with prefabricated offices and parking areas for administration and technical staff. This will also include areas for materials testing and storage, and equipment cleaning and maintenance. The need for residential accommodation is likely to be relatively minor;
- Construction Yards, comprising rock crushing and screening plant, pre-cast concrete yards, asphalt and concrete batching plants;
- Satellite Camps, additional area for equipment cleaning and materials storage;

- Temporary Camps may be needed at specific sites such as bridge crossings, where there will be a short-term concentration of equipment, materials and labor.

2.7 Estimate of the Staffing Requirements

The estimate of the staffing requirements is presented in Table 2-5.

Table 2-5: Estimate of Staffing Requirements

Type	Job Title	Number
Administrative Staff	Secretary	2
	IT support	2
	Serving personnel	2
	Security personnel	3
	Parking attendants	3
	Logistics Coordinator	2
	Warehouse/storage coordinator	4
	HR officer	1
	Procurement officer	1
Technical Staff	General Manager/Team Leader	1
	Senior Road Engineer	1
	Materials Engineer	1
	Road Engineer	2
	Structural Engineer	1
	Geo-technical Engineer	1
	Drainage Engineer	1
	Pavement Engineer	1
	Quantity Surveyor	1
	HS&E specialist	2
	Environmental and Social specialist	1
	Quality Assurance Engineer	1
Construction Crew	Machinery and equipment operators	25
	Unskilled labor	30
Total		89

2.8 Duration of Construction Activities

The summary of duration of construction activities is presented in Table 2-6.

Table 2-6: Duration of Construction Activities

#	Activity	Duration (man days)
1	Construction of temporary detour routes: <ul style="list-style-type: none"> from station 22+100 to station 22+700 from station 17+000 to station 18+000 from station 22+100 to station 22+700 from station 22+700 to station 28+100 	
1.1	Clearance and surveying	15
1.2	Cut and fill works	15
1.3	Curbstone works	22
1.4	Aggregate sub-layer	36
1.5	Paving	17
1.6	Traffic signs installation	5
1.7	Setting up construction camp	10
2	Main road works	
2.1	Clearance	55
2.2	Cut/excavation	75
2.3	Fill operations	85
2.4	Curbstone works	70
2.5	Base sub-layer	80
2.6	Base layer	50
2.7	Tiling	50
2.8	Bridges and culverts works	170
2.9	Utilities installation	80
2.10	Installing reinforced concrete structures	130
2.11	Installing road lighting equipment	90
2.12	Paving	60
2.13	Installation of guardrails and barriers	60
2.14	Traffic signs installation and road markings	30

2.9 Anticipated Operational Activities

The main operational activity of the new road will be the traffic movement. The traffic study conducted by GDRB has provided the estimates of the current traffic flow and composition on Segment 2 and projections, which summarized in Table 2-7.

Table 2-7: Traffic Data

Type	Articulated	Trucks	Buses	Medium goods	Cars
------	-------------	--------	-------	--------------	------

	trucks			trucks	
Number per day (2013)	1117	1683	31	852	6017
Number per day (2015)	1208	1820	34	939	6634
Number per day (2035)	2647	3989	91	2492	17601

Other activities during the operational phase are estimated as following:

- Landscape maintenance;
- Road structure maintenance including maintenance of pavement surface, drainage systems, etc.
- Auxiliary road structures maintenance such as street lighting, signs, markings

2.10 Main Land Use Patterns

The prevalent land use in the project area is agricultural, composed of the rain-fed cultivation of cereals and livestock grazing.

The rain-fed agriculture is prevalent, with the wheat and barley as main cultivated crops. The rain-fed farming systems are essentially as following: continuous wheat with fertilizer applications juxtaposed with a barley/fallow rotation which usually does not include fertilizer use, but may incorporate chickpeas one year in three or four.

It must be noted that there are no certain areas designated for livestock grazing, but rather customary boundaries between local communities are respected. Customary the herds of about 500 sheep and goats are wondering around the area on ad hoc basis.

There are no residential settlements in the project area. No cultural, religious and historic sites will be affected by the project. The map showing the location of such sites and the 1100 m corridor is presented in the Chapter 4. Industrial and commercial activities in the project area are presented in Table 2-8.

Table 2-8: Commercial and Industrial Establishments

#	Name of Business Entity	Location Coordinates
1	Evin Gas Oil Station	E: 42,652088 N: 36,978423
2	Junk Yard	E: 42,651081N: 36,979785
3	Girsheen Company and Fuel Station	E: 42,640558 N: 36,994753
4	Efor Company	E: 42,645086N: 36,957745
5	Bawer Fuel Station	E: 42,645028N: 36,967908
6	Aveen Tires and Repair Shop	E: 42,651098N: 36,979775
7	Azra Company	E: 42,652551N: 36,977560
8	Arcelik Company	E: 42,654433N: 36,974378

In addition to the business entities in the project area, there are a number of fixed assets that are likely to be affected by the ROW and are subject to land acquisition:

- Fence at the abandoned private ceremonial building, commonly known as “Marriage Hall”;
- Fences around uncultivated land;
- Sign post of the Bawer Fuel Station;
- Sign post of Effor Company;
- Sign post of Evil Gas Station.

Additionally, the number of electrical posts belonging to the Ministry of Electricity will require relocation, as presented in Table 2-9.

Table 2-9: Electric Poles to be relocated

#	Description	Location
1	Electric Pole	E: 42,645020 N: 36,987926
2	Electric Pole	E: 42,652088 N: 36,978423
3	Electric Pole	E: 42,645086N: 36,957745

The photographic survey of the structures, fixed assets, and utilities is presented in Annex 3.

2.11 Estimates of Land Acquisition

In total of 568,698 m² of land are to be acquired permanently for the project, 565,615m² are used cultivation and grazing activities. Additionally, 1,897.5 m of fences including the block reinforced concrete will be acquired, 167.5 m² pertaining to the complete business relocation and 2,950 m³ of the traditional storage facility.

The permanent land to be acquired includes all land needed for the right of way, servicing areas, underpass and culverts.

The detailed breakdown of the land acquisition is presented in Table 2-10 and Table 2-11.

Table 2-10: Agricultural Land Acquisition for Segment 2: Batil – Gersheen Interchange

#	District	Land Plot No.	Land Parcel No.	Total Land Area (m ²)	Land to be Acquired		PAP
					(m ²)	%	
1	Batil	68	1/5	1,205,435	5,750	0.47	PAP_001
2	Batil	68	1/5	1,205,435	4,500	0.37	PAP_002
3	Batil	68	1/5	1,205,435	5,500	0.45	PAP_003
4	Batil	68	1/5	1,205,435	7,000	0.58	PAP_004
5	Batil	68	1/5	1,205,435	4,500	0.37	PAP_005
6	Batil	68	1/5	1,205,435	17,500	1.45	PAP_006

#	District	Land Plot No.	Land Parcel No.	Total Land Area (m ²)	Land to be Acquired		PAP
					(m ²)	%	
7	Batil	68	1/5	1,205,435	20,000	1.6	PAP_007
8	Batil	68	1/5	1,205,435	29,000	2.4	PAP_008
9	Batil	68	1/5	1,205,435	2,500	0.2	PAP_009
10	Batil	68	1/5	1,205,435	6,250	0.5	PAP_010
11	Batil	68	1/5	1,205,435	21,400	1.77	PAP_011
12	Batil	68	1/5	1,205,435	34,500	2.86	PAP_012
13	Batil	68	1/2	6,550,000	27,600	0.42	PAP_013
14	Batil	68	1/2	6,550,000	12,500	0.19	PAP_014
15	Smail Ava	52	6	5,167,500	9,500	0.18	PAP_015
16	Smail Ava	52	6	5,167,500	2,250	0.043	PAP_016
17	Smail Ava	52	6	5,167,500	2,250	0.043	PAP_017
18	Smail Ava	52	6	5,167,500	1,750	0.033	PAP_018
19	Smail Ava	52	6	5,167,500	6,000	0.11	PAP_019
20	Smail Ava	52	6	5,167,500	9,500	0.18	PAP_020
21	Kr Othman	51	1/1	637,500	18,500	2.9	PAP_021
22	Kr Othman	51	1/15	3,015,000	5,200	0.17	PAP_022
23	Kr Othman	51	1/13	360,000	18,600	5.16	PAP_023
24	Kr Othman	51	1/13	360,000	3,700	1.03	PAP_024
25	Kr Othman	51	1/13	360,000	6,700	1.86	PAP_025
26	Kr Othman	51	1/16	43,269.23	5,265	12	PAP_026
27	Kr Othman	51	1/16	86,297.68	4,400	5.09	PAP_027
28	Gersheen	73	1/3	1,559,020	210,000	13.47	PAP_028
29	Gersheen	73	1/3	1,559,020	14,000	0.89	PAP_029
30	Turkshan	74	1/4	463,780	52,500	11.32	PAP_030
					568,615		

According to the land acquisition requirements of the proposed expansion of the road, six businesses will be subject of the fixed assets acquisition, as presented in Table 2-11.

Table 2-11: Acquisition of Fixed Assets

#	District/County Name	Land Plot No.	Land Parcel No.	Total Land Area (m ²)	Land to be Acquired	Unit	Description	PAP
1	Batil	68	1/2	6,550,000	425	m	BRC/fence	PAP_014

#	District/County Name	Land Plot No.	Land Parcel No.	Total Land Area (m ²)	Land to be Acquired	Unit	Description	PAP
2	Kr Othman	51	1/16	86,297.68	262.5	m	Fence	PAP_027
3	Kr Othman	51	1/16	14,9038.45	425	m	BRC/fence	PAP_031
4	Kr Othman	51	1/13	360,000	335	m	BRC/fence	PAP_025
5	Kr Othman	51	1/13	360,000	450	m	BRC/fence	PAP_032
					1,897.5	m	Total length of fences	
					2,950	m ³	Traditional storage made of rocks	
6	Kr Othman	51	1/16	67,500	84.5	m ²	Concrete and block ramp	PAP_033
					63	m ²	Concrete pavement around the building	
					20	m ²	Concrete structure with corrugated sheet roof	
					167.5	m ²	Total area of Aven tire shop	

Business entities in the vicinity of Segment 2 operate on state-owned land with a formal lease agreement except for the Aven Tire Shop. The owners received cash compensation for the land acquired, any fixed assets on the acquired parcel of land and additional financial compensation as transitional assistance for the income restoration.

The Aven Tire Shop will be required to relocate, and the land acquired is 100 % of the total area (167.5 m²), with the building to be demolished.

Main crops in the area are cereals (barley and wheat) with production rate of 500 kg/Dunum⁵ and legumes (chickpeas and lentils) with production rate 560 – 590 kg/ha⁶. Based on the above-mentioned factors the estimate of the crop losses is about 138.1 tons⁷ of crops.

There are number of trees previously planted along the road sides, mainly pine and eucalyptus trees. Estimate of the exact number of trees was not possible, since the plant nursery company started removal of them for further replanting upon completion of the road construction according to the agreement with MoCH.

2.12 Estimate of Financial Requirements for RAP

According to census survey results, a total of 33 households (three households have both agricultural and fix assets) are likely to be affected by land acquisition, in total 412 persons will be affected, of which 50 are females and 316 are children under 18 years of age. All of the

⁵ Iraqi Dunum equals 2,500 m²

⁶<http://www.fao.org/docrep/006/y9870e/y9870e07.htm>

⁷ Metric tons

households depend on agricultural activities for their income, 67.7 % earn their livelihood entirely through agriculture.

It must be noted that at the time of the preparation of this report, the Compensation Committee has finalized land, property and assets valuation and already finalized the cash compensation amounts for each individual PAP (Table 2-13 and Table 2-14).

The compensation rates for crops values are according to the Ministers Decree No. 360 of 2008 based on specification of the type of crops, their financial value and quantities.

Table 2-12: Compensation Rates for Crops

Type of Crop	Production Rate (kg/Dunum)	Compensation Rate (ID/ton)
Wheat	500	800,000
Barley	700	800,000
Chickpeas	560	800,000
Lentils	600	800,000

Due to the fact that the land acquisition process have started after the standing crops on the areas subject to acquisition were collected and sold, the PAPs have received compensation for the crops potentially to be planted the season after the land acquisition. In fact, the cash compensations received by PAPs for crops are actually the transitional assistance for loss of income. The PAPs are not entitled to compensation for land since they have no formal legal title deeds to land they are using. However, they cannot be considered encroachers due to the fact that a lot of documents were burned during the uprising of 1991. The state recognizes them as land users *de facto*.

The compensation for the fixed assets and structures was based on the physical presence of the assets and evaluated according to the market price.

The total cash compensation offered to PAPs is 250,220,000 IDs equivalent to 204,261 US \$. The tables of cash compensation paid to each individual PAP are presented in Table 2-13 and Table 2-14.

Table 2-13: Summary of Cash Compensations for Agricultural Lands

#	District	Land Plot No.	Land Parcel No.	Total Land Area (m ²)	Land to be Acquired		Crop	Compensation rate (ID/ton)	Crop Quantity (kg)	PAP	Cash Compensation (ID)
					(m ²)	%					
1	Batil	68	1/5	1,205,435	5,750	0.47	wheat	800,000	1,150	PAP_001	920,000
2	Batil	68	1/5	1,205,435	4,500	0.37	wheat	800,000	900	PAP_002	720,000
3	Batil	68	1/5	1,205,435	5,500	0.45	wheat	800,000	1,100	PAP_003	880,000
4	Batil	68	1/5	1,205,435	7,000	0.58	wheat	800,000	1,400	PAP_004	1,120,000
5	Batil	68	1/5	1,205,435	4,500	0.37	wheat	800,000	900	PAP_005	720,000
6	Batil	68	1/5	1,205,435	17,500	1.45	wheat	800,000	3,500	PAP_006	2,800,000
7	Batil	68	1/5	1,205,435	20,000	1.6	wheat	800,000	4,000	PAP_007	3,200,000
8	Batil	68	1/5	1,205,435	29,000	2.4	wheat	800,000	5,800	PAP_008	4,640,000
9	Batil	68	1/5	1,205,435	2,500	0.2	wheat	800,000	500	PAP_009	400,000
10	Batil	68	1/5	1,205,435	6,250	0.5	wheat	800,000	1,250	PAP_010	1,000,000
11	Batil	68	1/5	1,205,435	21,400	1.77	wheat	800,000	4,300	PAP_011	3,440,000
12	Batil	68	1/5	1,205,435	34,500	2.86	wheat	800,000	6,900	PAP_012	5,520,000
13	Batil	68	1/2	6,550,000	27,600	0.42	wheat	800,000	5,520	PAP_013	4,416,000

#	District	Land Plot No.	Land Parcel No.	Total Land Area (m ²)	Land to be Acquired		Crop	Compensation rate (ID/ton)	Crop Quantity (kg)	PAP	Cash Compensation (ID)
					(m ²)	%					
14	Batil	68	1/2	6,550,000	12,500	0.19	wheat	800,000	25,000	PAP_014	20,000,000
15	Smail Ava	52	6	5,167,500	9,500	0.18	wheat	800,000	1,900	PAP_015	1,520,000
16	Smail Ava	52	6	5,167,500	2,250	0.043	wheat	800,000	450	PAP_016	360,000
17	Smail Ava	52	6	5,167,500	2,250	0.043	wheat	800,000	450	PAP_017	360,000
18	Smail Ava	52	6	5,167,500	1,750	0.033	wheat	800,000	350	PAP_018	280,000
19	Smail Ava	52	6	5,167,500	6,000	0.11	wheat	800,000	1,200	PAP_019	960,000
20	Smail Ava	52	6	5,167,500	9,500	0.18	wheat	800,000	1,900	PAP_020	1,520,000
21	Kr Othman	51	1/1	637,500	18,500	2.9	wheat	800,000	3,700	PAP_021	2,960,000
22	Kr Othman	51	1/15	3,015,000	5,200	0.17	wheat	800,000	1,040	PAP_022	835,000

#	District	Land Plot No.	Land Parcel No.	Total Land Area (m ²)	Land to be Acquired		Crop	Compensation rate (ID/ton)	Crop Quantity (kg)	PAP	Cash Compensation (ID)
					(m ²)	%					
23	Kr Othman	51	1/13	360,000	18,600	5.16	wheat	800,000	3,750	PAP_023	2,976,000
24	Kr Othman	51	1/13	360,000	3,700	1.03	wheat	800,000	740	PAP_024	592,000
25	Kr Othman	51	1/13	360,000	6,700	1.86	wheat	800,000	1,390	PAP_025	1,072,000
26	Kr Othman	51	1/16	43,269.23	5,265	12	wheat	800,000	2,830	PAP_026	2,665,000
27	Kr Othman	51	1/16	86,297.68	4,400	5.09	wheat	800,000	880	PAP_027	704,000
28	Gersheen	73	1/3	1,559,020	21,000	13.47	wheat	800,000	42,000	PAP_028	33,600,000
29	Gersheen	73	1/3	1,559,020	14,000	0.89	wheat	800,000	2,800	PAP_029	2,240,000
30	Turkshan	74	1/4	463,780	52,500	11.32	wheat	800,000	10,500	PAP_030	8,400,000
Total					568,615				138,100		110,820,000

Table 2-14: Cash Compensation for Fixed Assets

#	District/County Name	Land Plot No.	Land Parcel No.	Total Land Area (m ²)	Asset to be Acquired	Unit	Unit Rate	Description	Name of Land User	Cash Compensation (ID)
1	Batil	68	1/2	6,550,000	425	m	40,000 ID/m	BRC/fence	PAP_014	17,000,000
2	Kr Othman	51	1/16	86,297.68	262.5	m	50,000 ID/m	Fence	PAP_027	13,125,000
3	Kr Othman	51	1/16	14,9038.45	425	m	40,000 ID/m	BRC/fence	PAP_031	17,000,000
4	Kr Othman	51	1/13	360,000	450	m	40,000 ID/m	BRC/fence	PAP_032	62,250,000
					1,897.5	m		Total fences		
					2,950	m ³	15,000 ID/m ³	Traditional storage made of rocks		
5	Kr Othman	51	1/13	360,000	335	m	40,000 ID/m	BRC/fence	PAP_025	17,000,000
6	Kr Othman	51	1/16	67,500	84.5	m ²	50,000 ID/m ²	Concrete and block ramp	PAP_033	13,025,000
					63	m ²	100,000 ID/m ²	Concrete pavement around the building		
					20	m ²	150,000 ID/m ²	Concrete structure with corrugated sheet roof		
					167.5	m ²				
Total										139,400,000

3 Methodology and Approach

The study is executed in full compliance with the provided ToR and the World Bank Safeguard Guidelines. Chapters below provide the overview of the methodology applied in project execution.

3.1 Literature Review and Analysis

The initial stage of the project comprises information collection. The information collection involves the desk study review and analysis of the available information, such as previous studies, engineering design, Internet and literature sources as such Framework Study prepared by the Arabtech Jardaneh Company.

Information collection also includes the series of interviews with the relevant stakeholders, such as representatives of MoCH/General Directorate of Roads and Bridges Dohuk, and representatives of other authorities and local communities.

The literature review encompasses the following:

- Engineering design for the Segment 2 and description of the main features of the project such as geometrical design, materials, schedule of works;
- Traffic study, including current traffic conditions and projections for the life time of the project comprising traffic volume and composition;
- Available land use maps and descriptions;
- Policies, legislative, institutional and administrative framework;
- Applicable World Bank Operational procedures and Policies;
- Available studies pertaining to the physical environment in the project area, including climatic conditions, geology and soils, water resources, hydro-geological modeling, air quality and noise;
- Available studies related to the biological environment, such as eco-systems, flora and fauna, migratory birds, protected areas, sensitive environmental receptors;
- Reports on the previous public consultations in particular the results of the Consultation Session conducted by the Arabtech Jardaneh Company at the time of the preparation of the framework study;
- Statistical data relevant to the baseline socio-economic conditions.

3.2 Reconnaissance Visits

In order to visualize and register the existing conditions the number of the reconnaissance field visits was conducted to the project area. The field visits were conducted on 15.11.2013, 17.12.20013 – 29.12.2013, and 16.01.2014 – 15.02.2014. During the field visits the following issues were observed and recorded:

- All existing settlements, structures, fixed assets, business entities along the project alignment, pinpointed by GIS coordinates and supplemented with the photographic survey;
- Land use pattern in the area;
- Existing physical and biological resources in the project area, especially presence of the micro-habitats and sensitive environmental receptors, such as riparian habitats along the existing seasonal water courses;
- Existing cultural, religious and historical sites in the vicinity of the 1 km corridor along the road alignment as specified in the TOR.
- Interviews and social profiling of PAPs.

The field visits were conducted in coordination with the PMT team members at GDRB.

3.3 Anticipated Impacts Identification

Impacts evaluation constitutes prediction of environmental and ecological changes relative to baseline taking into account the nature, magnitude and seriousness of the anticipated impacts:

- Identifying potential impacts which may be harmful or beneficial to the environment;
- Identifying receivers, habitats or resources which are vulnerable to change;
- Defining the project/environment interactions;
- Examining the chain of events linking cause with effect;
- Describing and predicting the reasonable case scenario and/or the worst case scenario;
- Predicting the likely nature, extent and magnitude of the anticipated changes and effects such that an evaluation, in quantitative terms as far as possible.

It must be noted that the impacts have different level of significance during construction and operational phases.

The impacts significance evaluation is performed using the Leopold Matrix (LM)⁸. This matrix has: on the horizontal axis, the actions that cause environmental impact, and on the vertical axis, the existing environmental conditions that may be affected by those actions. This provides a format for comprehensive review of the interactions between proposed anthropogenic actions and environmental factors.

⁸Leopold et al., 1971

3.4 Impact Mitigation

The methodologies proposed for mitigation give priority to avoidance of impacts. The proposed mitigation measures are evaluated for their feasibility of implementation. The assessment methods are:

- Identify and evaluate mitigation measures in order to avoid, reduce or remedy the impacts;
- Assess the effectiveness of mitigation measures; and
- Define the residual environmental impacts, which are the net impacts remaining with the mitigation measures in place.

3.5 Air Quality and Noise Modeling

For the evaluation of the potential impacts on air quality the MOVES modeling was used. EPA's Office of Transportation and Air Quality (OTAQ) has developed the Motor Vehicle Emission Simulator (MOVES). This new emission modeling system estimates emissions for mobile sources covering a broad range of pollutants and allows multiple scale analysis. MOVES estimates emissions from cars, trucks & motorcycles.

The following type of data is needed for the model:

- 1- Design specifications
- 2- Traffic data (provided in the engineering design study)
- 3- Fuel type
- 4- Components of the vehicles fleet
- 5- Age and distribution of the vehicles age.
- 6- Climate data

Equipment noise emissions at a reference distance of 50 feet will be used for the evaluation of noise levels on the job site. Construction noise prediction technique includes the following steps:

- Identification of areas (including limits) with the potential to be impacted by construction noise;
- Identification of construction operations and their potential to create noise impacts;
- Determining time periods during which specific operations will occur;
- Estimation of duration and frequency of each significant noise-producing event;
- Simple quantitative analysis using manual analysis techniques
- Determine components of each construction operation in terms of equipment type and source noise level.

Since noise level measurements were not available, and in order to estimate the expected noise levels during the operation of the road, a noise prediction model was used. The input of the model included Duhok climatic data as well as the projected traffic data. The traffic data included vehicle classification, speed of vehicles, as well as pavement surface conditions and characteristics.

3.6 Social Assessment

In order to estimate the overall permanent and temporary land acquisition and resettlement impacts a detailed survey was conducted by the project team during December 2013 – February 2014. The census survey consisted of several stages:

- Reconnaissance field visits to the project area, assisted by the Senior Land Surveyor of GDRB, Eng. Abdullah Cimo, in order to register the land use patterns, existing business entities along the road alignment, main crops cultivated in the area, pastoral activities pattern, infrastructure, amount of land that is the subject to permanent acquisition, cultural/religious/historic sites, any existing dwellings and physical assets.
- In order to acquire the proposed compensation rates for different types of land acquisition, and in order to acquire the information on the possibility of the in lieu compensation, the interviews with the governmental officials were carried out, namely the representatives of the Compensation Committee.
- Consultations with the local administration on the level of the sub-district of Siemel administration and the heads of administration of the villages, which are the permanent residence of PAPs.
- Socio-economic survey of PAPs was conducted through the series of the structured interviews with the heads of the households with the help of the Kurdish translator. The interviewer registered the information due to the fact that the prevailing number of the household are illiterate or have a very low level of education and therefore are not capable of filling the questionnaire.
- The census survey covered 100% of the households affected and provided inventory of 100 of assets affected by the road ROW in the project area. The results of the inventory have been confirmed by each affected household. The key purpose of the census survey was to identify and enumerate affected people, create an inventory of affected land and other assets, and to establish key data for many other aspects of resettlement planning.

3.7 Public Hearings and Consultation

Consultation Session is an essential part of the ESIA process that includes all stakeholders potentially affected by the project, whether from the public or private sectors. The main purpose of the session is to present the proposed project and to solicit feedback concerning environmental impacts.

In addition to the Consultation Session, meetings and interviews were conducted with the PAPs, which served the dual purposes: registering the issues of concern and conducting a comprehensive census survey.

Further, the results of the consultation session were taken into consideration in the process of the impacts significance evaluation.

3.8 ESMP

The ESMP provides description of feasible and cost-effective measures that may reduce potentially significant adverse environmental impacts to acceptable levels. The plan includes compensatory measures if mitigation measures are not feasible, cost-effective, or sufficient. Specifically, the ESMP

- Identifies and summarizes all anticipated significant adverse environmental impacts including involuntary resettlement;
- Describes -with technical details - each mitigation measure, including the type of impact to which it relates and the conditions under which it is required together with responsibilities, frequency of monitoring, and anticipated costs, as appropriate;

Environmental monitoring during construction and operational phases provides information about key environmental aspects of the project, particularly the environmental impacts of the project and the effectiveness of mitigation measures.

The ESMP identifies monitoring objectives and specifies the type of monitoring, with linkages to the impacts assessed and the mitigation measures. Specifically, the monitoring section of the ESMP provides: a specific description, and technical details, of monitoring measures, including the parameters to be measured, monitoring frequency and responsibility to ensure early detection of conditions that necessitate particular mitigation measures, and furnish information on the progress and results of mitigation.

The ESMP encompasses:

- An implementation schedule for measures that must be carried out as part of the project, showing phasing and coordination with overall project implementation plans;
- The capital and recurrent cost estimates and sources of funds for implementing the ESMP.

ESMP provides also indication of the administrative and institutional framework required for the successful implementation of the project.

4 Policy, Legal and Institutional Framework

4.1 Relevant Strategies and Policies

4.1.1 National Development Plan 2011 -2014

The National Development Plan of Iraq set the following strategic objectives:

- Increase in the gross domestic product (GDP) at a rate of 9.38% per year during the plan period.
- Generate 3 to 4.5 million new jobs based on the proportion between capital concentration and work that will be used in activities and projects adopted by the Plan.
- Diversify the Iraqi economy through achievement of gradual increases in the rate of participation by other sectors in GDP, particularly the production, agriculture, and industrial sectors, along with tourism, which is a sector with some accomplishments and promise.
- Strengthen the role of the domestic and foreign private sectors, either in terms of the magnitude of investment anticipated within the country, estimated at about 46 percent, or in terms of job opportunities.
- Improve and increase productivity and promote the concept of competition, by focusing on comprehensive rural development and the creation of job opportunities, particularly for vulnerable groups such as youth and women, and focus on ensuring basic services, particularly educational and healthcare services, for rural areas and vulnerable groups.
- Establish a spatial development trend characterized by fair distribution of infrastructure services and public services (water and sanitation, health, education, etc.) among all of Iraq's provinces in a manner consistent with their population size and the extent of their deprivation and need.
- Establish sustainable development that balances economic, social, and environmental considerations so as to optimize use of available natural resources without undermining the right of future generations to benefit from those resources. Further to this, focus on keeping up with international developments in the areas of climate change and the use of environmentally friendly technologies.
- Strengthen the role of local governments in developing their provinces and building capacity for coordination and complementarities, using their comparative advantages.

Investment that must be secured at around 218 trillion Iraqi dinars, i.e., US\$186 billion during the five years of the plan; US\$100 billion would be funded by the federal budget at a rate of 30 percent per year of the overall budget. The remaining US\$86 billion would be funded by the domestic and foreign private sectors; the public and private sectors would contribute 53.7 percent and 46.3 percent, respectively.

The Plan sought to reserve 12.5 percent of its investments for the regional development program and 17 percent (31.6 US \$ billion) for the Kurdistan region.

In regards to transportation sector the objectives for road and bridge activities during the plan period focus on two axes.

The first axis consists of:

- Improving the condition of the current road network by repairing existing roads and reconstructing bridges affected by the war, military operations, and sabotage, as well as installing instructional, directional, and warning signs;
- Performing periodic maintenance on the existing road and bridge network, using modern and advanced techniques that would more quickly and economically implement repair and maintenance procedure, including the cold in-place asphalt pavement recycling technology recently approved in Iraq.

The second axis consists of increasing the network's capacity and its level of user safety and security, and protecting it from damage, by:

- Completing the remaining portions of highways previously constructed, and completing links between these roads and city centers that had not yet been linked thereto;
- Constructing new highways, particularly Highway No. 2, to link urban centers and complete the link between Iraq and neighboring countries that have not been linked by highways to date;
- Continuing to construct secondary lanes on arterial roads and one-lane roads, particularly those that have reached maximum capacity;
- Expanding construction of crossroads among the provinces, thereby reducing travel time
- Expanding construction of bypass roads that reduce congestion in cities and limit entry of through-traffic to city centers;
- Continuing to implement the plans' remaining stages to replace floating bridges with fixed bridges;
- Continuing to eliminate railroad crossings;
- Furnishing outer roads with instructional, directional, and warning signs;
- Protecting the road network from excessive weight by constructing weigh stations to detect and deter vehicle weights and axle loads that exceed the allowable limits;
- Continuing the program of constructing rural roads and increasing their reach to serve the greatest number of rural villages and agricultural projects and ensure their connection of agricultural production centers with markets.

4.1.2 Kurdistan Regional Government's Economic Development Strategy

The aim of the KRG's strategy⁹ is to develop Kurdistan's economy to the long-term benefit of the people, by nurturing a new and more innovative private sector that will produce goods and services in a competitive and sustainable environment. In order to support a vibrant private sector, the Kurdistan National Assembly, the Region's parliament, passed in 2006 an investment law that is one of the most investor-friendly in the entire Middle East. This policy is in line with Iraq's Economic Reform Strategy.

4.1.3 Iraqi Transport Master Plan

The Iraqi transport Master Plan¹⁰ was produced as a joint venture between the Iraqi and Italian Governments, with the aim to identify a plan of infrastructure investments and maintenance operations for roads, railways, airports, maritime and fluvial and intermodal facilities. A strategic multi-modal transport model was developed for the whole country with 91 internal zones, each corresponding to one or more districts, and 43 external zones representing other countries. In the Kurdistan region, there is a greater level of aggregation with 3 model zones in the Governorate of Duhok, 4 for Erbil and 5 for Sulaymaniyah.

Under this study, the values of time for Iraq were estimated at US\$1.30/hour for employed people and US\$0.432/hour for non-employed people, and at US\$2.94/hour for freight vehicles (2004 values).

4.2 Legislative Framework

The legislative framework provides a basis for addressing different aspects of the activities pertaining to the road construction and operation and maintenance.

4.2.1 National Legislation

The national legislative framework comprises laws, regulations and instructions issued by the Iraqi Government and by KRG. The summary of the legislation relevant to the scope of the present project and applicable for the whole road length including the segments beyond the scope of the Segment 2 are presented in Table 4-1.

Table 4-1: National Legislation

Legislation	Brief Overview	Issued By:
The Law for the Protection and Improvement of Environment No. 27, 2009	Main issues addressed by the Law: <ul style="list-style-type: none"> Establishment of the Environmental Council Importance of conducting EIAs 	Iraqi Government

⁹<http://www.krg.org/articles/detail.asp?lngnr=12&smap=03010800&rnr=145&anr=18617>

¹⁰ Iraqi Transport Master Plan (ITMP), October 2005, CIITI, Italian Consortium for Iraqi Transport Infrastructure.

Legislation	Brief Overview	Issued By:
	<ul style="list-style-type: none"> • Water protection • Control of noise emissions • Ecological protection • Hazard Management 	
The Forestry Law No. 30, 2009	<p>Main issues addressed by the Law:</p> <ul style="list-style-type: none"> • Combating desertification • Enhancing the environmental situation • Protection and control of forests 	Iraqi Government
The Law on the Protection of Wild Animals and Birds No. 17, 2010	<p>Main issues addressed by the Law:</p> <ul style="list-style-type: none"> • Protection of wild animals and natural resources • Hunting licensing and permits • Punitive system for illegal hunting 	Iraqi Government
Public Health Law No. 89, 1981	<p>Main issues addressed by the Law:</p> <ul style="list-style-type: none"> • Provision of health care for citizens; • Public health awareness; • Provision of health environment in the work place 	Iraqi Government
The Regulation for the Protection of Rivers No. 25, 1967 and instruction Corrections issued in pursuance to the provisions of Article 16	<p>The regulations contains provisions for the following:</p> <ul style="list-style-type: none"> • Defines water resources • Water contamination • Requirements for physical and chemical testing of water • Limit values for chemical and physical content 	Iraqi Government
The Law of Antiquities and Heritage No. 55, 2002	<p>Main provisions of the Law:</p> <ul style="list-style-type: none"> • Defines all movable and immovable antiquities, archeological properties and artifacts • Regulates communication channels for each type of contact between the public and revealed and non-revealed archeological sites 	Iraqi Government

Legislation	Brief Overview	Issued By:
	<ul style="list-style-type: none"> Governs contact with archeological sites for developmental activities in case their location is within the vicinity of archeological sites 	
Regulation for the Provision of Water Resources, No. 2, 2001	The regulation states that it is prohibited to discharge any amount of contaminants into any water bodies unless the special permit was obtained.	Iraqi Government
The Law of Environmental Protection and Improvement Board in the Iraqi Kurdistan Region No. 3, 2010	<p>Main provisions of the Law:</p> <ul style="list-style-type: none"> Environmental and public health protection Pollution prevention Preservation of natural resources and biodiversity Encourage environmental awareness 	KRG
Law of Environmental Protection and Improvement in Iraqi Kurdistan Region No.8, 2008	<p>Main issues:</p> <ul style="list-style-type: none"> Environmental protection of the Kurdistan region Prevention of pollution Protection of natural resources Raising environmental awareness Making the environmental policy a part of the developmental planning Environmental Impact Assessment requirements Environmental inspection and monitoring 	KRG
Law on Public Roads No. 35, 2002	<p>The law provisions for the procedures and practices for the resettlement and acquisition of land and properties during road construction and rehabilitation</p> <p>Compensation procedures are presented in (Annex 1) Part III:</p> <ul style="list-style-type: none"> General Directorate of Roads and Bridges identifies land and properties that are located on the 	KRG

Legislation	Brief Overview	Issued By:
	<p>ROW and presents the request for acquisition to the Governor</p> <ul style="list-style-type: none"> The Governor forms a Committee for compensation and acquisition. The Committee has the right to appoint expert(s) Public Roads Act No. 35 of 2002 specifies that the authorities have the right to acquisition of 25 % of the area of the land without any compensation to the owner. In case there are crops planted in the same area the state compensates for the value of the crops for the year including the value of the crops planted on the 25 % part that is state acquisition. However, no compensation is provisioned for the value of the land. The Committee for the acquisition and compensation provide assessment of the crops value according to the Ministers Decree No. 360 of 2008 based on specification of the type of crops, their financial value and quantities. 	
The Law for Investment in Kurdistan Region No. 4, 2006	The law stipulates that any investor has an obligation to safeguard the environment, public health and safety and to comply with the standardization and quality control systems according to the International standards.	KRG
Instruction No. 2, 2011	Provide measures for the protection of the ambient air quality from pollution and sets limits for the pollutant from different industries	KRG
Instruction for the Environment Protection and Improvement Board No. 1, 2011	Includes instructions on control of noise levels in Kurdistan Region and sets limits in decibels within different type of activities	KRG

Legislation	Brief Overview	Issued By:
Land Acquisition Law No. 12, 1981	The Law specifies that the state has the right to remove encroachers from state owned land without compensation	Iraqi Government

4.2.2 International Conventions and Treaties Signed by Iraq

The number of international conventions were signed and ratified by the Iraqi Government. These conventions and treaties are presented in the Table 4-2.

Table 4-2: International Conventions and Treaties

Name of the Convention/Treaty	Brief overview
Basel Convention on the Control of Trans-boundary Movements of Hazardous Wastes and Their Disposal	<p>The convention governs the movement of hazardous wastes across the international boundaries.</p> <ul style="list-style-type: none"> • It prohibits any movement/export/import across boundaries. • Reduction of hazardous waste generation to the minimum taking into consideration social, economic and technological aspects • Environmentally sound management of hazardous wastes • Ensure the safety of workers handling hazardous materials through implementation of prevention measures
UN Convention for Biological Diversity	<ul style="list-style-type: none"> • Conservation of biological diversity, the sustainable use of its components. • Introduce the procedures minimizing any adverse impacts on the biodiversity and its components and allow for public participation for the projects requiring ESIA studies.
UN Conventions to Combat Desertification	<ul style="list-style-type: none"> • Minimize the effects of the drought through preparation of the national action plans and strategies • Provide and implement procedures to minimize the land degradation and loss of productivity of the land • Mainstreaming of measures to combat desertification into national development plans
RAMSAR Convention for Wetlands	<ul style="list-style-type: none"> • Conservation and sustainable utilization of wetlands • Reduce loss of wetlands

Name of the Convention/Treaty	Brief overview
	<ul style="list-style-type: none"> Recognizing the fundamental ecological functions of wetlands and their economic, cultural, scientific, and recreational value
Montreal Protocol on Substances that Deplete the Ozone Layer	<ul style="list-style-type: none"> Control of the emission substances that have detrimental effect on the ozone layer
UNESCO World Heritage Convention	<ul style="list-style-type: none"> Addresses the need to ensure that effective and active measures are taken for the protection, conservation and presentation of cultural and natural heritage Mainstreaming the procedures for protection of the sites of the cultural and natural heritage into comprehensive planning programs. Set up services and operating methods for the protection of natural and cultural heritage.
United Nations Framework Convention on Climate Change (UNFCCC) and Kyoto Protocol	<ul style="list-style-type: none"> Sets an overall framework for intergovernmental efforts to tackle the challenge posed by climate change Considers the protection of climate system from industrial and other emissions of carbon dioxide and other Green House Gases (GHGs).

4.2.3 ESIA Requirements in National Legislation

There are two valid laws currently in force that regulate the preparation of the ESIA in Kurdistan Region: the Law for the Protection and Improvement of Environment No. 27, 2009 (issued by the Iraqi government) and the Law of Protection and Improvement in Iraqi Kurdistan Region, No 8, 2008 (issued by the KRG).

In the view of the present study it's deemed that the Law issued by KRG will be more applicable as more relevant to the study area.

The provisions of the Law of Protection and Improvement in Iraqi Kurdistan Region, No 8, 2008 are as following:

Articles 12, 13, 14 and 15 discuss the procedures related to ESIA studies as follows:

Article 12: Requires any individual, institution or agency performing an activity that may impact the environment to conduct an ESIA study to assess environmental impacts generated from project activities and consequently obtaining the Ministry of Environment's approval for it.

The study must include the following:

1. Assessment of the positive and negative impacts as a result of the project;
2. Proposed mitigation measures to prevent or treat contamination and pollution sources in accordance with the acceptable environmental standards and guidelines;
3. The probably emergency pollution cases and the prevention / reservations that must be implemented;
4. Assessment of suitable alternatives for using cleaner environment techniques;
5. Reduce and manage wastes and adopt measures for reuse of recycling;
6. Assessment of the cost of environmental benefits and damages that will be generated as a result of the project.

Article 13: The Minister may request from any individual, institution or agency to prepare an ESIA study prior to practicing of any activity that may potentially affect or impact the environment in accordance with the requirements of environmental protection.

Article 14: The Board for Environmental Protection and Improvement in Kurdistan will establish standards and specifications, necessary controls to identify projects and areas that are subject to environmental impact assessment studies and the preparation of lists relative to these projects and the development of systems and procedures for environmental impact assessment.

Article 15: All concerned parties must comply, in coordination with the Ministry and prior to obtaining the approval for any project to take the following measures and actions:

First: to work to prevent negative environmental impacts resulting from its projects or projects that are being supervised by these parties.

Second: take all appropriate measures to ensure the application of the rules contained in this law, including the regulations and instructions issued under this law.

Third: monitor and follow-up on environmental regulations and standards and commitments to their projects or the projects under supervision; And to provide the Board with periodic reports about it.

Fourth: Coordination with the Board before issuing any approvals or permits related to the exercise of strategic or major activities that may significantly impact the environment.

4.2.4 Contractual Obligations

Contracts signed with contractors for the provision of road works include special provisions pertaining to the protection of the environment and public and workers health and safety in compliance with the Law of Environmental Protection and Improvement in Iraqi Kurdistan

Region, No 8 for 2008, in particular, Clause no. 5, Article (12) which is related to Environmental Assessments and Environmental Permits.

The applicable terms of contract relevant to environmental and social/health and safety issues are as follows:

- Contractors are obliged to protect the Environment, including dust control management;
- Contractors are obliged to provide all health and safety procedures and protective equipment such as provision of traffic safety signage and warning signs mandatory in three languages: English, Arabic and Kurdish;
- Contractors are obliged to provide Personal Protective Equipment (PPE) for workers;
- All works must comply with Iraqi technical specifications relating to roads and bridges (SORB) in addition to special standards and specifications provided in the plans, and to comply with the necessary general conditions of contract; and the Instructions of Implementing Governmental Contracts for the year 2011 issued by the Ministry of Planning of the Kurdistan Regional Government, Iraq.

4.2.5 Land Acquisition and Resettlement Provisions

The Law that governs land and property acquisition and resettlement is the Public Roads Law No. 35 of 2002, which details procedures and practices to be followed on resettlement and acquisition of land and property relating to road construction and rehabilitation.

The ownership of land in Kurdistan Region has its own specifics:

- For legal purposes land in Kurdistan Region is all state-owned;
- Privately owned land with the Western understanding of property ownership exists almost exclusively in the urban areas;
- In agricultural areas the leased state-owned agricultural land is considered as “private land” by leasees.

Although the leased land is officially state owned the leasees receive compensation on the following basis: the State can acquire up to 25% of the leased State land without compensation, except that cash compensation is given to leases for the crops grown on these lands as well as for crops grown on the remaining packet of leased land for one year. Cash compensation amounts for various types of crops and trees are based on the Council of Ministers’ Decision No. 360 of 2008.

In instances where an entire parcel of leased land must be acquired from a leasee, cash compensation is provided for the value of the crops on that land for one year, and the leasee is entitled for the allocation of 12% of the total land parcel as “privately” owned land.

In the instances where the small businesses have been granted licenses for operation along the public roads and the land on which they operate is required for the road upgrade, the law stipulates that the license can be revoked and the land reclaimed without compensation. The license issued to the business owner specifies that such appropriation may be made and that no compensation will be provided for structure and equipment losses or livelihoods losses in such instances.

Additionally, Land Acquisition Law No. 12 of 1981 specifies that the State has the right to remove encroachers' state-owned lands without compensation. The law stipulates that the private land acquired for public purposes is not compensated if the amount of acquired land does not exceed 25 %. If the acquired amount of land exceeds the 25 %, the owner is entitled for compensation calculated according to the market price of the land.

National laws do not require consideration of alternatives to relocation of affected peoples who are encroaching on state lands. There are some precedents have been set whereby the Government has compensated unlicensed and encroaching occupants on road ROWs. In these cases, compensation amounts were determined by a committee comprised of:

1. Deputy Provincial Governor (head of the committee);
2. Director of the Roads and Bridges;
3. Real Estate Registration Office Director;
4. Agriculture Director;
5. Representative from the Agricultural Associations;
6. State Properties Representative in the Governorate;
7. Affected Person or anybody representing him/her

This is the main discrepancy between the national laws and WB OP 4.12. It has been agreed that the WB OP4.12 will apply to project activities and guide preparation of all social safeguards instruments such as the RPF and RAPs under the project.

4.2.6 World Bank Safeguard Operational Policies

The World Bank provides operational safeguard policies for the projects implemented and/or funded by the World Bank. The main purpose of these policies is to ensure prevention or minimization of the adverse environmental and social impacts and to increase socio-economic benefits.

The main safeguard policies are:

- OP/BP 4.01 Environmental Assessment
- OP/BP 4.04 Natural Habitats

- OP/BP 4.09 Pest Management
- OP/BP 4.10 Indigenous Peoples
- OP/BP 4.11 Physical Cultural Resources
- OP/BP 4.12 Involuntary Resettlement
- OP/BP 4.36 Forests
- OP/BP 4.37 Safety of Dams
- OP/BP 7.50 Projects on International Waterways
- OP/BP 7.60 Projects in Disputed Areas
- BP 17.50 Disclosure Policies

The policies that are viewed as most relevant to the scope of the present study are:

- Environmental Assessment (OP/BP 4.01)
- Involuntary Resettlement (OP/BP 4.12)
- OP/BP 4.11 – Physical Cultural Resources
- BP 17.50 Disclosure Policies

Additionally, Environmental, Health, and Safety Guidelines for Toll Roads are viewed as applicable for the project.

OP/BP 4.01 Environmental Assessment

This policy is triggered if a project is likely to have significant adverse environmental impacts in its area of influence. For category A projects, a comprehensive ESIA will be required with emphasis in integrating environmental measures in project planning, design, implementation and operation, in addition to help ensure the environmental soundness and sustainability of investment projects.

The Environmental Assessment takes into account the natural environment (air, water, and land); human health and safety; and social aspects (involuntary resettlement, physical cultural resources, etc.) in addition to trans-boundary and global environmental aspects.

This operational policy states the roles of the Bank and the Borrower:

The Bank mainly screens and sets the environmental assessment category and advises the borrower in terms of the Environmental Assessment requirements. The Bank reviews the findings and recommendations of the EA to determine whether they provide an adequate basis for processing the project for Bank financing. When the borrower has completed or partially completed EA work prior to the Bank's involvement in a project, the Bank reviews the EA to ensure its consistency with this policy. The Bank may, if appropriate, require additional EA work, including public consultation and disclosure.

The Borrower assists the bank in proper screening and will be responsible for carrying out environment assessment in compliance with the Bank's rules and national laws. The Borrower will also be responsible in consulting project affected persons and local Non-Governmental Organizations. The Borrower will disclose the draft/final documents and respond to any feedback provided from the Bank and/or the Public/stakeholders.

According to the World Bank WB OP 4.01 **the Project is classified as Category A.** "A proposed project is classified as Category A if it is likely to have significant adverse environmental impacts that are sensitive, diverse, or unprecedented. These impacts may affect an area broader than the sites or facilities subject to physical works".

OP/BP 4.12 Involuntary Resettlement

This policy requires that adverse social impacts of projects it supports be mitigated, including when land or property is acquired or its use modified under a project so that PAPs suffer loss of income, residence, livelihoods or access to resources, either permanent or temporary, whether the land occupation/use is legal or illegal. Resettlement or relocation of PAPs adversely affected by project activities must be undertaken in accordance with laws, regulations and guidelines for Resettlement/Land Acquisition of KRG and OP 4.12. If there is a gap between KRG laws and the Bank's OP 4.12 then the Bank's provisions must apply.

According to OP 4.12, the main objectives of this policy are:

- Involuntary resettlement should be avoided where feasible, or minimized, exploring all viable alternative project designs.
- Where it is not feasible to avoid relocation, resettlement activities should be conceived and executed as sustainable development programs, providing sufficient investment resources to enable the persons displaced by the project to share in project benefits.
- Displaced persons should be assisted in their efforts to improve their livelihoods and standards of living or at least to restore them, in real terms, to pre-displacement levels or to levels prevailing prior to the beginning of project implementation, whichever is higher.

This policy covers direct economic and social impacts that both result from Bank-assisted investment projects, and are caused by:

The Involuntary taking of land resulting in:

- Relocation or loss of shelter;
- Loss of assets or access to assets; or
- Loss of income sources or means of livelihood, whether or not the affected persons must move to another location; or

- The involuntary restriction of access to legally designated parks and protected areas resulting in adverse impacts on the livelihoods of the displaced persons.

The Bank's OP 4.12 on Involuntary Land Acquisition and Resettlement requires that affordable and accessible procedures for third party settlement of disputes arising from resettlement (i.e., grievance redress mechanisms) be made available. This GRM should take into account the availability of judicial recourse as well as traditional and community dispute resolution mechanisms. A checklist of issues recommended for consideration in establishing a GRM includes the following:

- Developing an inventory of reliable conflict mediation organizations in the project area to determine if any can be used instead of creating new ones.
- Reviewing GRM design and operation for simplicity, accessibility, affordability, and accountability. Good practice is to ensure that PAPs are well-informed about the existence and mode of operation of the GRM that they can lodge grievances orally and in the local language, that explicit time limits are set for addressing grievances, and that appeals procedures are well-specified.
- GRMs must be given authority to effectively resolve complaints. To support this, GRM committees usually include government officials (local and provincial), project officials, staff from other agencies with a substantial role in resettlement activities, and representatives of local communities and NGOs.

In addition to the two safeguard policies stated above the OP/BP 4.11 – Physical Cultural Resources is also applicable if any accidental discoveries or chance finds were encountered during construction activities.

BP 17.50 WB Disclosure Policies

This Bank Policy supports decision-making process by the Borrower and Bank through allowing public access to information on environmental and social aspects of projects.

Disclosure of key project documents, including Executive summaries in English and the local language, is mandated:

- In Country – prior to project appraisal in local language and in English;
- In the WB Info Shop before project appraisal in English with the Executive Summary in English and in the local language.

Environmental, Health, and Safety Guidelines for Toll Roads

The EHS Guidelines for Toll Roads include information relevant to construction, operation and maintenance of large, sealed road projects including associated bridges and overpasses.

Environmental issues during the construction and operation of roads are similar to those of other large infrastructure projects involving significant earth moving and civil works and their prevention and control recommendations are presented in the General EHS Guidelines.

These impacts include, among others,

- construction site waste generation;
- soil erosion and sediment control from materials sourcing areas and site preparation activities;
- fugitive dust and other emissions (e.g. from vehicle traffic, land clearing and movement, and materials stockpiles);
- noise from heavy equipment and truck traffic;
- and potential hazardous materials and oil spills associated with heavy equipment operation and fuelling activities.

Environmental issues specific to construction and operation of roads include the following: Habitat alteration and fragmentation

- Storm water;
- Waste;
- Noise;
- Air emissions;
- Wastewater.

4.2.7 Differences between the WB Safeguard Policies and National Legislation

The differences in national legislation and WB safeguard Policies in regards to the resettlement issues are summarized in the Table 4-3:

Table 4-3: Differences between National Legislation and WB Policies

Issue	WB	National Legislation
Avoidance or minimization of displacement of people	Avoid or minimize by exploring all viable alternatives; If resettlement is required – execute as sustainable program;	Not specified in national legislation

Issue	WB	National Legislation
Definitions of Adversely Affected Persons	<ul style="list-style-type: none"> Relocation or loss of shelter Loss of assets or access to assets; or Loss of income sources or means of livelihood, whether or not the affected persons must move to another location; or The involuntary restriction of access to legally designated parks and protected areas resulting in adverse impacts on the livelihoods of the displaced persons. 	People impacted by involuntary taking of land resulting in loss of land, assets and livelihoods in both laws No. 35 and 12
Requirement for Resettlement Action Plan (RAP)/Resettlement Policy Framework (RPF)	Full RAP required for 200+ adversely affected people. Abbreviated RAP for less than 200 adversely affected people	Law No. 35 provides for identification through land title registration and a compensation committee is formed to verify adversely affected persons
Consultations	Affected persons, communities, local authorities, NGOs – on eligibility criteria for compensation and assistance; Displaced persons & their communities and host communities – participate in planning, implementing and monitoring resettlement	The only consultation requirement is the negotiation procedure between affected parties with the compensation committee according to the Law No. 35
Impact on Informal Settlers	Included, but only entitled to resettlement assistance for structure and other assets lost (not land), and livelihood losses during resettlement.	Laws No. 35 and No. 12 do not provide for resettlement assistance or mitigation for informal/illegal settlers.
Compensation for Housing/Structures	Replacement structures provided or full replacement costs	Cash compensation for these assets as per established public valuation records

Issue	WB	National Legislation
		according to the Ministers Decree No. 360 of 2008 based on specification of the type of crops, their financial value and quantities
Compensation for Land	Agricultural land: market value of land of equal productive potential in vicinity plus the cost of preparing land to levels similar to affected land plus cost of transfer taxes & registration	Law No. 35 provides for acquisition of 25% of land without compensation In case of acquisition of whole packets of leased state land compensation is offered for 25% of that land packet size
Livelihood Support/ Transitional Assistance	Provide mitigation to fully redress livelihood losses including cash compensation, short-term employment opportunities on project activities, development assistance such as land preparation, credit facilities, training or job opportunities (includes business premises); For impacts on agricultural land – PAPs that are actively cultivating affected land are given combination of training, money to invest to improve productivity, agricultural extension and income restoration allowance. Adversely affected owners of land and entities are entitled for compensation and also the employees who work at those entities and whose livelihood will be adversely affected.	Not provided for.

In the view of the difference between the National Legislation and WB Safeguard Guidelines in definition of persons eligible for compensation and provision of compensation measures, it has been agreed that the WB procedures will prevail over the national legislation provisions.

4.3 Institutional Framework

The role of environmental protection is divided between different governmental institutions, which are responsible for specific aspects of environmental management. Also, some NGOs and scientific centers and universities are contributing to the nature protection in the Kurdistan Region.

The **Ministry of Natural Resources** of the Kurdistan Regional Government is responsible for the development of natural resources in the region. The Ministry of Natural Resources is the sole authorized signatory of production-sharing agreements with companies willing to invest in the exploration of hydrocarbons and mineral resources in the region. The ministry is also the authority awarding licenses for transportation and storage infrastructure, hydrocarbons and minerals production operations as well as refining, petrochemicals and retail operations.

Under the production sharing contracts, the companies are mandated to contribute to an environment fund every year. They are required to meet international petroleum industry standards of practice and adhere to the Kurdistan Region's laws to prevent pollution and protect the environment. This includes the protection of fauna and flora, property, agricultural areas and fisheries. Other obligations in the contracts include preventing environmental damage when constructing pipelines, and decommissioning or surrendering contract areas according to international petroleum industry standards of practice.

The Ministry has recently established a Health, Safety and Environment Department (HSED) to assume primary responsibility for the Ministry's regulatory activities in these areas.

The HSED's mission is to strive for the development of the Kurdistan Region's hydrocarbon resources in a socially and environmentally responsible manner, to meet the growing needs of the local population. Its activities are aimed at protecting the Region's environment (including its biodiversity, wild habitat and water resources) and promoting safe and environmentally sound practices in the industries regulated by the ministry, while encouraging the optimal exploitation of the Kurdistan's natural resources. In particular, the Health, Safety and Environment Department:

- Regulates and monitors the hydrocarbons industry to identify and reduce unsafe and environmentally damaging behavior at all stages of exploration, development, production and rehabilitation;
- Supervises the industry to ensure compliance with the provisions of applicable primary and secondary legislations, accepted standards and guidelines for environmental protection and health and safety; and

- Develops and promulgates suitable instructions and guidelines on environmental and health and safety issues related to the exploitation of natural resources in the Region.

Ministry of Agriculture and Water Resources regulates agricultural research, agriculture, national resources and forestry throughout Kurdistan.

In regards to water resources MAWR is responsible for the construction, operation and maintenance of water supply and sewage facilities and the national water resources management.

- Survey the different water resources, conserve them, and determine ways, means and priorities for their implementation and use.
- Develop the potential water resources in Kurdistan, increase their capacity and improve their quality, protect them from pollution, supervise them and administer their affairs and put forth programs and plans to meet future water needs by providing additional water resources.
- Regulate, and advise on, the construction of public and private wells, investigate groundwater resources, drill exploratory, reconnaissance, and production wells, and license well drilling rigs and drillers.
- Issue permits to engineers and licensed professionals to perform public water and sewerage works, and participates in organizing special training courses to qualify them in order to improve the standard of such works and to reduce water losses and pollution.
- Regulate the uses of water, prevent its waste, and conserve its consumption.

In regards to the agricultural issues in Kurdistan the responsibilities of the Ministry include:

- Setting of agricultural policy and future plans and projects in Kurdistan;
- Management of public rangelands and forests;
- Protection of soil, pastureland and flora;
- Pesticide and fertilizers authorizing;
- Support of different agricultural sectors.

Ministry of Environment/Environmental Protection and Improvement Board is the major governmental agency responsible for environmental conservation and protection.

The duties and authorities of the Ministry include but are not limited to:

- Establishing the general policy for protection of the environment, and putting forward, as required, essential plans and programs to implement them.
- Establishing the specifications and standards for elements of the environment.
- Monitoring and verifying environmental elements in coordination with scientific research centers and in accordance to the specifications set by the MOE.
- Proposing draft laws and regulation related to the Environment.

- Inspecting and auditing private and public institutions to ensure compliance with environmental requirements (parameters and specifications).
- Conducting and sponsoring research and studies on environment related issues.
- Issuing conditions and instructions, as required, for agricultural development, commercial, industrial and housing projects.

Ministry of Construction and Housing: Over the past ten years, Kurdistan has experienced a boom in infrastructure and construction development. The Ministry of Construction and Housing is one of the vital ministries within the KRG. The ministry has two major activities; the first is the construction of roads, and the second is the construction of housing projects and all other public service buildings. For the road sector, the Ministry has developed a Master Plan up to 2030, which was finished at 2011 as a road map for the future. The Ministry has already started implementing its components. The priority is highway construction – roads of at least two lanes connecting all of the major cities. The second stage of the master plan is the construction of express motorways.

Ministry of Municipalities and Tourism/Archeological Directorate of Duhok is entrusted with the following responsibilities:

- Develop and implement the archaeological policy of the region with regards to identification, supervision, protection, maintenance, register and restoration of archaeological sites.
- Promote archaeological sites on national and international levels.
- Conduct public awareness about archaeological sites in accordance to prevalent laws and regulations.

Municipalities are responsible for solid and liquid waste management, land use planning within their jurisdiction, licensing of economical and urban activities, construction and maintenance of roads and other infrastructures. It must be mentioned that it is a common practice in Kurdistan Region that a Mayor will act as a “citizen’s lawyer” in resolution of issues with the relevant authorities.

Farasheen Organization for Environmental Protection (FOEP): located in Zakho. Farasheen NGO has helped to build civil society networks to activate grassroots support for the protection of the environment, particularly the watersheds of Kurdistan, Northern Iraq. Further, FOEP strives to build capacity within Duhok Governorate, both in government and in academia, to help restore and protect the environment.

Duhok Farmers Union: The not-for-profit cooperative provides free technical assistance and training to farmers. The co-op also facilitates access to low-interest lines of credit to purchase or rent agricultural equipment and supplies — such as seed and fertilizer — and to secure needed

farm services at lower costs than the farmers could otherwise find. Also, this co-op negotiates on behalf of farmers with the governmental institutions.

University of Dohuk is currently implementing the program “Restoration and Preservation of the Natural Environment, Water for Every One (WFEO) - National Strategy to Save Water Resources” within the framework of the Kurdistan Water Program.

The Kurdistan Water Program (KWP) is a Regional Water Program was created in 2005. KWP is a platform bringing together competent organizations working regularly on water issues in the region. KWP represents the Global Water Partnership in the Kurdistan Region, and as such has the responsibility of implementing its principles and initiatives in the region. KWP goal is to promote and exchange knowledge on IWRM for the sustainable use of the region’s water resources. The main goals of the KWP are:

- To contribute and encourage the transformation of national water policies towards sustainability and to integrate water concerns into sectorial policies.
- To meet the strategic target to halve the proportion of people who do not have access to safe drinking water and adequate sanitation.
- To build synergies by setting up active water partnerships at the regional and the national level.
- To build capacity, to raise public awareness and to educate the youth and women on water issues.

A number of international donor organizations are active in the Kurdistan Region and are implementing projects designed to improve the livelihoods of the population. In some cases, the environmental protection guidelines applied by the agencies are stricter than the requirements of the National Legislation. Among the international agencies are:

- The World Bank;
- JICA – Japanese International Cooperation Agency;
- Embassy of Finland;
- FAO;
- Permaculture Institute of Australia.

Despite the fact that quite a number of institutions are involved in environmental protection and conservation, the institutional framework of the Kurdistan Region is characterized with a number of deficiencies:

- Dispersion of authorities and low level of coordination between different institutions.
- Overlap of jurisdiction, which might lead to overlooking the significant issues.

- Lengthy and bureaucratic process of obtaining the permits for different kind of activities that involves the number of institutions. For example: for operating a crusher for construction operations, a Contractor must seek agreement from 8 different entities and Departments which include: Ministry for Communication and Transportation; Ministry of Electricity; Ministry of Agriculture and Water Resources; General Directorate of Antiquities and Heritage; Ministry of Environment; Kurdistan Board of Investment; Ministry of Construction and Housing/Directorate of Roads and Bridges and the Land Registration Department.

4.4 Administrative Framework for Land Acquisition

As authorized by KRG, GDRB of Duhok bears primary official responsibility for ensuring that land acquisition and resettlement associated with the new road alignment are planned and implemented in a manner consistent with the laws and regulations of Kurdistan Region, and in a manner consistent with the principles and procedures of World Bank OP 4.12.

In accordance with the national legislation, the Compensation Committee has been established. The primary function of the CC is to establish and manage effective means for valuation of land and other assets that will be affected by the road, to establish and administer RAP eligibility criteria for all categories of affected persons, to assess and certify compensation amounts due affected persons, to recommend approval for timely payment of compensation in full to affected persons, and to ensure full and effective delivery of all other forms of assistance to affected persons.

The Compensation Committee comprises of:

1. Deputy Provincial Governor (head of the committee);
2. Director of the Roads and Bridges;
3. Real Estate Registration Office Director;
4. Agriculture Director;
5. Representative from the Agricultural Associations;
6. State Properties Representative in the Governorate;
7. Affected Person or anybody representing him/her

Effective implementation of resettlement program will require coordination with the Duhok governorate along with their subordinate district governments, and with local councils and village committees functioning at the village or settlement level.

Governorate and district-level officials have participated in the census and survey process. The governorate will have a role to play in determining increases to compensation, above the unit compensation rates, to take account of local extenuating circumstances, variation in production output capacity, or other location-specific factors. The cooperation of governorate and districts also will be solicited on an ad-hoc basis for many other aspects of RAP implementation. This may include facilitation of external project monitoring, addressing grievances from affected persons,

working with local councils and beneficiary committees to facilitate assistance to significantly affected persons or vulnerable persons, and facilitating local consultations and information disclosure.

At district level, the local council will have a more direct role in working with the GDRB to ensure that local facilities and services that are damaged or disrupted because of the project are rehabilitated or restored. The local council also will play a leading role in formulating, and facilitating the work of village committees. Similar to governorate level officials, the local council may be involved in facilitation of external project monitoring, addressing grievances from affected persons, and facilitating local consultations and information disclosure.

At the village or settlement level, the village level committees - existing formal, informal or customary organizations in local village or settlement - will play an important ad-hoc role in facilitating RAP implementation in devising strategies or opportunities to assist affected persons whose livelihoods are significantly affected, who may lack formal legal rights, who may be displaced from communal land or structures, or who are otherwise vulnerable to disadvantage because of the project.

The hierarchy of local administration is presented in Figure 4-1.




Figure 4-1: Hierarchy of Local Administration

5 Public Consultations

Public participation in the ESIA process has an important role in integrating economic, social and environmental objectives. Public participation makes a positive contribution to the project in terms of minimizing and avoiding potential public controversy and in identification of priorities of assessment.

Public participation in the present study was provided for through the following:

- A consultation session was conducted on July 17th, 2013 by Arabtech Jardaneh Company;
- Seven structured consultations with PAPS.

5.1 Stakeholders Identification and Analysis

A stakeholder is any entity with a declared or conceivable interest or stake in a project. Stakeholders fall into one or more of the following categories: international actors, national or political actors, public sector agencies, interest groups, commercial/private for-profit, nonprofit organizations, civil society members, and users/consumers.

Stakeholder analysis is a way of determining who among stakeholders can have the most positive or negative influence on the project, who is likely to be most affected by the effort, and how to work with stakeholders with different levels of interest and influence.

Generally, the stakeholders can be divided into the following categories:




Figure 5-1: Stakeholder Categories

Influence means that an individual or a group might apply power in some way and thus induce changes to the project. Interest means that people or organizations might be interest in the project in general or directly affected by it.

Based on this approach, the stakeholders identified for the project are presented in Table 5-1.

Table 5-1: Analysis of Stakeholders

Stakeholder	Interest	Influence
Farmers	Loss of agricultural land and crops due to land acquisition	Negotiations on the land acquisition mitigation and compensation
Business entities	Loss of part of the property; Potential disturbance to business activities due to obstruction of access	Negotiations on the land acquisition mitigation and compensation
Water Directorate of Duhok	To ensure that water resources in the area are not affected by the project	Regulates the use of water resources
Agricultural Directorate of Duhok	To minimize loss of productive fertile land	Regulates distribution of agricultural land parcels; Part of Compensation Committee
Directorate for Environmental Protection and Improvement Board of Duhok	To ensure that there is minimal impact on biodiversity along the road alignment; Avoidance of pollution of air, soils and water resources	Issues conditions and instructions for agricultural development, commercial, industrial and housing projects.
General Directorate of Roads and Bridges of Duhok	Provision of adequate and cost effective alignment alternative	Part of Compensation Committee; Road planning and design; Approval of the road alignment.
Directorate of Tourism and Archeology of Duhok	Avoidance of damage to the sites of historical and cultural importance. Ensure that in chance of accidental discovery the department is informed and proper procedure is followed.	Delay in construction works and change in the alignment in case of the chance discovery
Local administration: Governor of Duhok, Kai-makam of Siemel District, Batil Municipality, Administrators of local villages adjacent to the road	To ensure that farmers rights are met; No additional pressure is imposed on the municipal waste disposal	Responsible for provision of municipal services; Governor has the power to overrule the decision of the Compensation Committee; Part of Compensation Committee
Farmers' Union of Duhok	To ensure the farmers' rights are met during land acquisition	Representing farmers in the Compensation Committee

Stakeholder	Interest	Influence
Farasheen Environmental NGO	To ensure protection of environment	Close connection with the community, academics and Directorate of Environment
World Bank	To ensure that social and environmental safeguard are met according to the agreement with KRG	Funding agency
University of Duhok University of Zakho	Whether there is an interaction between their activities and road construction	Involved in developing strategy on sustainable water use in the region
Duhok Security Directorate and Duhok Traffic Department	To ensure safety of road users	Issue regulations on speed restriction, control drivers behavior, control road signage and marking

5.2 Public Awareness

Public awareness in the ESIA process is defined as public participation in all stages of the project planning and implementation. Keeping public informed ensures better level of the project acceptance, which is crucial to successful and timely completion of the project.

The plan of the road construction, although without any specific details, has been announced via local media. However, it must be stated, that this type of announcement was largely overlooked by the general public. Some of the governmental institutions due to the lack of coordination between them were not fully aware of the proposed development.

The further steps in public awareness are:

- Consultation Session;
- Individual interviews with PAPs;
- Interviews with the governmental officials;
- Negotiations of Compensation Committee with individual PAPs on the size of the land acquisition and proposed compensation.

5.3 Consultation Session

This public consultation exercise enables the stakeholders and public to understand the project and its activities, as well as to ensure that their concerns and issues were considered during all phases of the project especially at the planning phase.

The public consultation session at the announcement of the project was held on July 17th, 2013 at the Jiyan Hotel in Duhok (see figure 14). Approximately 40 people attended the Consultation

Session including representatives of governmental institutions, NGOs and CBOs and PAPs. The list of participants is presented in Annex 4.



Figure 5-2: Consultation Session

5.3.1 Objectives of the Consultation Session

The session was organized to present the proposed project and to solicit feedback concerning environmental and social impacts. The main objectives of the consultation session included:

- Inform the public about the project, including the proposed design of the road alignment, the need for land acquisition, and rationale for the road construction;
- Identify and prioritize the main issues of concern of different stakeholders;
- Obtain stakeholders acceptance of the project;
- Identify significant effects and factors to be studied in detail;
- Define the project boundaries.

5.3.2 Consultation Session Proceedings

The first part of the consultation session after the welcome of the GDRB officials was the presentation about the project and the purpose of the ESIA study:

- Proposed road alignment;
- Project description and main attributes;
- Purpose of the ESIA study and process of ESIA;
- Key potential issues;
- Role of public participation.

For the second session the participants were divided into four working groups, which provided recommendation and suggestions for the key issues to be addressed and expressed their main concerns.

5.3.3 Main Results of the Consultation Session

Overall the participants expressed their support for the project and viewed it as positive development in terms of the following:

- Improved safety of road users for motorists and for the entities alongside of the road;
- Reduced time to travel and ease of access to urban centers;
- Opportunity of the economic development and consequently additional employment opportunities;
- Improved access to the settlements located in the close proximity to the road alignment.

The participants also expressed their main concerns pertaining to the following issues:

- Socio-Economic Issues:
 - The effect of land acquisition on livelihood levels of the PAPs;
 - Impact on the household income due to the loss of crops;
 - Equitable compensation for the loss of land plots and possibility of obtaining the alternative plots;
 - Provision of employment opportunities for local residents in the project activities;
 - Communication with the relevant institutions and complaints resolution;
 - Provision of safety measures for the road users;
 - Minimization of impact on business entities during road construction;
 - Provision of opportunity for the local residence to supervise the project implementation;
 - Conservation of archeological sites and sites of cultural and religious importance.
- Environmental Issues:
 - Conservation of natural resources: water, soils and wildlife;
 - Minimization of the air pollution;
 - Location of the road alignment and the associated facilities, such as construction camp and borrow pits in the areas distanced from the environmentally sensitive receptors;
 - Avoidance and minimization of the negative impacts on biodiversity;
 - Provision of “green belt” of the row of trees alongside of the road alignment.

All these issues are taken into consideration in the detailed road design, possible alternatives in the road alignment and design features, and most significantly in the impacts scoping and evaluation.

The list of attendees is presented in the Annex 4.

5.4 Consultation with PAPs

The team has conducted seven consultations with PAPs along the road alignment. Three consultations were carried out in November 2013, and four in December 2013¹¹. The main results the consultations are as following:

- All the interviewed had previous knowledge about the road construction, and generally viewed it as a beneficial development for the area.
- The main concern of PAPs is the land acquisition and equitable compensation for it. Most prefer cash payments for the acquired land. However, some also expressed their concerns about the loss of the source of income and are interested whether the additional land plots will be available for them for cultivation and livestock grazing.
- The main recommendation of PAPs was to provide the infrastructure improvements to their villages and towns, in addition to improved roads accessing the settlements.



Figure 5-3: Consultations with PAPs

5.5 Meetings with Stakeholders

The summary of main meetings is presented in Table 5-2.

Table 5-2: Summary of Meetings with key Stakeholders

Date	Stakeholder	Brief Summary
4.11.2013	GDRB - PMT	Discussion and clarification of the TOR and preparation and approval of the work plan

¹¹ The dates of consultations with the PAPs: November 18, 19 and 21 2013; December 22, 29, 30, 31 2013

Date	Stakeholder	Brief Summary
15.11.2013	GDRB - PMT	Obtaining the framework study documents and engineering design
21.11.2013	GDRB - PMT	Discussion of the progress of the project
27.11.2013	Compensation Committee	Verify the findings of the field study in regards to eligibility for compensation and location on the ROW of the identified business entities and agricultural activities
17.12.2013	GDRB - PMT	Discussion of the progress of the project; Clarification of any alignment and design changes
21.12.2013	Duhok Environmental Department; Mr. Idris Kareem	Discuss the main environmental issues of concern
24.12.2013	Duhok Farmers Union, Mr. Hazem Pamir Loz	Discuss the main concern of farmers in regards to the land acquisition and crop losses
7.01.2014	Batil Agricultural Division, Walid Arab Suleiman	Discuss the main crops pattern in the project area, productivity, existence of wells in the vicinity of the project corridor
15.01.2014	Compensation Committee	Discuss the preliminary findings and estimates of land acquisition
25.01.2014	Duhok Archeological Directorate, Mr. Ethil Ibrahim Abdullah	Update on the final road geometry and design; Discuss the concerns about chance discovery of important sites

5.6 Project Acceptance

Overall, the stakeholders and the PAPs expressed their support for the project and viewed it as beneficial for the area. However, during the Consultation Session and consultations with stakeholders the number of issues was raised.

For all identified issues the severity of impact is evaluated, reasonable alternatives and adequate mitigation measures are proposed.

Based on stakeholders suggestions and recommendations project acceptance criteria are summarized in

Table 5-3.

Table 5-3: Project Acceptance

Parameter	Acceptance Criteria	Requirements
Land Acquisition	Avoidance and minimization of land acquisition where possible; Minimization of crop losses; Equitable compensation for land, crops and loss of income	Detailed census survey; Preparation of RAP; Provision of GRM
Water resources	Avoidance of surface and ground water contamination; Avoidance of changes of surface water discharge areas;	Condition of water bodies on or in the vicinity of the road alignment; Information regarding existing users, local abstraction and discharge consents; Extent of any catchment to be affected
Soil	Minimize soil contamination; Re-use of cut materials; Avoidance of soil erosion	Review of the project design for the amounts and composition of cut materials and areas to be affected; Desk study on soils type
Air quality	Minimization of air pollution from emissions; Abatement of dust generation	Assessment of the air pollution sources in the project area
Ecology	Avoid loss of flora and fauna species; Minimize habitat fragmentation	Desk study on species and habitats in the project area; Field visits
Waste management	Avoid uncontrolled disposal of generated solid waste and sewage in unauthorized areas	Current waste management practices in the project area; Population projections and future developments
Project facilities	Construction camp at sufficient distance from sensitive environmental receptors;	Identification of environmentally sensitive areas
Cultural and historical heritage	Avoid damage to the sites of historical, cultural and religious importance	An archaeological desk based assessment; A site visit and walkover survey
Aesthetic and visual impact	Reconstitution of the road sides to the pre-construction state; Landscaping and trees planting	Assessment of the current landscaping practices

5.7 Grievance Redress Mechanism

The Bank's OP 4.12 on *Involuntary Land Acquisition and Resettlement* requires that affordable and accessible procedures for third party settlement of disputes arising from resettlement (i.e., grievance redress mechanisms) be made available. This GRM takes into account the availability of judicial recourse as well as traditional and community dispute resolution mechanisms. GRMs must be given authority to effectively resolve complaints.

The proposed GRM is presented in Table 5-4.

Table 5-4: GRM Procedure

Step	Description	Responsibility	Timeframe/Duration
1	Receiving a written complaint, registering the date of receiving and entering the database for complaints. For illiterate persons or persons with very low level of literacy, they should be allowed to lodge a verbal complaint at the local administration office, contractors office or directly to the Project Grievance Officer, which will be further transferred in a written form to a GDRB.	Project Grievance Officer	1 working day
2	Acknowledgement of the receipt of the complaint and registering the acknowledgement date in the database	Project Grievance Officer	7 working days
3	The complaint via email is addressed to the designated authority in the KRG PMT	Project Grievance Officer	1 working day
4	Preparation of the response to the complaint	Responsible Officer at GDBR	20 working days
5	Receiving the response to the complaint and registering it in the database. If the proposed resolution requires cash expenditure, Management consent and approval is sought	Project Grievance Officer	1 working day
6	The written response is delivered by hand and includes a form for the complainant to (1) acknowledge receipt, and (2)	Project Grievance Officer	14 days

Step	Description	Responsibility	Timeframe/Duration
	<p>agree to the terms of the proposed resolution. In the event the complainant refuses to agree to the terms, he/she is invited to resubmit the complaint with explanation, and the process is repeated.</p> <p>The response for illiterate persons will be communicated to them through the local administration office.</p>		

6 Baseline Environmental and Socio-Economic Conditions

6.1 Physical Environment

The chapter below provides an overview of the physical environment in the project area.

6.1.1 Climate

The road alignment is located in the area, which is characterized as sub-humid upland and mountain region with semi-arid Mediterranean climatic conditions, which includes the Zagros Mountains and valleys as well as a part of the foothills. The main annual rainfall ranges between 400 mm and 1 100 mm. The mean minimum in July is about 22°C. In winter the mean monthly minimum in January is 10°C and the lowest minimum is -11°C.

The average rainfall for Iraq is presented in Figure 6-1 and Figure 6-2.



Figure 6-1: Precipitation Map of Iraq¹²

The nearest weather station to the project area is Zakho Metrological Station, which is around 17 km from Gersheen.

The average yearly rainfall at the project area was around 446 mm for the years 2003-2012. The highest rainfall is reported during January-February is 92 mm.




Figure 6-2: Mean Monthly Rainfall for Zakho Weather Station (2003 – 2012)

Temperature

Figure 6-3 presents the mean minimum temperatures measured for the years 2003-2012; lowest - in January (3.44°C) and the highest monthly average temperature in July (41.4°C). The average temperature for the ten years period was 20.75 °C.

¹² FAO: Iraq Country Pasture/Forage Resource Profile




Figure 6-3: Average Temperatures for Zakho Weather Station (2003 – 2012)

Wind Speed and Direction

The prevailing wind direction at the project area is South-East and sometimes tends to South-West and North-West. Wind speed is generally of light to moderate value with wind speeds between 0.74m/sec at times in November and 1.20m/sec at other times April to July.

6.1.2 Topography

Segment 2 is located in the area that is characterized as Undulating terrain: a transitional area between low plains and the mountainous region in the north and northeast (see figure 19). This category covers 67 000 km² and is divided into two sub-divisions one outside the mountainous region (42 000 km²) at altitudes ranging from 100-200 m, and the other within this region (25 000 km²) at an altitude varying from 200-450 m.



Figure 6-4: Topographic Map of Iraq¹³

6.1.3 Geology and Soils

6.1.3.1 Soils

The road is located at the foot of the Zagros Mountains and comprises of hills 500 to 1 000 meters high. It is underlain by beds of gravel, conglomerate and sandstones. The gravel and conglomerate layers alternate with thin layers of reddish loam and clay. The area is characterized as rolling hilly landscape with low parallel hill ridges and extensive valleys and plains. The hills are generally rounded and have thin soil. The level areas of valleys commonly consist of three different terraces. The lowest terrace usually being most extensive is most important with good arable soil.

¹³ FAO: Iraq Country Pasture/Forage Resource Profile

The soils are characterized as alluvial brown fertile soils belonging to the following types:

Calcic Xerosols: The subsoil has a reddish brown color and a sub angular blocky or blocky structure. The organic matter content is 0.5 to 0.9 percent in areas under cultivation; under neutral conditions it is expected to be about 1.0 percent or higher. These soils are very strongly calcareous below about 40 cm depth due to the presence of a zone of lime accumulation. At present they are used for dry farmed wheat and barley under a system of one year wheat and one year fallow.

Gypsum xerosols: These soils are similar to the calcic xerosols with a strong zone of gypsum accumulation. The subsoil is reddish brown and has sub-angular blocky or blocky structure. The zone of gypsum accumulation occurs at 20 to 80 cm depth. The thickness of the soil over the gypsum zone determines their agricultural value. Only those parts, which have at least 60 cm of soil above the gypsum zone are suitable for cropping. See soils map in Figure 6-5.




Figure 6-5: Soil Map of Iraq¹⁴

6.1.3.2 Geology

North Iraq is the north-eastern part of the Arabian Peninsula, which is a region of tectonic compression of particularly unstable area marked by convergent movements of the Arabian and Eurasian Plates that closed Tethys paleo-ocean and formed Zagros Belt in the north-eastern part of the Arabian Plate. This belt contains folded strata and normal faults trending NW – SE in the

¹⁴ FAO: Iraq Country Pasture/Forage Resource Profile

north-eastern part of the Arabian Peninsula toward Iran and turning E-W in its northern part toward Turkey.




Figure 6-6: Geological Formations in the Project Area

Stratigraphically the sections contain deposits of the Tethys Ocean during Jurassic and Cretaceous periods (Figure 6-6 and Figure 6-7). This ocean was mainly of dysoxic-anoxic paleo-environments along the equator and tectonically unrest that permitted preservation of high organic matter and development of oil and gas reserves.

The litho-stratigraphic section constitutes marine and subordinated lagoon beds deposited in the southern Tethys Ocean as sediment of carbonates, shale and anhydrites in a geologic time extending through Jurassic, Cretaceous and Paleocene up to Middle Miocene Fatha (Lower Fars Anhydrate) formation with double plunging anticline closures extending NW – SE turning towards north-western parts of Iraq, especially in the Sinjar Mountain to W – E trend.

A regional stratigraphic column¹⁵ in the Figure below shows the presence of a thick Jurassic and Cretaceous succession composed of carbonates, shale and anhydrites. The Jurassic Sargelu formation is extending through the whole of North Iraq.

At its type locality within Iraqi Kurdistan, the formation is composed of thin-bedded, black bituminous limestone, dolomitic limestone and black papery shale with streaks of thin black chert in the upper part with fossils of mainly *Posidinia spp.*, *Parkensonia spp.*, *Stephanoceras spp.*,

¹⁵US Geological Survey (Pollastro et al.1999)

Rhynchonella spp., plant fragments and poor impression of ammonites. They are overlain by bituminous limestone and shale of Upper Jurassic Naokelekan formation with a contact of apparently gradational and conformable taken below thin-bedded, highly bituminous contoured beds without chert and above thin-bedded black limestone with abundant chert and *Posidonia ornate*. The underlying formation is Lower Jurassic Allan Anhydrate formation that marked the lowest regional seal.




Figure 6-7: Regional Stratigraphic Column

6.1.4 Water resources

6.1.4.1 Groundwater Resources

The road passes over the Zakho Basin (see Figure 6-8). The Zakho Basin stretches across the border between Iraq and Turkey. It constitutes the lower part of the Feesh Khabour River (Tigris River tributary), and is bound from the east and west by the boundary of Feesh Khabour and from north and south by two anticlines, of which one is aligned with the southern border of the river basin. In Iraq, the Zakho Basin lies at an altitude of 500-600 m asl, with the surrounding mountains rising to 1,600-1,800 m asl. The basin is underlain by thick layers of productive recent deposits. Within the boundary of the suggested delineation, the basin covers a total area of 1,960 km², of which 1,695 km² are located in Iraq and 265 km² in Turkey.




Figure 6-8: Overview Map of the Zakho Basin¹⁶

The upper, dominant water-bearing formations in the Iraqi part of the Zakho Basin are made up of Quaternary deposits and Neogene clastics formations of the Bai Hassan and Mukdadia Formations and to a lesser extent of Upper and Lower Fars (Injana and Fatha) Formations. They form an unconfined aquifer system with a collective flow type centered on the Khabour River. The system extends briefly across the Khabour and Hezil Rivers into Turkey where it is bordered by a major fault in the north and obscured by younger volcanic deposits to the west of the Tigris River, northeast of Syria. The Paleogene, with its chalky limestone of the Pila Spi Formation, appears only at the axis of the two parallel anticlines that embrace the Zakho Basin. The Paleogene underlies the Neogene clastics at depth and forms a second confined groundwater aquifer system with the fine clastics Gercus Formation. The older Cretaceous aquifer system, which is widely present in north-eastern Iraq, is deep under the Zakho Basin.

In Iraq, the Zakho Basin has a catchment area of about 1,107 km². Within the catchment, it is assumed that 31% of the average annual rainfall (707 mm) infiltrates into the ground but only 23% reaches the aquifer systems. A total of 188 MCM/yr of water (160 MCM/yr in the inter-granular aquifer system and 28 MCM/yr in the fissured-karstic aquifer system) enters the basin as renewable resources. A considerable amount of the recharged volume is discharged through springs, especially those issuing from the fissured-karstic aquifer. A major spring (Deraboon) issuing near the Iraqi-Turkish border at the contact between the Pila Spi Formation and the less permeable overlying Lower Fars (Fatha) Formation is reported to have a discharge of 0.83-1.13 m³/s (see Overview Map).

Groundwater abstraction in the Iraqi part of the basin takes place mainly from the inter-granular Bai Hassan aquifer. In the early 1980s an estimated total of 24.3 MCM of good-quality (<700 mg/L TDS) water had been abstracted (9.5 MCM from deep wells and 12.3 MCM as spring discharge).

6.1.4.2 Wells

There are no wells in the vicinity of Segment 2 of the road. However, the limited information about wells in Duhok Governorate is available. It is estimated that there are 1958 licensed wells and about 62 illegal wells in the Duhok Governorate. The city of Duhok depends on the water supply from Tigris River, but other localities in the Governorate depend to some extent on the groundwater abstraction for the water supply.

¹⁶ Source: Compiled by ESCWA-BGR based on Aghanabati, 1993; Stevanovic and Markovic, 2004.

Generally, the wells are of 6-10 inches width, 10 – 50 m depth and yield ranging from 150 – 1000 gallon per minute. The water is generally unsuitable for drinking without treatment (see Table 6-1). Also, there are some records of the presence of the traces of heavy metals in groundwater¹⁷.

Table 6-1: Available Chemical Characteristics of water in Wells, Duhok Governorate¹⁸

Chemical Constituent	Average Concentrations	WHO Standard for drinking water
pH	6.5 - 8	6.5 – 8.5
TDS (total dissolved solids)	122 - 540	120
Cl ⁻	0.02 – 0.06	250
NO ₃ ⁻	16 - 230	40

6.1.4.3 Surface Water Resources

Main surface water resources comprise rainfall and the seasonal run off valleys. Figure 6-9 presents the seasonal run off valleys within the Segment 2.

The hydrogeological modeling was not conducted by the engineering team and the decision on the size and specifications of culverts was done based on the existing culverts on the road alignment and rough estimates. Generally, all the seasonal streams drain towards the Tigris River. The drainage area is characterized as undeveloped cultivated land with the catchment slopes ranging from 0.09 to 0.15 %. The catchment area is estimated as ranging from 1, 7 to 2.1 km². The peak runoff for 25 year period is evaluated as approximately 1.8 - 4.3 m³/sec.

¹⁷ International Journal of Engineering Science Invention ISSN (Online): 2319 – 6734, ISSN (Print): 2319 – 6726
www.ijesi.org Volume 2 Issue 4 | April. 2013 | PP.47-56

¹⁸ All values in ppm except of pH



Figure 6-9: Seasonal Run off Valleys and the Culverts in the Vicinity of Segment 2

6.1.5 Ambient Air Quality

There is no evidence nor data on ambient air quality monitoring in the project area. As there are no significant air pollution sources along the proposed motorway alignment, this issue was considered of minor importance.

The project area has no residential settlements and limited number of small scale businesses. The main activity in the area is the cereals cultivation with application of low level of pesticides and fertilizers. Therefore, the pollution from the operations of agricultural machinery is considered to

be negligible and short term. The dust generation is mostly from plowing of fields and use of the unpaved rural roads in close proximity to the road alignment.

The main source of air pollution is the vehicle emissions. The concentrations of pollutants in the air depends on a number of factors such as temperature, wind, humidity, cruise speed of vehicles, type of fuel, type of vehicles, etc.

The EPA standards for permissible concentrations of CO_x, SO_x, NO_x, lead, PM₁₀ and formaldehyde are presented in the Annex 4.

6.1.6 Noise

Noise is dependent on the specific equipment used and the proximity of that equipment to noise sensitive receptors. Since there are no residential communities in the vicinity of the road, and the existing businesses are operating predominantly during daytime for 8 working hours, noise is not considered as a significant issue.

The main source of noise is from the traffic using the road. Traffic types include short distance trips, long distance traveling and goods transportation with cars, public transport vehicles and small, large and heavy trucks.

There are no activities in the project area, which create vibrations. Therefore, vibrations are considered as extremely limited and not a relevant issue.

For the purpose of this project the maximum permissible noise limits, in terms of equivalent continuous noise level dB (A), for different areas set by the Jordanian Ministry of Environment (1997) were adopted (Table 6-2).

Table 6-2: Jordanian Standards for Maximum L_{eq} (1997)

Region	Maximum limits dB (A)	
	Day time	Night time
Urban residential	60	50
Suburban residential	55	45
Rural residential	50	40
Residential area with some workshops, simple handicrafts and commercial area in the center of the city	65	55
Industrial areas (heavy industries)	75	65
Areas of education, hospitalization and Worshipping	45	35

6.2 Biological Environment

The area has been subjected to diverse human induced impacts over the millennia such as rain-fed cultivation. Therefore, natural habitats have suffered the significant level of degradation over the past several hundred years. The forest type vegetation is almost non-existent, and most of natural non-forest type vegetation is on decline. The terrestrial ecosystem¹⁹ within the vicinity of the Segment 2 is characterized as Middle East Steppe eco-system, the conservation status is defined as vulnerable.

6.2.1 Flora

Vegetation reflects the Mesopotamian province of the Irano-Turanian eco-region and is characterized by the dominance of the drought-tolerant low shrubs with a variety of grasses and legumes. Herbaceous and dwarf shrub sage brush (*Artemisia* sp) communities tend to dominate in deeper, non-saline soils and often occur in association with grasses. The recorded vegetation is presented in Table 6-3 and the plant species observed during the field visit are presented in Figure 6-10, Figure 6-11 and Figure 6-12.

Table 6-3: Typical Irano-Turanian Steppe Vegetation

<i>Retama raetam</i>	<i>Artemisia herba-alba</i>	<i>Ferula communis</i>
<i>Noaea mucronata</i>	<i>Asphadelus aestivus</i>	<i>Lepidium aucheri</i>
<i>Salsola spp.</i>	<i>Urginea maritima</i>	<i>Cnicus spp.</i>
<i>Astragalus spinosis</i>	<i>Circium alatum</i>	<i>Paronychia argentea</i>
<i>Ballouta undulata</i>	<i>Achillea fragrantissima</i>	<i>Hordeum bulbosum</i>
<i>Thymus capitatus</i>	<i>Aegilops ovata</i>	<i>Crepis aspera</i>

¹⁹ National Report on Biodiversity in Iraq, July 2010



Figure 6-10: Artemisia Herba-Alba



Figure 6-11: Asphodelus aestivus



Figure 6-12: Cnicus spp.

6.2.2 Fauna

6.2.2.1 Birds

The area of the project is located in a general area identified as a fly-way route for migratory birds from Eastern Europe and West Siberia to Mesopotamia and Africa. The list of known bird species recorded in the area is presented in Table 6-4.

Table 6-4: Bird Species Recorded in the Vicinity of the Project²⁰

Common Name	Scientific Name	Breeding Status
Lesser kestrel	<i>Falco naumanni</i>	Migrant, summer breeder
Eurasian griffon vulture	<i>Gyps fulvus</i>	Migrant, summer breeder
Egyptian Vulture	<i>Neophron percnopterus</i>	Migrant, summer breeder
Long-legged Buzzard	<i>Buteo rufinus</i>	migrant
Steppe Buzzard	<i>Buteo buteo vulpinus</i>	migrant
Iraq babbler	<i>Turdoides altirostris</i>	Resident, spring-summer breeder
See-see Partridge	<i>Ammoperdix griseogularis</i>	resident
Red-wattled Lapwing	<i>Vanellus indicus</i>	resident
Finsch's Wheatear	<i>Oenanthe finschii</i>	Winter visitor
Graceful Prinia	<i>Prinia gracilis</i>	resident
Eastern Imperial Eagle	<i>Aquila heliaca</i>	Migrant, rare breeder
Northern Lapwing	<i>Vanellus vanellus</i>	Rare visitor
Common Cuckoo	<i>Cuculus canorus</i>	Common summer visitor
Turtle Dove	<i>Streptopelia turtur</i>	Migrant, summer breeder
Crested Lark	<i>Galerida cristata</i>	resident
Blackbird	<i>Turdus merula</i>	resident
European Bee-eater	<i>Merops apiaster</i>	Common migrant, summer breeder
Magpie	<i>Pica pica</i>	resident
Corncrake	<i>Crex Crex</i>	Passage migrant

6.2.2.2 Mammals

Large mammals that are associated with this ecoregion include: wolves (*Canis lupus*); Red fox (*Vulpes vulpes*); Golden jackals (*Canis aureus*); caracals (*Caracal caracal*); jungle cats (*Felis chaus*); Mongoose species (*Herpestes* sp); wildcats (*Felis silvestris*); Common otter (*Lutra lutra*); and Greater Horseshoe Bat (*Rhinolophus ferrumequinum*) – Table 6-5. Goitered gazelle (*Gazella subgutturosa*) and European badgers (*Meles meles*) can be found in more vegetated areas, and wild boar (*Sus scrofa*) can be found in reed thickets and semi-desert terrain. However, the status of these species is unknown and their presence was not recorded and is highly unlikely in the project area. The mammalian species recorded in the region include:

²⁰ R.F. Porter et al, Birds of the Middle East, First Princeton Field Guide Edition, 2004

Table 6-5: Mammals in the Vicinity of the Project

Scientific Name	Common Name	IUCN Status
<i>Hemiechinus auritus</i>	Long-eared Hedgehog	LC
<i>Paraechinus aethiopicus</i>	Ethiopian Hedgehog	LC
<i>Crocidura suaveolens</i>	Lesser white-toothed shrew	LC
<i>Suncus murinus</i>	Asian House Shrew	LC
<i>Suncus etruscus</i>	Pygmy White-toothed Shrew	LC
<i>Otonycteris hemprichii</i>	Desert Long-eared Bat	LC
<i>Allactaga euphratica</i>	Euphrates Jerboa	NT
<i>Jaculus jaculus</i>	Lesser Egyptian Jerboa	LC
<i>Gerbillus mesopotamicus</i>	Harrison's Gerbil ²¹	EN
<i>Gerbillus cheesmani</i>	Cheesman's Gerbil	LC
<i>Tatera indica</i>	Indian Gerbil	LC
<i>Meriones crassus</i>	Sundevall's Jird	LC
<i>Nesokia indica</i>	Short-tailed Bandicoot Rat	LC
<i>Rattus rattus</i>	Black Rat	LC
<i>Rattus norvegicus</i>	Brown Rat	LC

IUCN Categories: LC – Least Concern; NT – Nearly Threatened; EN - Endangered

6.2.2.3 Amphibians and Reptiles

The list of amphibian and reptile species expected to be present in the project area is presented in Table 6-6. However, their status and actual presence in the project area is unknown.

Table 6-6: Amphibians and Reptiles Recorded in the Project Area

Common name	Scientific Name
The Green Toad	<i>Bufo viridis</i>
The Green Frog	<i>Pelophylax ridibunda</i>
Keeled Rock Gecko	<i>Cyrtopodion scaber</i>
Asia Minor Thin-toed Gecko	<i>Cyrtopodion heterocercum</i>
Doria's Thin-toed Gecko	<i>Stenodactylus doriae</i>
Branford's Rock Gecko	<i>Bunopus tuberculatus</i>
Persian Gecko	<i>Asaccus elisae</i>
Yellow-bellied House Gecko	<i>Hemidactylus flaviviridis</i>
Persian Leaf-toed Gecko	<i>Hemidactylus persicus</i>
Snake-eyed Lizard	<i>Ophisops elegans</i>
Golden Grass Mabuya	<i>Mabuya aurata septemtaeniata</i>
The Bridled Mabuya	<i>Trachylepis vittata</i>
Glossy-bellied Racer	<i>Platyceps ventromaculatus</i>
Euphrates Soft-shelled Turtle	<i>Rafetus euphraticus</i>

²¹ Harrison, D. L. and M. Brown. The Wild Mammals of Arabia, 1991

6.2.3 Seasonal Water Bodies Habitats

There are a number of seasonal run-off wadis as presented in the Chapter 6.1.4.3. These wadis present the only remaining natural and semi-natural habitats. The green toad and green frog species, which number is on the decline due to the use of agrochemicals, can be found in such habitats. These wadis also present the habitat for the riparian vegetation, which serves as shelter for smaller animals, such as reptilians and a source of food. During the migratory season, the wadis might be used as short rest stops for some migratory bird species. The riparian vegetation on the sides of wadis also provides soil erosion protection. The most commonly found plant species are presented in the Table 6-7.

Table 6-7: Typical Riparian Vegetation in the Project Area

<i>Alisma laniceolatum</i>	<i>Fimbristylis sieberiana</i>	<i>Phragmites australis</i>
<i>Arundo donax</i>	<i>Juncus acutus</i>	<i>Polypogon monspeliensis</i>
<i>Baccapa monniera</i>	<i>Juncus articulatus</i>	<i>Salvinia natans</i>
<i>Bergia ammannioides</i>	<i>Lemna perpusilla</i>	<i>Veronica beccabunga</i>
<i>Cynancum acutum</i>	<i>Marsilea capensis</i>	<i>Zannichellia palustris</i>
<i>Cyperus rotundus</i>	<i>Paspalum paspaloides</i>	

6.2.4 Status of Habitats

6.2.4.1 Globally, Regionally, Nationally and Local Habitats

The project area does not contain any globally important habitats or ecosystems. The local importance of the area is that it represents the Irano-Turanian steppe area in Kurdistan. The local importance of the area is that it provides the resource for the livestock grazing. Also, due to the political situation in recent decades, the area has not been properly studied and might potentially contain some floral and faunal species that are not recorded in the area yet.

6.2.4.2 Legal Status of Habitats

There are no Nature Reserves or other legally protected areas in the vicinity of the project or in a close proximity. The area is well away from any sites of special ecological value. It is also distanced from “leading lines” that identify migration routes, and distant from Important Bird Areas (IBAs). The nearest IBA are located in Amadiya, approximately 60 km to the east of the project area:

- Ser Amadiya IBA
- Dori Serguza IBA
- Benawi IBA

No conservation practices are exercised in the project area apart from the control of hunting to the extent they are controlled and monitored throughout the country.

6.2.4.3 Status of Species

The project area has been used for over millennia, and agriculture and overgrazing in some cases has resulted in decline and disappearance of species. Only a few species have local, regional or international status.

There are no floral, amphibian or reptilian species of global importance in the project vicinity. The globally important mammalian species include the Euphrates Jerboa, defined by IUCN as nearly threatened and Harrison's Gerbil, defined as endangered. However, the habitat of this species is not located in the project area.

Bird species identified as regionally or globally important are listed in Table 6-8. None of these species has been recorded in recent years in the project area.

Table 6-8: Regionally and Globally Important Bird Species

Finsch's Wheatear	<i>Oenanthe finschii</i>	Winter visitor	Regionally threatened species
Corncrake	<i>Crex Crex</i>	Passage migrant	Globally threatened species

6.3 Baseline Socio-Economic Conditions

The baseline socio-economic conditions provide the background of the PAPs. The socio-economic survey was conducted through the series of structured interviews with PAPs with the help of the Kurdish translator and supplemented by the available statistical data. It must be noted that information available at the local level is limited, and in most cases, the statistical data is available to the whole governorate and/or sub-districts.

6.4 Demographics

6.4.1 Population Numbers

The proposed Transport Corridor traverses the Duhok Governorate. Duhok Governorate comprises 7 Districts and 29 Sub-districts. Table 6-9 presents aggregate population information for Dohuk Governorate and for each of its Districts and Sub-districts.

Table 6-9: Aggregate Population of Duhok Governorate (2009)

District	Sub-District	Population	Area (km ²)
Duhok	Duhok Center	284 040	104.1
	Mangesh	11 642	489.5
	Zawita	16 554	420.7
District Sub-total		312 236	1 014
Siemel	Batil	18 951	670.0
	Fayda	62 368	127.5

District	Sub-District	Population	Area (km ²)
	Siemel Center	72 205	578.6
District Sub-total		153 524	1 376.2
Zakho	Batifa	20 104	522.0
	Darkar	14 998	553.2
	Rizgari	17 800	364.4
	Zakho Center	175 155	11.7
District Sub-total		228 057	1 451.3
Amedi	Amedi Center	8 705	95.1
	Bamarne	6 936	240.6
	Chamanke	4 745	436.8
	Deraluk	45 095	993.6
	KaniMasi	9 180	756.9
	Sarsng	20 715	250.6
District Sub-total		95 376	2 773.6
Shekhan	Atrush	11 902	496.2
	Baadre	13 217	124.2
	Qasrok	59 995	297.0
	Shekhan Center/Esfne	21 270	179.2
	Zilkan	15 398	317.7
District Sub-total		121 782	1 414.2
Akre	Akre Center	66 346	124.5
	Bujil	17 478	286.7
	Dinarta	24 630	843.3
	Grdasin	40 345	577.5
District Sub-total		148 799	1 832.1
Bardarash	Bardarash Center	26 550	87.4
	Daratu	28 820	432.4
	Kalak	31 366	323.6
	Rofiya	29 910	306.8
District Sub-total		116 646	1,150.1
Total		1 176 420	11 011.8

The total population of Duhok Governorate is about 1,200,000 residents. However, due to the political situation in the region the area witnessed the influx of refugees, currently numbering about 1,300,000 people.

The villages adjacent to the newly proposed road date back from 1000 years ago and some people interviewed were 10th generation and still living in original housing. The central village is Kolli. Administratively Kolli represents Kani Kark, Kadia, Mazri, Khirbet Nour, Karkel, Turkshan, Kr Othman and Brav settlements; the combined population of these villages is approximately 600 people. Merga Sor is an administrative center for the group of small settlements comprising about 600 people in the Krowin district.

Growth rate is the average annual percent change in the population, resulting from a surplus (or deficit) of births over deaths and the balance of migrants entering and leaving a country. The growth rate is a factor in determining how great a burden would be imposed on a country by the changing needs of its people for infrastructure (e.g., schools, hospitals, housing, roads), resources (e.g., food, water, electricity), and jobs. The population growth rate is estimated as 2.23 for the year 2014.

6.4.2 Age and Gender Distribution

According to the official statistics, the ratio of males to females shows a close number of the two genders (Figure 6-13).




Figure 6-13: Age Pyramid in Iraq²²

Estimates of population and gender distribution for Iraq and in Kurdistan are presented in Table 6-10 and Table 6-11.

²²<https://www.cia.gov/library/publications/the-world-factbook/geos/iz.html>

Table 6-10: Age Distribution in Iraq (estimates for the year 2011)

Age Group	Percentage	Number	
		Male	Female
0-14 years	36.7%	6,093,069	5,878,590
15-24 years	19.6%	3,237,212	3,142,202
25-54 years	36.3%	6,032,379	5,785,967
55-64 years	3.2%	652,973	713,662
65 years and over	3.2%	487,841	561,797

The age and gender distribution of the Duhok Governorate population is presented in Table 6-11.

Table 6-11: Age Distribution in Duhok District for the Year 2009²³

Age Group	Number	
	Male	Female
0-15 years	104 600	107 700
16-65 years	130 700	147 500
65 years and over	68 000	82 000
Total	242 100	263 400

The population in Duhok is predominantly young. The economically active population constitutes almost half of the population. However, it must be noted, that the dependency rate is also very high, the dependency index is 84 (84 dependents per 100 of working persons).

6.4.3 Household Structure

On average the household in the study area is composed of 7.1 members with almost equal distribution between males and females of whom 2.6 are young people aged between 0 and 15 years and 3.5 are adults.

In the analysis of the demographic structure of the household the figure of the household head holds particular importance since it is the person that makes decisions and that manages the income and expenditure of the whole household. 89.8 % of the heads of the households are males and 10.2 are females.

²³Settlement and household survey report, Kurdistan Region Statistics Office, 2011

6.4.4 Household Income and Expenditure

The households receive income from the different sources, such as wages, social benefits, property income, etc.

Overall, households receive 45.3% of their income from wages and salaries; 25.0% from self-employment and employer income; 19.8% from property income; 5.2% from social payments; 4.7% from “transfers” from outside the country.

The average household income by income source is presented in Table 6-12.

Table 6-12: Household Income by Income Source (ID 000/month)²⁴

Area	Source of Income						
	Wages and Salaries	Self-employed and/or employer	Property Income	Social Benefits	Transfers	Total income Received	Total Income at Market Prices
Duhok	567.1	284.9	246.1	34.8	41.4	1,174.4	1,252.5
Iraq	388.8	214.9	170.2	44.4	40.5	858.8	952.4

As can be seen from the table above, the average household income in Duhok Governorate is slightly higher than the average for the country of Iraq.

It is estimated that the income from the agricultural activities (cultivation and livestock husbandry) ranges from 118,700 to 335,500 ID/months on average depending on the year and area of agricultural activity.

Additionally, under the food rationing system (Public Distribution System – PDS which replaced Food for Oil Program), each Iraqi is entitled to a monthly food basket for a nominal fee of 250 Iraqi dinars (\$0.21). The food basket is distributed, and fees collected, through approximately 45,000 “food and flour agents” – FFAs – throughout Iraq. Food agents are typically local groceries. Each Iraqi within Iraq is entitled to receive the PDS ration, tied to his official residence. The PDS individual monthly ration is the following: wheat (9 kg), rice (3 kg), sugar (2 kg), tea (200 grams), vegetable oil (1.25 kg), detergent (500 grams), pulses (250 grams), adult milk (250 grams), soap (250 grams) and infant formula (1.8 kg). This ration is estimated to supply 2,200 kcal per person per day. The cost of such food parcel estimated at approximately 25 US \$ at current market prices.

Also, government subsidizes heating/cooling of the dwellings, additional electricity supply of the dwellings by distributing fuel to households.

²⁴<http://cosit.gov.iq/en/rtl-support>

The household expenditure comprising the main items is presented in Table 6-13.

Table 6-13: Average Household Expenditure for Duhok Governorate²⁵

Item	Amount (ID 000/month)
Food	393.3
Clothing	124.8
Utilities Bills	374.4
Household Equipment	82.8
Health	33.4
Transportation	252.2
Communication	41.7
Education	33.5
Recreation	28.2
Miscellaneous	46.9
Cultural Activities	22.2
Total	1433.4

The highest household expenditure is food items, followed by the utility (water, electricity, gas, sewage) bills and transportation. Clothing is also one of the major items of expenditure of the household.

6.4.5 Household Characteristics of PAPs

Within the census survey of the area, the PAPs were interviewed with the help of the Kurdish translator. The interviews included the following questions:

- Size of the household;
- Number of people employed in the household;
- Legal rights, titles and claims pertaining to the ownership of the place of residence and agricultural land;
- Number of dependents in the household;
- Household income per year;
- Contribution of the agricultural activities to the household income.

Simultaneously, the respondents were informed about the project, and their recommendations were also recorded.

²⁵<http://cosit.gov.iq/en/living-conditions-statistics/surveys>

The main features of the PAPs households are as following:

- The household size is quite large, ranging from 6 to 9 people on average. Additionally, it is common practice that married sons with their spouses and children will continue living with the parents, contributing to the household income and expenditures.
- All of the households declared that they own the place of residence and land it is located on and have title deeds in the name of the head of the household;
- Although PAPs claim that they own the agricultural land they cultivate, there are no formal lease agreements or title deeds on agricultural land in their name;
- All household heads are male;
- There are no disabled and/or physically handicapped among the heads of the households;
- All of the household receive the food basket under PDS system;
- All of the interviewed PAPs are involved in the rain-fed agriculture, main crop cultivated – barley;
- Most of the households depend almost exclusively on the income from the agricultural activities;
- Additionally, some of the PAPs have additional income from employment in the government and army’

Table 6-14 shows social profile of 22 PAPs who agreed to share information regarding their social and financial status with the Consultant.

Table 6-14: Social Profile of PAPs

#	Place of Residence	PAP	Residence Ownership	Number of People Residing	Number of Persons Employed in the Household	Number of Dependents		Declared Income of the Head of the Household (US \$)	Income Contribution from Agriculture
						Female	Children (< 18 years of age)		
1	Batil	PAP_001	Owned	11	1	1	9	12 000	10%
2	Batil	PAP_002	Owned	1	1	N/A	N/A	12 000	100%
3	Batil	PAP_003	Owned	15	1	2	11	12 000	50%
4	Batil	PAP_004	Owned	14	6	2	10	12 000	50%
5	Batil	PAP_005	Owned	7	3	1	5	8 000	100%
6	Batil	PAP_006	Owned	7	2	1	5	10 000	50%
7	Batil	PAP_007	Owned	8	1	1	6	12 000	100%
8	Batil	PAP_008	Owned	12	1	1	10	10 000	100%
9	Batil	PAP_010	Owned	3	2	1	1	6 000	100%
10	Batil	PAP_012	Owned	10	3	1	8	10 000	100%
11	Batil	PAP_011	Owned	9	1	1	7	15 000	50%
12	Batil	PAP_013	Owned	7	1	1	5	20 000	100%
13	Batil	PAP_021	Owned	8	3	1	6	12 000	100%

#	Place of Residence	PAP	Residence Ownership	Number of People Residing	Number of Persons Employed in the Household	Number of Dependents		Declared Income of the Head of the Household (US \$)	Income Contribution from Agriculture
						Female	Children (< 18 years of age)		
14	Batil	PAP_031	Owned	30	2	3	24	40 000	100%
15	Batil	PAP_023	Owned	19	1	2	15	25 000	100%
16	Gersheen	PAP_017	Owned	13	1	1	11	8 000	100%
17	Gersheen	PAP_015	Owned	17	1	3	11	10 000	100%
18	Bawarda	PAP_016	Owned	7	6	1	5	20 000	100%
19	Bawarda	PAP_027	Owned	13	3	1	11	12 000	100%
20	Bawarda	PAP_018	Owned	32	2	3	26	34 000	100%
21	Bawarda	PAP_019	Owned	15	1	2	11	34 000	100%
22	Smail Ava	PAP_014	Owned	14	3	5	9	4 200	10%

6.5 Employment

The unemployment rate in Duhok Governorate reaches almost 17 %, which is slightly higher than the average of the Kurdistan Region (Table 6-15). Due to the data limitations, the only reliable available information on the unemployment is available for the year 2008.

Table 6-15: Unemployment Rate by Governorate, Area & Sex for the year 2008²⁶

Governorate	Center Urban			Other Urban			Rural			Grand Total		
	Male	Female	Total	Male	Female	Total	Male	Female	Total	Male	Female	Total
Duhok	12.1	23.8	14.3	14.2	46.3	18.2	12.9	58.5	17.5	13.3	39.7	16.9
Erbil	7.0	8.4	7.2	8.2	46.8	16.0	7.7	64.8	23.9	7.5	36.0	13.2
Sulaimaniya	6.3	24.6	10.4	9.4	33.7	13.4	7.1	23.7	11.3	7.9	27.4	11.9
Total	13.1	25.0	15.2	15.4	36.1	18.5	14.9	8.3	13.3	14.3	19.6	15.3

The employment pattern of the heads of the household is presented in Table 6-16.

Table 6-16: Employment Patterns of the Heads of the Household for Duhok Governorate for 2007²⁷

Type of Employment	Percentage
Farming- Self-employed	4.2
Agricultural laborer	3.8
Skilled laborer	10.8
Non-skilled laborer	11.9
Public servant	46.9
Self-employed - Non-Farm	20.3
Other	2.1

²⁶<http://cosit.gov.iq/en/population-manpower-statistics/manpower>

²⁷ Comprehensive food security and vulnerability survey of Iraq, 2007

6.6 Infrastructure and Utilities

6.6.1 Waste Disposal

Sewage disposal: the main method of sewage management are cesspits. Only 5.5 % of households are connected to the sewage network. The conditions of cesspits are questionable, mostly they are the earth-bottomed pits and the emptying of them happens not on a regular basis. Such sewage disposal presents the health hazard due to the potential soil and groundwater contamination. The situation worsens since the collected sewage is literally dumped into the streams without any kind of treatment that join the River Tigris.

The newly built residential compounds, such as Avro City, are supplied with wastewater treatment facilities, but their capacity is sufficient only for these compounds. The city of Duhok has no wastewater treatment facilities.

Solid waste disposal: solid waste collection from houses in residential areas in Duhok district stands at 79 %. However, 40% of the collected solid waste is dumped in open unauthorized sites. Leaching of the waste into the ground also poses the health hazard due to the potential soil and groundwater contamination. Recently, there has been an improvement in the solid waste collection on daily basis and separation at the collection stage for further recycling.

Collection of the solid waste and street cleaning in the city of Duhok has been outsourced to a private company. The company has established a recycling plant at the outskirts of the city of Duhok approximately 7 km south-west of the start of the road alignment. Adjacent to it is the waste dumping site where the non-recyclables and all other solid waste from the area are disposed.

**6-14:
Disposal**



**Figure
Waste
Site**

6.6.2 Utilities Supply

In terms of the adequacy of the infrastructure, Duhok district in Kurdistan is considered as relatively well supplied compared to the other district of Kurdistan and Iraq in whole.

Water Supply: 88 % of households in Duhok receive drinking water from the public water network. The main source of the drinking water is the treated water from the River Tigris.

Electricity: The percentages of working electricity supply system are of 70.3% in the urban areas, 89.5% in the collective towns, and 79.7% in the rural areas.

However, it must be mentioned that the electricity grid has an insufficient capacity for the grown population of the area. The electricity black-outs are a common occurrence. Therefore, it is a common practice for local residents to have a diesel fueled generator to compensate for the electricity cuts. The electricity black-outs in Duhok Governorate are reported to be from 6-15 hours per week.

6.6.3 Health Care

In the governorate of Duhok there is one hospital or health center in use for every 10,168 residents in the urban area, one for every 7,781 in the collective town, and one for every 5,421 in the rural area. In Duhok Governorate these are the ratios between permanent population to one medical staff: 278 in the urban areas, 641 in the collective towns, and 647 in the rural centers.

The number of available beds compared with the resident population is one of the significant indicators of such a structural deficiency of the health centers especially of those located in the sub-urban areas. According to the data provided by WHO, there should be 4 beds for every 1,000 people. In the Governorate of Duhok there is one available bed for every 425 people in the urban centers, one for every 3,493 in the collective towns and one for every 21,682 in the rural areas.

6.6.4 Education

Education is a very important indicator of the wellbeing of the population. As a general rule people with better education are better equipped to deal with the circumstances and are capable of finding better paid skilled jobs.

The number of students exceeds the 24% of the permanent population in all four areas of the Northern Iraq. In the urban areas, the number of people attending school is about 29.8% in the district of Duhok. The ratio between number of students and permanent population reaches 26.3% in the urban areas, 24.7% in the collective towns, and 23.6% in the rural areas. In the urban centers for every 1,582 inhabitants there is a school in the governorate of Duhok.

Illiteracy rate is about 30 % in the governorate of Duhok on average among the economically active population aged between 15 to 64 years (Table 6-17).

Table 6-17: Educational Level of Household Members >10 Years of Age

Educational Level	Percentage of Population (%)
Illiterate	30.5
Read and write	24.3
Primary School	22.9
Intermediate School	11.1
Secondary School	5.6
Diploma after secondary school	3.2
University Degree	2.0
Post Graduate degree	0.3

6.6.5 Cultural, Religious and Historic Facilities and Amenities

The population of the Duhok is predominantly Muslim in religion, and the places of worship are available in every settlement.

It is reported that there are a number of recreational facilities operating in Duhok, such as:

- Art galleries – 10
- Cinemas – 2
- Churches – 5
- Soccer fields – 20
- Gyms – 20
- Swimming pools – 3
- Mosques – 3
- Parks – 4

Settlements in Dohuk Governorate have a long history, dating back to 8000 BC, the period of the Sumerians & Akkadians. Dohuk's long history as a gateway to the Baghdad area and to the ancient cities in Iran has created a rich, distinctive cultural heritage. This culture is physically embodied by temples, churches, mosques, inscriptions, historic buildings, public art, historic public spaces and infrastructure.

A preliminary archaeological review was conducted for the project area in July 2013 along the entire 63 km road alignment, with specific attention being paid to Segments 2 and 3. This assessment was focused on the potential archaeological sites that might be located within a corridor of 1100 m width including the ROW of the two segments.

The main archaeological findings for the area of project activities are presented in Figure 6-15. A 1,100 m buffer zone is shown in the map, to enable the identification of significant sites that may be potentially impacted, in addition to other known sites that are located outside the 1,100m buffer zone.



Figure 6-15: Sites of Cultural Importance in the Vicinity of Segment 2 ROW

Within Segment 2, the only existing site of cultural importance the Batil Cemetery has been identified. Batil Cemetery is a modern cemetery; however it might have been in use for a more extended period of time. The cemetery is located on the western side of the road, approximately 80 m from the centerline. The road design avoids the cemetery and therefore direct impacts are not expected, however chance finds are possible.

6.6.6 Roads and Transportation

The length of the total primary and secondary networks, which have been surveyed in Kurdistan, is approximately 5000km, split as shown in the Table 6-18. This estimate excludes the roads under construction.

Table 6-18: Length of Transport Network in Kurdistan

Governorate	Highway (km)	Secondary (km)	Total (km)
Erbil	777.3	1124.5	1901.7
Duhok	559.6	852.4	1412.0
Sulaymaniyah	698.1	1269.4	1967.5
Total	2034.9	3246.2	5281.2

Table 6-19 shows the distributions of key attributes from the road inventory survey, in terms of the length of the road network with different characteristics, by road type and Governorate.

Table 6-19: Distribution of Road Length according to Land Use

Land Use	Duhok (km)			Erbil (km)			Sulaymaniyah (km)			Grand Total
	Highway	Secondary	Total	Highway	Secondary	Total	Highway	Secondary	Total	
Agriculture	48.2	132.2	176.9	27.5	147.1	170.2	66.0	187.4	249.8	591.5
Commerce	0.0	0.0	0.0	0.0	3.6	3.5	0.0	0.0	0.0	3.8
Industry	7.3	0.6	8.5	2.3	10.4	12.5	14.2	5.3	20.6	41.3
Residential	77.2	119.0	196.1	160.3	185.9	348.2	134.5	144.2	284.1	834.4
Vacant	426.9	593.4	1023.7	535.3	765.4	1301.1	471.7	917.2	1385.8	3706.1
Mixed use	0.0	1.2	1.1	49.8	0.0	52.8	0.0	0.0	0.0	57.9
N/A	0.0	6.0	5.7	1.9	12.1	13.5	11.6	15.3	27.3	46.2
Grand Total	559.6	852.4	1412.0	777.3	1124.5	1901.7	698.1	1269.4	1967.5	5281.2

General description of roads network:

- Land use: a large part of the land use around the roads surveyed is vacant, which is what could be expected from inter-urban sites such as the highway and secondary roads surveyed. The second most common land use is residential, followed by agriculture.
- Road surface: the majority of the roads surveyed are asphalted.
- Topography: most of the terrain is characterized by “rolling”, while the second most frequent topography is “mountainous”.
- Road conditions: a significant proportion of the roads surveyed are in “excellent” condition. In Sulaymaniyah, approximately half of the road network is in “excellent” conditions. However, some 863 km of roads are in “critical” conditions, about half as much just in Erbil.
- Road signs: from the sites where signage has been found, the majority of signs are in “good” conditions.
- Road markings: from the sites where markings have been found, most have been categorized as “eroded”.

The provision and organization of public transport services varies widely within Kurdistan (see Table 6-20).

Table 6-20: Number of Public Transport Vehicles Operating in Duhok

Route Name	No. of Vehicles Operating at Station	
	Taxi	Bus
Duhok – Zakho	75	2
Duhok – Mosel	29	16
Duhok – Erbil	93	0
Duhok – Sarsange	13	0
Duhok – Amedi	15	0
Duhok – Mangesh	23	0
Duhok – Deraluk	17	0
Duhok – Bamarne	1	0
Total	266	18

6.7 Main Land Use Patterns

Area along the alignment is characterized as predominantly agricultural area. It is considered as one of the most fertile area in Kurdistan and the main crop patterns include: cereals, legumes and vegetables. Irrigated agriculture is limited, and the predominant agricultural patterns are rain-fed seasonal cultivations.

The rain-fed subsector consists of a rain-dependent winter growing season extending from September/October to April/May. The season is supported by an average precipitation of 350 mm to 1 100 mm increasing from south to north and varying from year to year in both quantity and distribution, in a manner typical of semi-arid, continental climates. The rain-fed farming systems are essentially as following: continuous wheat with fertilizer applications juxtaposed with a barley/fallow rotation which usually does not include fertilizer use, but may incorporate chickpeas one year in three or four.

In rural area 62 percent of households reportedly own livestock compared to only 4 percent of those living in urban area. The most common animals owned by households were poultry, sheep and cattle with an average holding size of 19, 11 and 3 animals, respectively. However, the poultry industry was affected dramatically as a result of severe culling due to the incidence of avian flu in Iraq.


6.8 Project Area Activity Patterns

6.8.1 Agricultural Activity Pattern

Communities in the project area are developing increasingly diverse economic structure seeking to maximize the opportunities available to them from existing traditional lifestyles and the emerging mixed economy of Kurdistan (Figure 6-16). In effect they are seeking to gather the maximum benefit from their traditional ways of life and those of the urban dweller.

Notwithstanding the above, the rural communities of the project area remain predominantly agricultural and retain strong links to the land and social and economic structures of the past.

Main crops in the area are cereals (barley and wheat) with production rate of 690 – 840 kg/ha and legumes (chickpeas and lentils) with production rate 560 – 590 kg/ha²⁸. Labor requirements in crop production are kept to a minimum. Once land is planted it is rarely tendered again until harvest. Moreover, those farming the land invariably have second jobs in the public service and army, and also keep sheep and goats for their own consumption.



6 – Krowin	19 – Karkel	77 – Khirbet Nour	75 – Kadia	74 – Turkshan
7 – Merga Sor	78 – Buraq	76 – Kolli	73 – Gersheen	68 – Batil
51 – Kr Othman	52 – Smail Ava			

Figure 6-16: Map of Counties in Project Area

²⁸<http://www.fao.org/docrep/006/y9870e/y9870e07.htm>

These lands also play a significant role in the pastoralist economy providing grazing for the collective livestock herds. Loss of access to or non-cropping of these lands in the longer term could have a detrimental impact on local communities.

Figure 6-16 shows the parcels of land in Batil sub-district, which a section of the TC passes through. Base maps were collected from Dohuk Agricultural Department.

The road crosses the lands that are jurisdiction of the Batil Agricultural Directorate. Most of the land areas are categorized as agricultural with the majority being rain-fed agriculture. Table 6-21 provides the breakdown of agricultural lands.

Table 6-21: Breakdown of Land Use under Batil Agricultural Department Mandate

Category	Area (Dunum)	Area (km ²)	Percentage (%)
Forests and rocky areas	68 939	172.35	31.3
Pastures	9 976	24.94	4.5
Cultivated areas	141 555	353.89	64.2
Total	220 470	551.18	100
Breakdown of cultivated areas			
Rain-fed cultivation (no formal lease agreements)	74 414	186.04	52.6
Irrigated cultivation (no formal lease agreements)	236	0.59	0.2
Rain-fed cultivation (formal lease agreements)	65 478	163.7	46.3
Irrigated cultivation (formal lease agreements)	276	0.69	0.2
Fruit Orchards	189	0.47	0.1
Vineyards	360	0.9	0.2
Irrigated by water channels	602	1.51	0.4
Total	141 555	353.9	100

6.8.2 Business Activities

A number of business and commercial entities also operate on the sides of the road alignment. The business entities with their brief description are presented in Table 6-22. Photographic evidence is provided Figure 6-17 to Figure 6-22.

Table 6-22: Business Entities

#	Name of Business Entity	Location Coordinates	Name of the Owner	Short Description	Land Parcel Ownership	Number of Employees	Eligibility for Compensation/Mitigation
1	Evin Gas Oil Station	E: 42,652088 N: 36,978423	Mr. Shmal	Concrete 4 truck bay diesel pumping station with overhead concrete roof; backed by extensive multi story concrete building with concrete roof, all in poor repair. A lot of miscellaneous abandoned equipment and temporary structures are on the vacant land parcel adjacent to the station.	Reported Private	5-7	Not eligible, no land acquisition. Requires provision of entry/exit ramps during construction period
2	Junk Yard	E: 42,651081 N: 36,979785	Mr. Mahmoud Simo	Haphazardly heaped un-operational old vehicles and equipment	Reported private	1 (operated by the owner by request)	Not eligible. The equipment sold prior to the construction
3	Girsheen Company and Fuel Station	E: 42,640558 N: 36,994753	Mr. Hashim Sabry and Mr. Zeravan Mousa	Concrete 4 truck bay diesel pumping station with overhead concrete roof; backed by extensive one story concrete building with concrete roof, all in poor repair. 2 small shops adjacent – concrete with concrete roofs. Large gas pumping area with extensive one story concrete	Leased from Mr. Mohammad Abdulrahman Suaivany.	7-9	Not eligible, no land acquisition. Requires provision of entry/exit ramps during construction period

#	Name of Business Entity	Location Coordinates	Name of the Owner	Short Description	Land Parcel Ownership	Number of Employees	Eligibility for Compensation/Mitigation
				building behind; 2 small shops. Large informal truck parking area adjacent to the station. Irrigation pipe storage and shop.			
4	Efor Company	N: 36,957745 E: 42,645086	N/A	Efor Sign and metal fence in very good condition.	Leased from state	N/A	Needs relocation of the sign at the responsibility of the contractor. The fence and the company itself are not on the ROW.
5	Bawer Fuel Station	E: 42,645028 N: 36,967908	Mr. Jarjees Hamid Bashar	Modern, newly constructed 4 bay pumping station, backed by the one story building. Sign post erected in front of the station	Reported private	Not operational at the time of assessment	Requires relocation of the sign pole. Requires provision of entry/exit ramps during construction period
6	Aveen Tires and Repair Shop	E: 42,651098 N: 36,979775	Mr Bayer Mohammad Ismael	Concrete structure, tin roof. Large open room with small attached office space in rather poor condition. The business is operated without the business license and without the legal permits or lease agreements for the land it is located on.	Operating without business license and lease agreement for land	1 (operated by the owner)	Land acquisition of the entire plot of 167,5 m ² . Eligible for compensation

#	Name of Business Entity	Location Coordinates	Name of the Owner	Short Description	Land Parcel Ownership	Number of Employees	Eligibility for Compensation/Mitigation
7	Azra Company	N: 36,977560 E: 42,652551	N/A	Large warehouse with a sign pole on the ROW	Leased from the state	3	Requires relocation of the sign pole.
8	Private Land Fence	N: 36,977590 E: 42,652550	Mr Kareem	Metal fence around vacant land parcel, newly erected, excellent condition	Reported private	N/A	Compensation for fence of 450m length
9	Arcelik Company	E: 42,654433 N: 36,974378	N/A	Concrete warehouse with corrugated red/white tin roof and partial siding. Structure built at angle to the road with southern front corner close/in new ROW area. Surrounded by low cinder block wall, which would also be in new ROW. Newly erected fence encroaching on the proposed ROW	Leased from the state	3	Compensation for fence of 335m length
10	Marriage Hall	E: 29,1245 N: 40,94688	Mohammad Ismail Mohammad	The abandoned building, previously used for ceremonies, with the fence on the ROW	Reported private	N/A	Compensation for fence of 425m length



Figure 6-17: Evin Oil Gas Station




Figure 6-18: Junk Yards



Figure 6-19: Gersheen Company and Fuel Station



Figure 6-20: Efor Commercial Company



Figure 6-21: Bawer Fuel Station



Figure 6-22: Aven Tires and Repair Shop

6.8.3 Anticipated Development in the Area

Duhok Governorate is a highly urbanized area with approximately 70 % of the population living in cities. The population growth is 6.4 – 6.8 % over the past four years.

It is anticipated that by the year 2035 the population of the Governorate will increase almost by 5 %. The situation is exacerbated by the influx of refugees and IDPs due to the political situation in the region.

A Master Plan for Duhok is developed (see Figure 6-23). The first stage is till the year 2017 and the second stage till the year 2035. According to the Master Plan, the expansion of the residential built up area is not envisioned in the project area.




Figure 6-23: Master Plan of Duhok²⁹

Currently, there is no specific Master Plan developed for the Siemel District. However, in the interviews with the local administration it was stated that it is envisioned that the area will stay predominantly agricultural, with a low density commercial and light industrial development along the road alignment.

²⁹<http://www.slideshare.net/waheedamustafa/urban-manegement-final>

7 Project Impact Assessment

This chapter of the ESIA report discusses the potential impacts related to the road construction and operation.

During construction phase the anticipated impacts are essentially of two types: On-Site impacts arising from the physical construction activities within the ROW and Off-Site impacts arising from the related activities undertaken elsewhere, such as construction camps, fabrication yards

7.1 Impacts Scoping

The scoping of anticipated impacts was done using the Leopold Matrix. This matrix has: on the horizontal axis, the actions that cause environmental impact, and on the vertical axis, the existing environmental conditions that may be affected by those actions. This provides a format for comprehensive review of the interactions between proposed anthropogenic actions and environmental factors.

The scoping of project impacts requires the definition of two aspects of each action, which may have an impact on the environment.

The first is the "magnitude" of the impact upon specific parameters of the environment. The term "magnitude" is used here in the sense of degree, extensiveness, or scale. Magnitude (in the left upper corner) is presented on scale from 1 to 10, 1 being the least and 10 being the highest.

The second is the "importance," i.e., the significance of the proposed actions on the specific environmental characteristics and conditions. Unlike magnitude of impact, which can be readily evaluated on the basis of facts, the importance of impact is generally based on a value judgment. Importance was also presented on the scale from 1 to 10 in the lower right corner. The impacts that might have indirect impacts, such as contamination of the surface water resources and soil with consequent infiltration into the underground aquifers and pollution of the groundwater resources used for drinking purposes were given higher importance value. Also, the impact on species significant on local, regional or global scale is also considered as more important. The numerical values of magnitude (quantitative) and importance (qualitative) reflect the best estimates of the impact of each action.

The impacts scoping matrix is presented in Table 7-1.

Table 7-1: Impacts Scoping and Evaluation Matrix

		Pre-Construction		Construction																Operation and Maintenance						
Project Activity Parameter		Delineation	Land Acquisition	Site Clearance	Road Resurfacing	Workforce Camp	Asphalt Plant	Equipment and Machinery Encampment	Effluent Disposal	Solid Waste Disposal	Construction Debris Disposal	Excavation	Fill	Embankment	Access Road	Culvert	Heavy Vehicles Movement	Paving	Pedestrian Crossing	Underpasses	Traffic Movement	Maintenance	Accidents	Spills and Leaks	Total	
Physical	Topography/Landscape			52								62	62			62									238	
	Soil				83	82	72	72	72	74	84	97	86	86	86	66	76	86	85	41	62	51	64	51	74	14174
	Surface Water/Drainage			62	74	41	86	41	87	75	63	75	76	63	63	63	75	76	63	31	63	64	82	41	41	12770
	Groundwater			54	54	53	54	41	75	75	74	55	42	31	75	74	74	42	42	11	51	41	55	31	65	10367
	Air Quality			85	85	21	97	75	11	11	55	75	75	22	86	64	84	74	74	11	55	87	87	75	75	12290
	Noise and Vibration			51	61	11	75	51	11	11	11	62	62	51	31	11	51	73	74	22	22	51	61	11	11	8634
Biological	Flora			11	11	11	11	11	11	11	15	51	51	11	51	65	11	42	11	11		11	11	11	11	4126
	Fauna			11	11	11	11	11	11	11	15	51	51	11	51	65	11	42	11	11		11	11	11	11	4126
	Micro-habitats			55	51	42	55	65	65	65	75	75	41	65	95	75	55	41	75	31	55	22	55	55	84	10784
	Crops	87		72	51	11	11	11	11	11	52	64	44	41	51	51	41	51	11	11	11	11	11	11	11	6640
	Livestock Grazing	55		11	11	11	11	11	11	11	44	44	44	44	35	67	71	28	25	15	41	54	11	11	11	6146
	Migratory Birds			22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	4247
	Habitats Fragmentation			55	54	31	21	31	52	54	56	64	64	41	75	55	31	31	11	52	11	52	11	51	51	8552
Social	Land use	64	75	22	22	22	22	32	43	54	64	65	65	11	75	22	54	11		55			33			7561
	Structures and Fixed Assets	55	75	55	55																					1715
	Utilities		64	55	55																					116
	Disruption of Livelihood		75	44	44							75	53		85			44				53	65			4734
	Aesthetic value			52								64	52													168
	Health and Safety			54	54	54	54	54	54	54	54	54	54	54	54	54	54	54	87	87	57	54	54	54	54	11190
	Cultural/Historic/Religious Facilities and Amenities	11	11	11								11	11				11				11					55

The negative environmental and social impacts of the construction activities of the project are expected to be relatively minor to moderate and short-term. None of the identified negative impacts of individual construction activities was scored as particularly significant.

According to the scoping matrix, the project activities (construction phase) with the highest number of identified negative impacts are:

- Generation and disposal of construction waste;
- Operations of the construction camp;
- Site clearance and earthworks;
- Paving and operation of asphalt plant;
- Movement of construction machines and vehicles.
- Land acquisition.

The impact scoping exercise revealed that the potentially the key negative environmental and social impacts of the construction phase of the project are:

- Potential alteration of surface water courses;
- Increased level of soil erosion and potential soil contamination
- Dust emissions caused by earthworks;
- Impact on riparian habitats in the vicinity of seasonal run-off valleys and remnants of natural vegetation;
- Crop loss and reduced income level of local farmers;
- Disturbance to business activities due to restriction of access during construction;
- Potential tensions between the business operators and the construction crew due to the difficulty of access to the business facilities;
- Safety of road users and contractor's labor.

The social aspects related to encroachers on the ROW will be addressed through the implementation of a Resettlement Action Plan (RAP).

The following Sections provide detailed description of the most significant impacts.

7.2 Anticipated Impacts of Land Acquisition

Permanent land acquisition for the expansion of the ROW, construction of interchanges, lay-bys, culverts and underpass will have the following impacts:

Crop losses: It was estimated that approximately 80% of the agricultural lands subject to acquisition were planted at the time of the survey with cereals. Main crops in the area are cereals

(barley and wheat) with production rate of 690 – 840 kg/dunum and legumes (chickpeas and lentils) with production rate 500–590 kg/dunum³⁰. Estimated crop losses are about 138 tons.

Livestock grazing: although there are no specific designated areas for livestock grazing, land acquisition may potentially reduce the areas available for livestock grazing. This impact is estimated as minor.

Land loss: In total of 568,698 m² of land are to be acquired permanently for the project, 565,615 m² are used cultivation and grazing activities.

Fixed Assets: 1,897.5 m of fences including the block reinforced concrete will be acquired, 167.5 m² pertaining to the complete business relocation and 2,950 m³ of the traditional storage facility.

Disruption of public services and utilities: three electric poles require relocation, therefore, it is anticipated that there would be temporary disruption of electric supply.

Disruption of livelihood: One business entity, Aveen Tires will require relocation; the total area is estimated as 167,5m². The land acquisition of agricultural areas although not significant might potentially be detrimental to livelihoods of PAPs due to their dependence on agriculture as a primary source of income. It is estimated that 67.7 % of PAPs depend entirely on agriculture for their income.

The impact on **cultural, religious and historical sites** is considered negligible, since no such sites were identified during survey to be located on the ROW.

7.3 Anticipated Impacts during Construction Phase

7.3.1 Anticipated Impacts on Water Resources

Local alteration of water flow and drainage is likely to occur due to the construction of embankments and also due to the disposal of cut/debris material in rolling terrain. Temporary dislocation of existing drainage patterns is inevitable during road construction as cut and fill operations are undertaken. Adverse environmental impacts may include the following:

- Ponding, causing a threat to public health and safety, a concentration of nuisance insects and damage to surrounding soils and vegetation;
- Localized raising of water tables increasing risk of pollution and new surface waters;
- In extreme cases, flooding upstream of the construction activities causing damage to land, crops and property.

³⁰<http://www.fao.org/docrep/006/y9870e/y9870e07.htm>

Water contamination is relatively minor and generally limited to areas around bitumen coating plants, fuel storage tanks and similar facilities. Of potentially greater concern is the potential for spillages of chemicals and hydrocarbon products to pollute watercourses and eventually infiltrate into the underlying aquifers, thus causing pollution of the groundwater resources. However, should pollution occur it is unlikely to be of a magnitude that will seriously affect the present land uses adjacent to the ROW.

Another potential source of pollution is disposal of the raw sewage from the construction camp directly into the water courses as it is a common practice in the area.

Disposal of generated solid waste from the construction camp and construction debris on ad hoc basis as is also the common practice in the area may potentially be the source of groundwater contamination due to leaching of contaminants into the soil and eventually infiltrating into the aquifer.

7.3.2 Anticipated Impacts on Soil

Increased rates of **erosion and sedimentation**, especially in the vicinity of existing water courses may be the most severe impact. Increased erosion can be caused by:

- Installation of temporary discharge points in areas of substantial cut and fill.
- Clearance of the vegetation cover where exposure is over a long period and work is undertaken in rainy conditions.
- Cut and fill activities in unstable areas where the material is prone to erosion. Generally, newly cut slopes and land embankments are often very susceptible to erosion. Particular care will be required where cut operations intercept water tables, springs and other surface drainage features.
- Aggregate, fill and spoil heaps stored pending re-use and also highly susceptible to erosion due to their loose and unconsolidated nature.

As is the case with the water resources the soils in the vicinity of the ROW may be subject to pollution from accidental spillages of chemicals and hydrocarbon products and around the auxiliary facilities.

Loss of productive fertile soil is also identified as one of the moderate impacts on the soils in the area due to the excavation and temporary storage of soil.

7.3.3 Damage to Landscape

Construction sites are inherently unsightly and may impart substantial visual impact until excess soil and abandoned materials and equipment are cleared away on completion. Other temporary damage to the landscape may accrue from excessive ground clearance beyond ROW and other agreed working areas, such as borrow pits and waste disposal areas.

7.3.4 Anticipated Impacts on Traffic

The temporary impact during the period of construction will be primarily of two types:

- Complete but temporary closure and the diversion of all traffic;
- Partial closure with consequential delays and hold-ups.

At present the exact timing and duration of temporary and partial closures and the overall impact on the community is difficult to assess with any accuracy. The impact on vehicular traffic will generally be confined to increases in journey time and the costs associated with delays and use of a diversionary route.

7.3.5 Anticipated Impacts on Biodiversity

The physical earthworks and associated noise, dust and increased human activity associated with the construction sites frequently causes a temporary **reduction in biodiversity** even where the range of flora and fauna are able to re-establish themselves on completion of works albeit over several breeding/growing seasons.

The **impacts on flora** populations are associated with vehicle movements beyond ROW and other agreed working areas, and in some cases unplanned burning. However, the impact is considered low due to the absence of threatened or endangered species and ability of self-re-vegetation. Seeds caught up in stripped topsoil may remain dormant in spoil heaps until re-spread for final landscaping.

The **impacts on fauna** are estimated as more severe than on flora, in a range of moderate to high due to the fact that faunal species are less resistant to permanent derogation. Fauna may suffer reduction in biodiversity through destruction of dens, burrows and nests, clearance of feeding grounds, increased traffic kills and possible illegal hunting by off-duty construction workers. Especially sensitive to this kind of impact are migratory birds.

The disruption of wildlife movement and foraging patterns are also anticipated during construction phase.

Although the project area is developed for agricultural activities for a long period of time, there is a possibility of **habitat fragmentation** of the remnants of natural and semi-natural environments, which eventually might lead to decline in biodiversity in flora and fauna. However, this impact is considered as relatively low.

7.3.6 Anticipated Impacts on Air Quality

Dust is likely to have a rather serious impact than emission gases during the construction stage due to the large volumes of excavation and earth moving with heavy equipment in mostly dry conditions. Other dust generating construction activities include stone crushing operations,

handling and storage of sand and aggregates in the asphalt plants, concrete mixing plants and due to the movement of aggregates. The impacts of dust will mostly be concentrated on the construction sites and stone crushing sites. The impact of dust will spread downwind of the site for a considerable distance of up to 1000 m on windy days.

Another factor that will impact the air quality will be the **exhaust emissions** of the construction machinery and auxiliary vehicles movement. During the construction stage, negative impacts on air quality will be temporary and will affect the health of construction workers. However, since the new road alignment was defined to avoid proximity to settlements as much as possible, there are relatively few sensitive receptors close to the road alignment or within direct impact area.

7.3.7 Noise Impacts

According to the Environmental Protection Agency (EPA) standards, the maximum acceptable L_{eq} are summarized in Table 7-2. The maximum permissible noise limits, in terms of equivalent continuous noise level dB (A), for different areas set by the Jordanian Ministry of Environment (1997) are presented in Table 6-2 in Chapter 6.

Table 7-2: EPA Maximum Acceptable L_{eq} (2005)

Location	Effects	Maximum L_{eq}	Time of the day
Bedroom	Sleep disturbance annoyance	30	Night
Living room	Annoyance, speech interference	50	Day
Outdoor classroom	Moderate-serious annoyance	50-55	Day
Outdoor living area	Sleep disturbance, with open windows	42	Night
School classroom	Speech interference, communication disturbance	35	Day
Hospitals patient room	Speech interference, communication disturbance	30-35	Night and day

During the construction phase there will be unavoidable noise and vibration generation due to the operation of various types of equipment, and due to rock blasting at certain locations. The typical noise levels, in dB(A) at 5m, 20m, and 50 m distance from the noise source, associated with the corresponding construction equipment are presented in Table 7-4. Table 7-3 summarizes noise levels from the equipment expected with the various types of activities at different construction stages.

Table 7-3: Noise Emission Levels dB(A)

Type	Distance between Equipment and Recipient		
	5m	20m	50m
Loader	90	78	70
Grader	90	78	70
Vibration Roller	86	74	66
Bulldozer	86	74	66
Sprayer	87	75	67
Generator	98	86	78
Impact drill	87	75	67
Impact piling	112	100	92
Concrete mixer	91	79	71
Concrete pump	85	70	62
Pneumatic hammer	84	86	78

Table 7-4: Noise Emission Levels dB(A) of Construction Equipment

Clearing		Structure Construction	
Bulldozer	80	Crane	75-77
Front End Loader	72-84	Welding Generator	71-82
Jack Hammer	81-98	Concrete Mixer	74-88
Crane with Ball	75-87	Concrete Pump	81-84
		Concrete Vibrator	76
Excavation & Earth Moving		Air Compressor	74-87
Bulldozer	80	Pneumatic Tools	81-98
Backhoe	72-93	Bulldozer	80
Front End Loader	72-84	Cement and Dump Trucks	83-94
Dump truck	83-94	Front End Loader	72-84
Jack Hammer	81-98	Dump truck	83-94
Scraper	80-93	Paver	86-88
Grading and Compacting		Landscaping & Clean-Up	
Grader	80-93	Bulldozer	80

It is expected that during the construction stages the noise levels will be exceeding the EPA standards. However, since the construction stage is temporary and recipients live at a distance of 2 km from the alignment, noise would not be a major deterrent for the project.

7.3.8 Waste Generation and Disposal

During construction phase the main sources of liquid waste generation are:

- Sewage from offices, accommodation blocks and canteens;
- Wastewater containing high suspended solids;
- Oil residues and chemical fluids from washing of plant and vehicles;
- Waste oil, grease and de-greasing solvents from vehicle and plant servicing.

Oil residues, chemical fluids, waste oil and solvents are considered hazardous waste. Volume of hazardous waste is considered to be small and limited to servicing of vehicles and machines.

The main sources of solid waste are:

- Paper, discarded packaging and crates, redundant plant, used tires and broken or failed concrete products;
- Construction debris such as discarded materials from road resurfacing, unused excavated aggregate materials;
- Residential containing organic waste from construction camps (approximately 1.5 kg/person/day).

The main impact of the inadequate waste disposal is potential contamination of soil and surface water resources, and potentially contamination of groundwater by infiltration of contaminants into aquifer.

7.3.9 Resources Use

Significant granular material will be used in the project for road sub-base and as primary constituent of concrete. The estimated quantities are presented in the Annex 2. The aggregate materials are available from the existing private quarries located close to the Tigris River at a distance of approximately 30 km from the road alignment. The main risks associated with such facilities are:

- Increased heavy vehicular traffic on certain sections of the existing primary network and some local roads;
- The increase in HGV turning movements and the implications for the free flow of the existing traffic;
- Foreign matter such as mud and loose chippings being deposited on roads.

As has been mentioned previously the project will require substantial amounts of water for the provision of the water supply to the construction camp and yards as well as for the compaction of the fill. It is envisaged that water will be supplied from the privately owned wells located outside of the project area. The water haulage will mostly create the impact in terms of the vehicle movements similar to the haulage of materials from the borrow pits and quarries.

7.3.10 Construction Camp Impacts

The area of construction camp is approximately 1,350 m². The camp is located on the vacant public property land in agreement with the local beneficiaries. The main construction camp consists of barracks for offices, parking for employees' vehicles, canteen, storage facility and the prayer area. The machinery and equipment used for construction are placed in vacant areas within the ROW. The construction camp facilities if not adequately managed might potentially be detrimental to the environment. The impacts of the construction camp are considered as moderate and limited in magnitude and duration. The construction camp activities, which can cause an impact, are:

- Housing of construction crew and canteen;
- Storage of construction materials;
- Parking lot and maintenance area for the construction machinery and equipment;
- Septic tank for the housing and canteen and disposal of sewage;
- Accidental spillage of hazardous materials;
- Accumulation of discarded and excessive materials;
- Accumulation of construction debris and residential solid waste.

The most significant impact of the construction camp is potential soil contamination and consequent contamination of shallow aquifer.

7.3.11 Impacts on Cultural, Religious and Historic Heritage Sites

Batil cemetery is the only site located in the vicinity of the road alignment. However, the road design and construction plan isolate any activities from the cemetery. Therefore, direct impacts are not expected. However, chance finds are possible in the vicinity of the Batil cemetery.

7.3.12 Public Safety

The risk to public safety in both physical and the types of risk posed will be substantial. Areas of most danger to public include:

- Where heavy plant and heavy equipment are moving in and out of contractor's yards;
- The sites of excavation, particularly before they are stabilized;
- Where heavy plant and equipment are moving around interchange and road crossing sites;
- At storage areas for construction materials, fuel and surplus spoil.

There also will be increased risk of traffic accidents where diversions from established routes are imposed or altered without adequate warning. There is also the probability for unauthorized use of the ROW for local access and at night.

7.3.13 Worker's Safety

All construction sites are inherently unsafe. The substantial risks to public safety as discussed above are limited by occasional and casual acquaintance the public will generally have with the proposed construction activity. For those employed on the project the risks are more varied and omnipresent.

However, the risks to workers on construction sites are well understood and documented and providing normal, internationally accepted Health and Safety procedures are followed, they are easily minimized.

7.3.14 Disturbance to Local Settings

During the construction phase it is anticipated that there would be some disturbance to local settings, such as:

- Restricted access to the business activities;
- Interrupted provision of public utilities and services;
- Restriction of movement of livestock which is normally wanders freely over the area;
- Difficulties and extended time to travel to access urban centers and medical centers;
- Disruption of the food assistance delivery services due to the restriction of access during certain periods.

7.4 Anticipated Adverse Impacts during Operational and Maintenance Phase

This section of the report discusses the potential traffic-related environmental impacts that may accrue during the operation and maintenance of the road.

7.4.1 Air Quality

The degradation of ambient air quality might have a detrimental effect on human health affecting respiratory, cardiovascular and nervous systems. However, it must be noted, that there are no residential settlements in the vicinity of the road alignment of Segment 2.

Environmental effects of the vehicle emissions include acidification of soil and surface waters, adverse effects on crops and animal species, and damage to buildings and structures.

During the operational phase the main impacts on the ambient air quality are expected to be from the traffic using the road. Traffic types include short distance trips, long distance traveling and goods transportation with cars, public transport vehicles and small, large and heavy trucks.

The air pollution model MOVES (Motor Vehicle Emission Simulator) has been proposed for estimating anticipated air emissions from mobile sources during the operation of the highway. MOVES was developed by the USA Environmental Protection Agency to cover wide range of vehicles. The software has a huge capability of estimating emission for different scales (country, governorate, and small areas).

MOVES model was used for predicting emission for the Segments 2 and 3 of the Road no. 2.

Input data. The following type of data were needed for the model

- 1- Geographical descriptions
- 2- Traffic data
- 3- Fuel type
- 4- Components of the vehicles fleet
- 5- Age and distribution of the vehicles age.
- 6- Climate data

The following data were obtained from the traffic study:

Table 7-5: Traffic Data

Type	Articulated trucks	Trucks	Buses	Medium goods trucks	Cars
Number per day (2013)	1117	1683	31	852	6017
Number per day (2015)	1208	1820	34	939	6634
Number per day (2035)	2647	3989	91	2492	17601

MOVES used different nomenclature than names mentioned in the traffic study. Therefore, vehicle matching was performed between the traffic study and MOVES vehicles types:

Table 7-6: Vehicle Types

Traffic study name	MOVES name
Articulated trucks	Combinations short haul truck
Trucks	Single unit long haul truck
Buses	Transit Buses
Medium goods trucks	Light commercial trucks
Cars	Passenger cars

Assumptions:

- According to the traffic study, Segments 1 and 2 are connected, therefore the traffic volumes were assumed the same for the two segments;
- Fuel type used for these vehicles is Gasoline for Passenger cars and Diesel for other cars;
- Registered vehicles in the area are considered relatively new; traffic fleet is assumed to be less than 10 years old;
- Cruising speed was taken as 100 km/hr;
- Service roads during the construction phase they will be heavily used (about 80% of the traffic will use service roads). During operation, a maximum 10% will use service roads.

Scenarios

Different scenarios will be used in predicting air emissions:

1- Peak Hour Traffic

2- Increase in traffic by 100%.

3- Vehicles emissions during worst air stability conditioning

Scenario 1: Peak Hour Traffic

The model output of emissions of traffic for the year 2013 was used as an assumption for the baseline ambient air quality data. Emissions during the peak hours are considered the highest. Therefore, peak hour traffic was calculated using a transformation factor applied on the Average Annual Daily Traffic (AADT). A factor of 20% was chosen. Emission results from MOVES are shown Table 7-7.

Table 7-7: Scenario 1

Source	CO (g/mi)		Formaldehyde (g/mi)		NOX (g/mi)		PM (g/mi)	
	Model Output	EPA Emissions Standard	Model Output	EPA Emissions Standard	Model Output	EPA Emissions Standard	Model Output	EPA Emissions Standard
Passenger Car	7.091	3.4	0.000	0.015	0.254	0.4	0.004	0.04
LDV Standards	4.4	4.2	0.018	0.018	0.3	0.4	0.04	0.08
Medium Goods Trucks	0.796	1.7	0.007	0.022	2.535	0.8	0.058	0.08
Bus	0.790	2.2	0.021	0.027	12.322	3.8	0.249	0.5
Truck	0.822	2.5	0.017	0.022	12.205	3.8	0.143	0.5
Articulated Truck	0.784	6.4	0.016	0.035	12.282	3.8	0.327	0.5
HDV Standards	7.3	7.3	0.032	0.035	0.2	1.5	0.02	0.5
Aggregate	21.983	29.5	0.111	0.174	40.098	14.5	0.841	2.2

LDV: Light duty vehicles

HDV: Heavy duty vehicles.

Results show that the CO emissions from passenger cars will exceed the EPA standards, while the remaining parameters will be in compliance with the standards. On the other hand, trucks and other vehicles that run on diesel will exceed the NO_x and PM standards and comply with CO and Formaldehyde.

Scenario 2: 100% increase in traffic

In this scenario, emissions were estimated based on a projected increase of 100% in traffic volumes. Results from MOVES for this scenario came out as follows:

Table 7-8: Scenario 2

Source	CO (g/mi)		Formaldehyde (g/mi)		NOX (g/mi)		PM (g/mi)	
	Model Output	EPA Emissions Standard	Model Output	EPA Emissions Standard	Model Output	EPA Emissions Standard	Model Output	EPA Emissions Standard
Passenger Car	7.091	3.4	0.000	0.015	0.254	0.4	0.004	0.04
LDV Standards	4.4	4.2	0.018	0.018	0.3	0.4	0.04	0.08
Medium Goods Trucks	0.798	1.7	0.007	0.022	2.545	0.8	0.055	0.08
Bus	0.779	2.2	0.021	0.027	12.322	3.8	0.249	0.5
Truck	0.822	2.5	0.017	0.022	12.203	3.8	0.143	0.5
Articulated Truck	0.784	6.4	0.016	0.035	12.282	3.8	0.327	0.5
HDV Standards	7.3	7.3	0.032	0.035	0.2	1.5	0.02	0.5
Aggregate	21.974	29.5	0.111	0.174	40.106	14.5	0.838	2.2

The results indicate similar results from 100% traffic increase to the results from peak hour traffic. CO from passenger cars is expected to exceed the EPA standards while NO_x are expected to exceed the standards for heavy duty vehicles.

Scenario 3: The worst case

Simulation was conducted for the worst traffic and weather conditions. Vehicles are assumed to be in a status of extended idle condition with a very low cruising speed. In addition, poor weather conditions were assumed. Results from MOVES came as follows:

Table 7-9: Scenario 3

Source	CO (g/mi)		Formaldehyde (g/mi)		NOX (g/mi)		PM (g/mi)	
	Model Output	EPA Emissions Standard	Model Output	EPA Emissions Standard	Model Output	EPA Emissions Standard	Model Output	EPA Emissions Standard
Passenger Car	35.453	3.4	0.002	0.015	1.313	0.4	0.012	0.04
LDV Standards	4.4	4.2	0.018	0.018	0.3	0.4	0.04	0.08
Medium Goods Trucks	3.982	1.7	0.037	0.022	13.005	0.8	0.153	0.08
Bus	3.927	2.2	0.083	0.027	63.148	3.8	0.665	0.5

Truck	4.112	2.5	0.085	0.022	62.525	3.8	0.583	0.5
Articulated Truck	3.919	6.4	0.081	0.035	62.919	3.8	0.978	0.5
HDV Standards	7.3	7.3	0.032	0.035	0.2	1.5	0.002	0.5
Aggregate	63.093	29.5	0.338	0.174	203.41	14.5	2.433	2.2

Results indicate significant limits exceeding under such an extreme conditions. Formaldehyde and PM will remain within limits for passenger cars, and carbon monoxide (CO) will be under limits for heavy duty trucks.

Current information indicates that the closest village and inhabited areas are at least 3 km away from the project. Such distance should be enough to disperse emissions from vehicle and have near no harm on the village. However, close habitats may be affected.

7.4.2 Noise and Vibration

In Duhok, there was no available database of historic traffic noise data on major highways. Since noise level measurements were not available, and in order to estimate the expected noise levels upon the operation of segment 2, a noise prediction model was used. The input of the model included Duhok climatic data as well as the projected traffic data. The traffic data included vehicle classification, speed of vehicles, as well as pavement surface conditions and characteristics.

Temperature is important since it affects the speed of sound. Heat, like sound, is a form of kinetic energy. Molecules at higher temperatures have more energy, thus they can vibrate faster. Since the molecules vibrate faster, sound waves can travel more quickly. In Duhok, mean minimum temperatures measured during 2003-2012 in January (3.44 °C) and the highest monthly average temperature in July (41.4 °C). The average temperature for the ten years period was 20.75 °C.

The speed of sound is also affected by other factors such as humidity and air pressure. The prevailing wind direction at the project area is South-East and sometimes tends to South-West and North-West. Wind speed is generally of light to moderate value with wind speeds between 0.74m/s at times in November and 1.20m/s at other times April to July.

The output of the model was L_{eq} of 56 dB(A) and 49 dB(A) during the day and night, respectively. It is worth noting that the right-of-way of the highway is 100m, and closest recipients are within at least 2 km from the highway alignment. The noise level at this distance is expected to be 40 dB(A) and 32 dB(A) during the day and night, respectively. These levels are acceptable and within the EPA standards. In conclusion, noise would not be considered a major environmental impact of the project.

Vibration due to traffic takes the form of a low frequency disturbance that produces physical movement in buildings and their occupants that can be transmitted through the air or the ground. The frequency of air born traffic vibration is typically less than 200 Hertz, with the dominant frequencies 50 – 100 Hz. Ground born vibration produced by interaction between wheels and the

road surface is typically of lower frequency, 8 – 20 Hz. Poor road condition is the prime factor in determining the susceptibility of buildings to traffic vibration which will not apply to the newly constructed road.

The UK's Department of Transport recommends assessments of impacts due to increased vibration use the same indicators used for assessment of noise. In the absence of any other standard, analysis in respect of the Segment 2 has followed this approach. Vibration impacts are therefore assumed to be identical to those from noise and thus equally limited.

7.4.3 Impacts on Water Resources

All watercourses in the region are seasonal and there is little potential for pollution since contaminants will be dispersed or captured between flow events. An average annual daily traffic flow is estimated well below 20 000 vehicles/day threshold for significant highway pollution from normal runoff following rainfall events.

Water levels and the nature of geological strata in the project area do not promote contamination of ground water by normal runoff.

Water resources and soil contamination is probable due to accidental spills of hazardous materials.

7.4.4 Impacts on Biodiversity

Physical separation by road structure will potentially have the following impacts:

- Habitat fragmentation;
- Incidents of road kill of wild animals.

These impacts are anticipated to be low due to the fact that the area has been developed for millennia and there are only few remnants of natural habitat. Also, there are no habitats of specific importance in the project area.

As far as the birds population, there are two local bird species listed in the IUCN Red List: Finsch's Wheatear (*Oenanthe finschii*) – winter visitor, and Corn crake (*Crex Crex*) – passage migrant. Both species are listed as being of least concern due to their large population elsewhere. The habitat for the Corn crake is high grass – hence it is extremely unlikely that this species is found in the vicinity of the project, which is heavily used for agriculture. The Finsch's Wheatear feeds on insects. Its population may be disturbed by elevated noise levels.

7.4.5 Public Safety

The major concerns for public safety during the operational stage are:

- Traffic accidents: the majority of accidents are caused by driver error or the actions of the pedestrians and relatively few by the road infrastructure; there is nevertheless a relationship

between accidents and design weaknesses, poor road information and similar factors. The use of appropriate design standards and signage will ensure the required standard of safety is met.

- The transport of hazardous materials poses a potential risk to people and the environment in the event of the accident. Specific emergency response procedures need to be developed for effectively dealing with accidents involving potentially hazardous materials.
- Potential for accidents involving pedestrians and livestock

7.4.6 Landscape Maintenance

The main cause of concern in respect of the maintenance of the landscape planting is the use of chemical fertilizers, pesticides and herbicides, causing damage to flora and fauna, and to the public and to maintenance workers. However, the impacts of landscape maintenance are expected to be low.

7.4.7 Highway Maintenance

Two primary sources of potentially adverse impacts arising from highway maintenance are waste disposal and accidents involving maintenance workers and/or traffic flow modifications during road maintenance.

The potential in respect of waste disposal is primarily due to the often heavily contaminated material removed during drain clearance operations, which will need to be disposed of appropriately.

The risk of accidents can be greatly reduced by effective planning of activities, including adequate use of warning signs and site supervision.

7.5 Potential Benefits/Positive Impacts

Among the benefits to the population and businesses of the area are:

- Ease of access: currently the area is not serviced by healthcare and educational facilities and access to the main urban centers is restricted due to the condition of the road. Road upgrading will improve the access to the urban centers. This is also important for the businesses in the area – the road will improve their access to the main markets.
- Business Development Opportunities/Secondary Induced Development: rest houses and coffee shops could be established along the road targeting the drivers going through the area.
- Employment Opportunities: due to the induced development it is anticipated that there would be creation of employment opportunities for the local residents.
- Due to the improved access to the residential areas, there is a possibility of the increase of the privately owned real estate value.

In addition, induced development is expected to generate significant benefits in the following areas:

- Improved road safety.
- Improved infrastructure facilities, including improved sewerage system, water and electricity supply.
- Stimulate investment and industrial expansion.
- Provision of the underpasses for livestock movements.
- Businesses along the newly proposed roadside will experience larger stopping areas, improved ease of access for clients, and decreased traveling time to central city markets and supplies. These advantages will increase roadside property values.
- Landscape enhancement through planting of trees along the road alignment.
- The newly proposed road will offer a conduit between the newly commenced Duhok International Airport, Southern Kurdistan, the broader Iraq community, and Turkey.
- Economic benefits in terms of reduced time to travel and consequently reduction of fuel consumption.

7.6 Indirect and Cumulative Impacts

Generally, new roadways encourage new or additional development, in large part, because of the improvements in accessibility they provide. The induced development is viewed as positive impact in terms of economic growth; however, the induced development can potentially have negative environmental impacts.

7.6.1 Indirect Impacts

Indirect impacts are defined as “caused by the action and are later in time or farther removed in distance, but are still reasonably foreseeable”.

The construction activities such as transportation of materials, excavation, fill, clearance contribute to dust generation and vehicle and equipment emissions which settle on soils and in run off during dry season consequently contributing to the transport of sediments and pollutants to the main water bodies and infiltration into the shallow aquifer.

Inadequate waste management and accidental spills of hazardous materials could potentially have an impact on the groundwater quality. The impact is exacerbated by inadequate waste management practices in the project area.

Difference in land use is equivalent to the direct project impacts; thus, the indirect land use impacts are negligible in terms of total area and involve minor changes in agricultural patterns. The induced development might potentially involve change from agricultural to low density commercial/industrial development.

Road construction and operation might have a minor impact on permanent vegetated habitat loss.

7.6.2 Cumulative Impacts

Cumulative impact is defined as “the impact on the environment which results from the incremental impact of the action when added to other past, present, and reasonably foreseeable future actions”.

The main causes of the cumulative impacts are:

- Increase of impervious surfaces: road pavement and increase in built up area due to the induced development;
- Increase of traffic flow;
- Dramatic increase of population, in addition to the population growth in the area there is a significant influx of refugees and IDPs.

The main cumulative impacts are:

- Increases in impervious surface have a direct effect on water storage and flow in a watershed. As the amount of impervious surface increases, runoff increases in velocity, quantity, temperature, and pollution load. In addition, impervious surfaces prevent natural pollutant filtering by preventing percolation. Impacts in one area can potentially have a water quality effect downstream.
- Land use and farmland conversion: induced development will contribute to the change of agricultural land use to the low density commercial/industrial mix alongside the road alignment.
- Incremental effect of construction waste disposal on waste management in the area.
- Incremental impact on habitat fragmentation.

7.7 Irreversible Impacts

Irreversible impacts are defined as “Uses of nonrenewable resources during the initial and continued phases of the project may be irreversible since a large commitment of such resources makes removal or use thereafter unlikely. Primary impacts and, particularly, secondary impacts (such as highway improvements which provide access to a previously inaccessible area) generally commit future generations to similar uses. Also irreversible damage can result from environmental accidents associated with the project”.

Nonrenewable resources generally include biological habitat, agricultural land, mineral deposits, water, and some energy sources.

Growth inducing effects of the proposed project at the local level could result in long-term commitment of resources to urban development.

Relatively minor impacts would occur to previously disturbed habitats, non-native vegetation communities and agricultural lands. These environmental changes are considered irreversible, but not significant.

The approved alignment alternative would result in the permanent acquisition of approximately 350 ha of agricultural lands. Within the acquired lands there are relatively small remnants of natural and semi-natural habitats. Additionally, the long-term use of the road will have the impact on air quality and noise.

The irreversible impacts are considered minor and include:

- Change of land use pattern;
- Habitat fragmentation;
- Impact on air quality and noise.

7.8 Alternatives Evaluation

As stated in the ToR for the project there would be no alternative road alignments and major changes to the proposed design. The evaluation of alternatives was done in comparison of the proposed development and “zero” or “no project” alternative. The criteria developed for the alternatives evaluation is based on the impacts’ severity.

Table 7-10: Criteria for Impacts Evaluation

Severity of Impact	Value
Minor negative	-1
Minor positive	1
Moderate negative	-2
Moderate positive	2
High negative	-3
High positive	3
Negligible or no change to existing situation	0

Alternatives evaluation in terms of the anticipated impacts on the different environmental and socio-economic parameters is presented in Table 7-11.

The proposed development will potentially have negative impacts during construction phase, which are limited in the magnitude and duration. However, the benefits of the road expansion in terms of the secondary induced development, improved accessibility and improved public health and safety outweigh the negative project impacts.

The “no project” alternative will not provide additional socio-economic benefits or at a very minimal level, and potentially detrimental to public safety due to the number of road accidents as a result of inadequate road condition. In terms of impacts on the environment they are almost the

same as the road expansion alternative and in some cases more severe, such as impact on surface water resources owing to the poor condition of the.

The construction of the clover-leaf intersection for the traffic diversion will facilitate minimization of the traffic congestion thus contributing to minimization of the air pollution due to traffic emissions.

Culverts and underpasses are envisioned to provide positive impacts in terms of containing the water flow thus reducing the risk of flooding and soil erosion. Also, the underpasses will enable safe crossing by livestock and wild animals. Thus, the culverts will reduce the habitat fragmentation.

Table 7-11: Alternatives Evaluation

Parameter	Key Issue	Road Alignment		Design Features		
		Proposed Road Alignment	“No Project” Alternative	Road Expansion with no additional design Features	Elevated Clover-leaf Intersection	Culverts and Underpasses
Physical Environment	Noise	0	0	0	0	0
	Dust and Emissions	-1	-2	-3	0	0
	Landscape	0	-1	-1	1	2
	Water resources	-1	-2	-2	1	3
Biological Environment	Pressure on flora and fauna	-1	-1	-1	0	1
	Habitat fragmentation	-1	-1	-1	0	1
Socio-Economic Environment and Settings	Land acquisition	-2	0	-2	-1	0
	Employment opportunities	2	1	0	0	0
	Services/Utilities	2	1	0	0	0
	Accessibility	3	-1	0	0	0
	Secondary induced development	2	1	0	0	0
	Economic benefits (reduced time to travel)	2	-2	0	2	1
Cultural, religious, historic sites	Potential destruction of archeological sites	0	0	0	0	0
Health and safety	Traffic accidents	2	-3	-2	3	3
Total Aggregate		7	-8	-12	6	11

8 Mitigation Measures

8.1 Design Features

Detailed design represents a major opportunity to minimize adverse environmental impacts through appropriate route selection in delineation of the centerline for the proposed road alignment.

Careful route selection has ensured that the final ROW does not intercept any known archeological remains and the land acquisition for the project is minimized.

The design takes into consideration the main seasonal water bodies and their flow, and culverts have been located and sized to minimize the impact of the new road.

Embankment slope angles, the degree of compaction and use of the materials have been determined by reference to internationally accepted standards.

Safety features incorporated into the design include a median New Jersey Barrier to separate vehicles travelling in opposite directions and the provision of basic infrastructure for future pipeline and cable crossings, and for future installation of lighting and emergency warning signs.

The design also provisions for ensuring the safety of livestock crossing by the design of the designated underpass.

8.2 Mitigation of Land Acquisition Impacts

The exact procedures for mitigation of land acquisition impacts are described in detail in the RAP report. The summary of mitigation measures is:

- Cash compensation for the loss of 138 tons of crops.
- Cash compensation at the replacement cost for business entity (Aveen tire shop of 167.5 m²). In addition, the business owner will be compensated with another piece of land after completion of construction. Further, he will be assisted in obtaining business license.
- Cash compensation for the loss of fixed assets.
- No monetary compensation for the loss of agricultural land as the land is state owned.
- Additional financial assistance to vulnerable PAPs

8.3 Construction Impacts Mitigation

The majority of construction-related impacts is temporary and can be mitigated through good construction practice and effective site supervision.

8.3.1 Damage to Landscape

The contractor shall exercise care to preserve natural landscape and conduct their operations so as to prevent any unnecessary destruction, scarring or defacing of the natural surroundings in the vicinity of works:

- All trees, native shrubbery and vegetation should be preserved and protected from damage by equipment and operation, except where clearing is required for works;
- Movement of crews and equipment should avoid damage to property, productive lands and known sites of historical and archeological importance;
- In case where the excessive destruction of landscape, natural vegetation or productive lands has occurred, the contractor is responsible for correcting at his own expense.
- Upon completion of the works, all surplus equipment and materials to be removed and all work areas smoothed and graded to conform to the natural appearance of the surrounding landscape.

8.3.2 Mitigation of Impacts on Biodiversity

To minimize damage to the biodiversity a combination of measures are required:

- Avoid the movement of construction traffic at night;
- Reduce noise levels by regular maintenance of construction machines and equipment;
- Confine traffic to defined routes;
- Using only defined and approved liquid and solid waste disposal sites;
- Extracting gravel and other materials only from approved sites;
- Providing training to the construction crew on the impact of disturbance and damage to habitats;
- Ensure the Terms of Employment include penalties for unnecessary disturbance to environmentally significant sites and hunting and enforce such penalties;
- Providing the crew and the construction camp with the fuel for heating and cooking to avoid their use of lighting of fires for such purposes;
- Provision of safe conduits, such as underpasses for livestock and wildlife crossing.

8.3.3 Mitigation of Impacts on Water resources

The contractor shall comply with all applicable regulations concerning the control and abatement of water pollution. All activities shall be performed in a manner that will prevent the entry or accidental spillage of solid matter, contaminants, and debris into watercourses.

- Vehicle used during construction/ maintenance phases should be well maintained to reduce emissions, be free of leaking fluids and be covered to reduce/prevent spills.
- Removing or minimizing side casts.
- Applying upgraded surfacing.
- Allowing time restrictions during rain events.
- Disconnecting road sediment sources to watercourses through use of rolling dips, water weirs and filter strips.
- Use of sufficient drainage structures to minimize run-off in inside ditches.
- Regular disposal of solid and liquid waste.
- In order to avoid the natural runoff pattern alteration, the placement of excavated material should be avoided in the areas of the runoff routes.
- Provision of six adequate size culverts.
- Heaps and stockpiles of aggregate, fill and spoil should be located at sites that do not permit direct runoff into watercourses and are on land sloping at less than 1.5 %.
- In the event of accidental spill or contamination, the contractor shall immediately inform the GDRB. Any remedial works shall be undertaken a matter of urgency by the contractor. Failure to notify of such spills will be considered a Breach of Contract.
- Avoid storage of surplus materials on site and provide for regular disposal of all surplus materials.

8.3.4 Mitigation of Impacts on Soil

In order to minimize the soil erosion and contamination the following mitigation measures are proposed:

In order to minimize the soil erosion:

- Placement of drains to avoid cascading;
- Localized lining of receiving channels;
- Construction of sufficient discharge points;
- Avoid site clearance well in advance of construction. Maximum permitted elapsed time between site clearance and the initiation of construction should be 3 weeks.

In order to minimize the loss of the topsoil, the clearance procedures that separate topsoil, transport and store topsoil and possible transport to the re-use site should be adopted.

In order to avoid the soil contamination the same measures as for prevention of water contamination are to be applied as specified in section 8.2.3.

8.3.5 Abatement of Noise

Noise from construction activities will primarily be derived from the operation of plant and equipment:

- The contractor shall ensure all his equipment is fitted with noise muffing devices;
- Ensure plant operated intermittently is shut down or throttled down during idle periods;
- Any piling operations should be restricted to the hours 08.00 – 19.00 and not undertaken during public and religious holidays;
- All operations other than piling shall be restricted to the hours of 07.00 – 20.00.

8.3.6 Abatement of Air Pollution

In the conduct of construction activities and the operation of equipment, all practical methods and devices to control, prevent and otherwise minimize atmospheric emissions should be utilized:

- The methods of handling cement and pozzoloid should include means of eliminating atmospheric discharges;
- Proper and adequate maintenance of vehicles and equipment to ensure there are no excessive exhaust emissions;
- Burning of materials from clearance of trees, bushes and other combustible matter should be prohibited;
- Ensure the plant operating intermittently is shut down during idle periods.

Specific dust suppression measures include:

- Damping down of sites and not paved access roads;
- Provision of water troughs at entry and exit points to prevent carryover of dust emissions from sites;
- Establishing speed restrictions for all vehicles operating within sites and on unsurfaced access roads;
- Covering all vehicles transporting materials likely to give off excessive dust.

8.3.7 Waste and Sewage Management

Solid waste generated during construction activities consists of the construction debris, and the waste generated at construction camps. The solid waste should be transported to the existing landfill with an agreement of the landfill operators or otherwise, with the approval of the relevant authorities organize the burial site. Borrow pits and un-operational quarries could also be used for such purposes, provided that they pose no threat to the groundwater resources.

Hazardous wastes are expected to be generated in small quantities primarily from servicing and refueling of vehicles and construction machines. Oil residues, chemical fluids, waste oil and

solvents should be temporarily stored in sealed containers and placed on paved base with a sump, prior to final disposal.

Sewage generation and discharge is a concern. The main source of sewage generation is the construction camp. Therefore, it is proposed:

- Location of the camp outside known aquifer recharge zones;
- Provision of adequate infrastructure (septic tank) for sewage collection;
- Regular disposal of sewage: the problem is exacerbated by the absence of treatment facilities in the Duhok Governorate as whole; therefore, one of the solutions will be to discharge the sewage in the existing landfill site.

8.3.8 Mitigation of Construction Camp Impacts

As described above, the construction camp could pose a threat to environment in the project area. The following mitigation is suggested:

- Location of the camp outside known aquifer recharge zones;
- Provision of adequate infrastructure (septic tank) for sewage collection;
- Regular disposal of sewage;
- Regular disposal of solid waste;
- Provision of collection pits for collection of used machinery oils;
- Adequate vehicle maintenance;
- Transporting wastes to the designated disposal sites.

8.3.9 Mitigation of Construction Materials Transporting

The aggregate materials for the road construction is available from the existing quarries located near the Tigris river, approximately 30 km west of the alignment. The minor environmental impact is associated mainly with transporting of the materials.

The mitigation measures include:

- Establishing speed restrictions for all vehicles operating within sites and on unsurfaced access roads;
- Covering all vehicles transporting materials likely to give off excessive dust.

8.3.10 Mitigation of Impact on Cultural Resources

Chance find procedures will be used as follows:

- Stop the construction activities in the area of the chance find;
- Delineate the discovered site or area;

- Secure the site to prevent any damage or loss of removable objects. In cases of removable antiquities or sensitive remains, a night guard shall be present until the responsible local authorities and the Ministry of Culture take over;
- Notify the supervisory Engineer who in turn will notify the responsible local authorities and the Ministry of Culture immediately (within 24 hours or less);
- Responsible local authorities and the Ministry of Culture would be in charge of protecting and preserving the site before deciding on subsequent appropriate procedures. This would require a preliminary evaluation of the findings to be performed by the archeologists from the Dohuk Department of Antiquities (DDA) and the Ministry of Culture (within 72 hours). The significance and importance of the findings should be assessed according to the various criteria relevant to cultural heritage; those include the aesthetic, historic, scientific or research, social and economic values;
- Decisions on how to handle the finding shall be taken by the responsible authorities from the DDA and the Ministry of Culture. This could include changes in the layout (such as when finding an irremovable remain of cultural or archeological importance) conservation, preservation, restoration and salvage;
- Implementation for the authority decision concerning the management of the finding shall be communicated in writing by the Ministry of Culture; and
- Construction work could resume only after permission is given from the responsible local authorities and the Ministry of Culture concerning safeguard of the heritage.

These procedures must be referred to as standard provisions in construction contracts, when applicable. During project supervision, the Site Engineer shall monitor the above regulations relating to the treatment of any chance find encountered are observed.

8.3.11 Mitigation of Traffic Impacts

Mitigation of the impacts likely to accrue from construction traffic should primarily take three forms:

- Access control: will require restriction of turning movements to approved access points to and from existing highways and if necessary, improvements of the existing junctions to reduce potential for accidents. Restriction on timing of use may also be necessary, with construction traffic prohibited outside specified, supervised hours.
- Road clearing measures will be required to ensure major carriageways are kept in a safe condition, with oil, mud and other material removed regularly.
- Timing restrictions for transportation of abnormal loads.

8.3.12 Public Safety

For mitigation of impacts on public safety the following mitigation measures are proposed:

- All construction vehicles shall be appropriately marked and carry adequate visual and audio warning systems;
- Speed limitations on the work site vehicles;
- Adequate signage should be provided for motorists and pedestrians;
- Designate clearly marked areas for livestock crossing.

8.3.13 Workers Safety

The procedures for workers safety are well established and the contractor will be obliged contractually to follow them. Additionally:

- Provide training on First Aid Procedures
- Provide training on potential risks and hazards of construction;
- Provide the PPE and enforce its use.

8.3.14 Mitigation of the Impacts on Local Settings

Temporary restriction of access to the public utilities and services, impeded access to business activities and so on is unavoidable during the construction phase. The mitigation measures incorporate warning of the public of the planned activities so that can arrange their timing and routes and to restore access in the shortest time possible.

In order not to disrupt the operations of the businesses it is important that the entrance/exit ramps will be provided, as well as the relevant gaps in road barriers to facilitate the access to the business entities.

8.4 Mitigation of Impacts during Operational and Maintenance Phase

8.4.1 Mitigation of Impacts on Water Resources and Soil

It is anticipated that during operational phase the impacts on water resources and soil will be minimal. However, the blockage of the drainage systems and accidental spills of hazardous materials could prove to be detrimental. The main mitigation measures are:

- Maintaining the roads drainage systems;
- In case of the accidents involving the spill of hazardous chemicals and vehicle fuel, apply emergency measures for neutralization of chemicals and if necessary remove and replace the contaminated soil to the extent possible in liaison with the Civil Defense Department.

8.4.2 Mitigation of Noise

At present, due to the fact that there are no receptors in close proximity to the road, and the noise level reaching residential areas is way below acceptable limits, there are no specific mitigation

measures are required for noise abatement. However, in case in the future there would be residential settlements along the road, the sound barriers should be considered.

8.4.3 Mitigation of Impacts on Air Quality

In order to minimize the impacts of the traffic on the surroundings the trees and bushes forming the so called “green belt” should be planted on the road sides at a distance that would not create visual obstruction of signs and other roadway users, sight distance obstructions (at intersections, driveways, and curves), and an overhead hazard to large trucks. In order to avoid potential visual obstruction height restrictions on objects in the sight triangle, such as “no objects permitted between 30 and 96 inches above the ground” should be considered.

Also, at the national policy level the following measures should be considered:

- Introduction of regular vehicle testing;
- Incentive taxation for non-pollution vehicles;
- Tax incentives for use of cleaner fuels;
- Promotion of higher vehicle occupancies by vehicle sharing.

Emissions management strategies including ambient air quality monitoring program should be developed and implemented during operational phases.

The air quality monitoring program should encompass the following components:

- Monitoring parameters which should reflect the pollutants of concern;
- Monitoring type and frequency;
- Monitoring locations (off-site or fence line) based on the results of scientific methods and mathematical models;
- Sampling and analysis methods should apply national or international methods and standards for sample collection and analysis by entities certified for this purpose;
- Control measures for curtailing vehicular air pollution such as:
 - Apply the emission standards on the quantity or concentration of pollutants that discharged from vehicles;
 - Apply standards that specify fuel quality for motor vehicles;
 - Requirements to use a certain technology designed to reduce vehicle emissions
 - Traffic restrictions.

8.4.4 Mitigation of Impacts on Biodiversity

The habitat fragmentation by the motorway is unavoidable due to the presence of the road as physical barrier. However, the impacts for migrating animals will be minimized by provision of culverts that enable crossing of livestock and wild animals. Three underpasses (culverts) are design

for animal crossing. Their size (3x3m) is sufficient for crossing by livestock (sheep and goats), and Goitered gazelle sporadically found in the project area (the height of Goitered gazelle does not exceed 1,5 m). In addition, wild animals can cross down the wadis under the motorway bridges. The GDRB must make sure that the provided underpasses/culverts are in serviceable conditions and clear of accrued debris, especially after winter rains.

8.4.5 Mitigation of Landscape Maintenance Impacts

The mitigation measures include:

- Planning and preparation beforehand;
- Effective advance warning signs;
- Effective material handling, storage and use;
- Site supervision.

8.4.6 Mitigation of Potential Impacts on Public Safety

The road safety concerns are incorporated into the design, such as:

- Provision of a median concrete barrier, a New Jersey barrier that will run the full length of the road mainline;
- Provision of street lighting to reduce accidents at night and at times of reduced visibility;
- Provision of directional and warning road signage;
- Provision of the underpass for livestock crossing.

Additionally, the enforcement of proper road behavior will be required, which should be implemented by the traffic police.

8.5 Residual Post-Mitigation Impacts

Residual impacts are defined as the adverse effects that remain or are predicted to remain after all mitigation measures are applied. It is envisioned that the residual impacts will be minor and short-term during the construction phase.

8.5.1 Noise and Vibration

Application of restricted hours of operation and implementation of appropriate noise control measures during construction will ensure that the noise impact is kept to acceptable levels. Some exceeding is expected at properties directly facing the site works. Given the linear nature of works, the noise impacts will be short-term at any given area. No further mitigation measures are required.

The noise impact during operational phase is identified as minor due to the absence of residential areas. Therefore, the residual impact is identified as negligible. In case of further development of residential areas additional mitigation measures will be required, such as noise barriers.

8.5.2 Landscape and Visual Impact

The proposed road development by means of its very presence will have the permanent effect and consequently residual impact on the landscape within its immediate corridor. However, with application of the mitigation measures for landscape resoration the road will be integrated within landscape settings in the longer-term.

8.5.3 Ecology

The loss and fragmentation of habitats are unavoidable during road construction and have more or less permanent character, and consequently even with the application of mitigation measures will still be present. However, due to intensive agricultural development of the area there are practically no natural habitats left, and therefore, the impact is estimated as minor. Landscaping and re-vegetation will provide ecological continuity further facilitated by provision of mammal underpasses.

8.5.4 Soils and geology

In general, the residual impacts on soils are considered negligible with mitigation measures in place and do not require additional mitigation measures. Groundwater seepages may result in erosion and instability of slope over time. The significance of this residual impact is considered negligible.

8.5.5 Water Resources

The mitigation measures related to potential groundwater contamination will ensure that the risk of groundwater contamination is minimized. No residual impacts on groundwater are anticipated.

With mitigation measures in place related to surface water resources, the impacts on catchment areas, status of receiving surface waters, flood risk due to increased runoff, the residual impacts on surface water resources are considered negligible.

8.5.6 Air Quality

The impacts of the road construction on air quality are short-term and with the implementation of mitigation measures are envisioned to be moderate. During operation phase, the air pollution from transport emissions is permanent. However, due to the absence of residential areas it is considered as minor. No additional mitigation measures are required.

9 Environmental and Social Management Plan

In order to manage the Environmental & Social impacts in line with KRG policies, and policies of funding agencies for the project, an Environmental and Social Management Plan (ESMP) has been prepared. The ESMP contains management measures avoidance, mitigation, as well as enhancements that would be implemented during the construction and operation/maintenance phase of the project. ESMP also defines the monitoring parameters, frequency of monitoring and monitoring responsibility, as well as cost estimate of mitigation measures and monitoring where applicable.

It covers the measures on and near the highway right-of-way and also in the construction-related sites such as camps, asphalt mixing plants, equipment workshops, etc.

In addition to the ESMP, a Resettlement Action Plan (RAP) has also been prepared to ensure appropriate approach for involuntary resettlement of Project Affected People (PAP).

The Environmental and Social Management plan matrices are prepared for the proposed project during construction and operation /maintenance phases. The main element of ESMP is the cost of implementation, which shall be integrated into the contractor's cost.

Part of the mitigation measures included into the Environmental Management Plan are imbedded into the project design and procedures and therefore do not require additional investment. These are:

- Provision of the PPE for working personnel (responsibility of the contractor);
- Provision of warning signs for public safety;
- Provision of safe crossings for pedestrians;
- Provision of waste collection and disposal;
- Provision of monetary compensation for loss of income from agriculture.

The estimated costs of mitigation measures during the construction phase of the project reach 2,735,000 US \$. The mitigation measures during the operational phase of the project are limited to standard maintenance activities. Therefore, they are not specifically priced.

The ESMP monitoring costs during the construction phase are estimated at 76,500 US \$ (see section 9.3). They consist of the cost of environmental monitoring specialist, and the cost of tests. The annual cost of monitoring during operational phase is estimated at 11,800 US \$ (see section 9.3). The cost include 3,800 US \$ for testing, and 8,000 US \$ cost of environmental monitor input.

The responsibility for safeguards monitoring during the construction phase lies primarily with the GDRB and the Contractor. During the operational phase, GDRB will be in charge of monitoring.

Table 9-1: ESMP - Construction Phase

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
Land Acquisition	Loss of crops (approximately 138 tons of cereals).	Expansion of the ROW.	Monetary compensation for loss of crops At 800 US \$ per ton.	<ul style="list-style-type: none"> • Compliance with the land acquisition plan and disbursement of compensation. • Restoration of access to the resources. • Sufficient provision of the compensation budget. • Disbursement of transitional and other allowances as identified. • Registration records of grievance issues. • Records of communication with the local community. 	<ul style="list-style-type: none"> • First three months – once a week. • Following four months – bi-weekly. • The rest of construction period – monthly. 	PMT at GDRB. Compensation Committee.	Market value at the time of survey – 110,000 US \$	No additional environmental and social monitoring cost for the Contractor.
	Business relocation (Aveen Tire Shop – 167.5 m ²).	Land acquisition for underpasses, intersections, lay-byes, culverts.	Allowance to cover relocation of equipment, fixtures and inventory.				11,000 US \$	
	Fixed assets acquisition (total 1,897.5 m of fences).		<ul style="list-style-type: none"> • Compensation at replacement cost. • A combination of cash compensation at replacement cost and land-for-land replacement with a total value equivalent to the total valuation of the land to be acquired. 				103,164 US \$	
	Loss of agricultural land (total 568,615 m ²)		No monetary compensation – the land is state owned.				N/A	
	Livelihood disruption.		Monetary compensation for loss of crops at 800 US \$ per ton for the year after land Additional financial assistance to vulnerable PAPS.				Individual financial assistance to be reviewed case by case by GDRB.	

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
	Disruption of Services.	Relocation of four electric poles.	Restoration of services. Consider upgrading of infrastructure.				2 000 US \$	
Water Resources	Local alteration of water flow and drainage at locations: 1. N: 36.997206 E: 42.639803 2. N: 37.037690 E: 42.645715 3. N: 37.024310 E: 42.645715	<ul style="list-style-type: none"> Excavation. Disposal of construction debris in surface water courses. Uncontrolled run-off in ditches. 	<ul style="list-style-type: none"> Placement of excavated material and debris should be avoided in the areas of the runoff routes. Provision of sixteen adequate size culverts. Disconnecting road sediment sources to watercourses through use of rolling dips, water weirs and filter strips. Use of sufficient drainage structures to minimize run-off in inside ditches. 	Changes of water courses, placement of excavated materials, culverts compliance with design.	Bi-weekly during rainy season.	GDRB – monitoring and supervision.	1 970 705 US \$ for culverts construction.	No additional environmental monitoring cost for the Contractor.
	Potential contamination of surface water (same locations as the point above).	<ul style="list-style-type: none"> Leakage of hazardous fluids from construction machinery. Accidental spills of oils and petrol. Wash off of construction 	Vehicle used during construction/ maintenance phases should be well maintained to reduce emissions, be free of leaking fluids and be covered to	Visual observations of vehicle conditions, storage of materials, inspection of logbook, photographic evidence.	One time prior to construction to establish baseline. One time during construction during rainy	GDRB: monitoring and supervision.	No additional cost.	GDRB: 500 US \$ per test, total 6 water quality tests – 3 000 US \$ No additional environmental monitoring

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
		materials during rain events. • Inadequate storage of construction materials. • Inadequate disposal of liquid and solid waste at construction camp site.	reduce/prevent spills. • Removing or minimizing side casts. • Applying upgraded surfacing. • Applying time restrictions during rain events. • Heaps and stockpiles of aggregate, fill and spoil should be located at sites that do not permit direct runoff into watercourses and are on land sloping at less than 1.5 %. • Avoid storage of surplus materials on site and provide for regular disposal of all surplus materials. • Emergency response for accidental spills of hazardous materials.	Water quality parameters: pH, Turbidity, Electrical Conductivity (EC), Color, Total Suspended Solids (TSS), Total Dissolved Solids (TDS), Chemical Oxygen Demand (COD), Biological Oxygen Demand (BOD), Polychlorinated Biphenyls (PCBs).	season for each seasonal run-off			costs for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
Soils	Soil erosion (along the road alignment).	<ul style="list-style-type: none"> Site clearance Excavation/Cut operations. Inadequate drainage. 	<ul style="list-style-type: none"> Placement of drains to avoid cascading. Localized lining of receiving channels. Construction of sufficient discharge points. Avoid site clearance well in advance of construction. Reinstatement and after-use. 	<ul style="list-style-type: none"> Alteration of natural drainage systems and/or additional drainage channels observed, photographic evidence. 	Bi-weekly during the rainy season, and after sporadic rains. Duration between the site clearance and start of construction activities not to exceed three weeks.	GDRB – monitoring and supervision.	Cost of drainage systems (as specified above)	No additional environmental monitoring costs for the Contractor.
	Soil Contamination near the temporary storage site of fuel and liquid waste, and near the construction camp).	<ul style="list-style-type: none"> Accidental spills of hazardous materials. Leakage from construction machinery and stored construction materials. Inadequate disposal of liquid and solid waste at construction camp. 	Same measures as for prevention of surface water contamination.	Visual observation of spillages and leakages, photographic evidence, inspection of logbook. Soil parameters: pH, temperature, organic content, poly-aromatic hydrocarbons (PAHs); Faecal coliforms and Total coliforms.	Random soil test along the road alignment to establish the baseline. Soil tests immediately after any spillages of fuel and liquid waste. One random soil test after completion of works at locations of temporary	GDRB: monitoring. Directorate of MAW of Duhok: supervision.	No additional costs.	GDRB: soil tests: 1,500 US \$ total. No additional environmental monitoring cost for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
					storage of fuel and waste.			
	Loss of productive fertile soil (along the road alignment).	<ul style="list-style-type: none"> Site clearance. Excavation. 	<ul style="list-style-type: none"> Clearance procedures that separate topsoil. Transport and store topsoil and possible transport to the re-use site should be adopted 	<ul style="list-style-type: none"> Conditions of soil in the temporary prism storage. Approach to re-use of soil. 	Monthly	GDRB: monitoring and supervision.	No additional cost.	No additional monitoring costs for the Contractor.
Ecology and Biodiversity	Habitat fragmentation	<ul style="list-style-type: none"> Site clearance; Landscape alteration Inadequate disposal of solid waste and construction debris; Excavation. 	<ul style="list-style-type: none"> Avoid works on or near watercourses during rainy seasons. Provision of three underpasses for livestock and wild animals. Using only defined and approved liquid and solid waste disposal sites. Importing gravel and other materials only from approved sites. 	<ul style="list-style-type: none"> Habitat disruption due to construction activities. Number of animal kills. Provision of training for the workers on habitat fragmentation. Site restoration after work completion. Inspection of logbook, photographic evidence. 	Monthly	GDRB: monitoring. Directorate of Environment of Duhok: supervision.	538,525 US \$ for underpasses construction.	No additional environmental monitoring costs for the Contractor.
	Loss of trees and plant species.	<ul style="list-style-type: none"> Vehicle movements beyond ROW. Cutting down the trees and bushes to 	<ul style="list-style-type: none"> Providing the workers camp with the fuel for heating and cooking to avoid cutting of wood. 					

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
		be used for fuel and burning.	<ul style="list-style-type: none"> • Replanting of removed trees. • Confine traffic to defined routes. 					
	Loss of fauna species.	<ul style="list-style-type: none"> • Destruction of dens, burrows and nests, clearance of feeding grounds. • Increased traffic kills. • Possible illegal hunting by off-duty construction workers. 	<ul style="list-style-type: none"> • Limiting construction noise and vibration to day time hours. • Provision of underpasses for wild animals and livestock. • Training for construction crew on the impact of disturbance and damage to habitats. • Avoid works along watercourses during rainy season. 					

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
	Dust nuisance.	<ul style="list-style-type: none"> • Movement of vehicles on unpaved surfaces. • Excavation. • Transporting of cut materials and aggregate materials. 	<ul style="list-style-type: none"> • Water spraying of sites and not paved access roads. • Water troughs at entry and exit points to prevent carryover of dust emissions from sites. • Establishing speed restrictions for all vehicles • Covering all vehicles transporting materials likely to give off excessive dust. • Construction sequencing and disturbing only small areas at a time. 	<ul style="list-style-type: none"> • Dust abatement approach (visual observations, photographic evidence, logbook inspections). • Air quality parameters: PM10, PM2.5, SO2, TSP, NOx, CO, Ozone and HC 	Weekly monitoring of implementing of dust abatement measures. Air quality testing: <ul style="list-style-type: none"> • One time prior to construction to establish the baseline; • One time during construction (during dry season). 	GDRB: monitoring and supervision. Contractor – internal monitoring.	Cost of regular vehicles maintenance. Cost of water spraying of unpaved surfaces.	GDRB: outsourcing of air quality testing: 6 000 US \$ No additional environmental monitoring costs for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
Ambient Air Quality	Air pollution from emissions.	<ul style="list-style-type: none"> • Inadequate condition of construction machinery and vehicles. • Burning of combustible materials. • Burning of the vegetation from clearance. 	<ul style="list-style-type: none"> • Regular maintenance of vehicles and equipment to ensure there are no excessive exhaust emissions. • Burning of materials from clearance of trees, bushes and other combustible matter should be prohibited. • Ensure the machinery operating intermittently is shut down during idle periods. 					

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
Noise and Vibration	Increased noise levels that are potentially detrimental to human health.	Operating of construction machinery and equipment.	<ul style="list-style-type: none"> The contractor shall ensure that his equipment is fitted with noise muffing devices. Ensure machinery operated intermittently is shut down or throttled down during idle periods. Time restrictions of activities to the day-time working hours. Provision of PPE. 	<ul style="list-style-type: none"> Level of occupational noise. Operating conditions of vehicles and machines. Use of muffling and switching off machines during idle periods. Use of protective gear. Inspection of logbook. 	Bi-weekly	Contractor – internal monitoring. GDRB: monitoring and supervision.	Cost of PPE	GDRB: cost of noise level monitoring: 1,000 US \$ No additional environmental monitoring cost for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
Construction Camp	<ul style="list-style-type: none"> Potential soil contamination and consequent contamination of shallow aquifer. Temporary land acquisition. 	<ul style="list-style-type: none"> Storage of construction materials. Inadequate disposal of discarded and surplus materials. Inadequate disposal of construction debris. Spillage of machinery oils. Leakage of domestic sewage from septic tank. 	<ul style="list-style-type: none"> Location of the camp should be agreed with the local beneficiaries. Provision of septic tank for sewage collection and temporary storage. Regular disposal of sewage. Regular disposal of solid waste. Provision of collection tanks for collection of used machinery oils. Regular vehicle maintenance. Transporting wastes to the designated disposal sites. 	<ul style="list-style-type: none"> Disposal method of sewage and solid waste. Approach to storage of construction materials. Vehicle maintenance. Contaminants in soil as specified above. Inspection of logbook. 	Bi-weekly	Contractor – internal monitoring. GDRB: monitoring and supervision.	No additional costs	No additional environmental monitoring costs for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
Waste Management	Potential soil contamination and consequent contamination of shallow aquifer.	<p><u>Liquid waste:</u></p> <ul style="list-style-type: none"> • Sewage from construction camp. • Oils, chemical fluids, grease and de-greasing solvents. <p><u>Solid waste:</u></p> <ul style="list-style-type: none"> • Construction debris; • Discarded and surplus construction activities. 	<ul style="list-style-type: none"> • Hazardous liquid and solid waste should be stored in sealed containers. • Regular disposal of liquid and solid waste at designated sites. • Avoid placing of construction camp and construction material storage areas in close proximity to aquifer recharge areas. 	<ul style="list-style-type: none"> • Approach to temporary storage of benign construction waste prior to final disposal. • Use of designated waste disposal sites. • Inspection of logbook. 	Weekly	GDRB: monitoring and supervision.	Cost of transporting the waste.	No additional environmental monitoring costs for the Contractor.

Public Health and Safety	Increased risk of accidents.	<ul style="list-style-type: none"> • Movement of construction machinery. • Movement of transport vehicles. • Borrow pits. 	<ul style="list-style-type: none"> • Construction vehicles shall be appropriately marked and carry adequate visual and audio warning systems. • Speed limitations on the work site vehicles. • Adequate signage should be provided for motorists and pedestrians. • Designate clearly marked areas for livestock crossing. • Mark and fence the areas of active borrow pits. • Provision of barriers at construction sites. • Access control: restriction of turning movements to approved access points to and from existing highways. • Construction traffic prohibited outside specified hours. 	Presence of fencing/barriers and warning signs, and traffic speed limitations, inspection of logbook, photographic evidence.	Bi-weekly	GDRB: monitoring. Traffic Department of Duhok: supervision.	Cost of provision of warning signs and fencing.	No additional environmental monitoring costs for the Contractor.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
			<ul style="list-style-type: none"> • Timing restrictions for transportation of abnormal loads. • Provision of safe crossings for pedestrians and livestock 					
	Health hazards for construction workers.	<ul style="list-style-type: none"> • Operating the equipment. • Noise and dust generation from construction equipment. • Vehicles movement. 	<ul style="list-style-type: none"> • Provide training on First Aid Procedures. • Provide training on potential risks and hazards of construction. • Provide the PPE and enforce its use • Provide warning signs. 	<ul style="list-style-type: none"> • Use of PPE and presence of warning signs. • Application of the noise abatement and dust abatement measures. • Inspection of logbook. 	Weekly	Contractor – internal monitoring. GDRB: supervision.	Cost of PPE. Cost of dust abatement measures. Regular cost of vehicles and equipment maintenance.	No additional environmental monitoring costs for the Contractor.
Disruption of	Restricted access to the business entities:	<ul style="list-style-type: none"> • Excavation. • Traffic diversion. • Paving. 	<ul style="list-style-type: none"> • Provide temporary exit and entry ramps. 	<ul style="list-style-type: none"> • Provision of temporary access points to business entities. 	Bi-weekly	GDRB: monitoring and supervision.	Cost of entry/exit ramps.	No additional environmental monitoring

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
	<ul style="list-style-type: none"> Evin Gas Station; Girsheen Gas Station; Bawer Gas station. 		<ul style="list-style-type: none"> Restore access upon completion of construction works. Provide gaps for entry/exit in road barriers. Advance warning of the start of works. 	<ul style="list-style-type: none"> Provision of information in local media on scheduled works. Warning signs. 				costs for the Contractor.
	Disruption of utilities.	Relocation of electric poles.	<ul style="list-style-type: none"> Advanced public warning of the start of works. Restoration of utilities provision in a shortest time possible. 	Restoration of service provision.	Monthly			
	Visual and Aesthetic Impact.	<ul style="list-style-type: none"> Landscape damage due to the piles of excavated materials, construction debris and discarded materials. Clearance and trees and shrubs removal. 	<ul style="list-style-type: none"> All trees, native shrubbery and vegetation should be preserved and protected from damage. Movement of crews and equipment should avoid damage to property, productive lands and known sites of historical and archeological importance. 	Approach to landscape restoration, visual observations, photographic evidence.	Monthly			

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Cost of Mitigation	Cost of Monitoring
			<ul style="list-style-type: none"> Restoration of the landscape to the original state. Upon completion of the works, all surplus equipment and materials to be removed and all work areas smoothed and graded to conform to the natural appearance of the surrounding landscape. 					
Heritage sites	Accidental damage to the sites of historical, cultural and religious significance.	<ul style="list-style-type: none"> Excavations along the alignment. Borrow pits. 	In case of chance find the cultural resources procedure should be applied.	Inspection for presence of artifacts in excavated material, inspection of logbook.	Bi-monthly	Contractor – internal monitoring. Directorate of Antiquities	N/A	No additional environmental monitoring costs for the Contractor.
Estimated costs:							2,735,334US\$	75,500 US \$ (11,500 US \$ plus 64,000 US \$ input of environmental monitor)

Table 9-2: ESMP – Operational and Maintenance Phase

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Annual Cost of Mitigation	Annual Cost of Monitoring
Water resources	<ul style="list-style-type: none"> Flooding of drainage channels and alteration of discharge patterns. Water resources contamination. 	<ul style="list-style-type: none"> Blockage of drainage systems and culverts due to the accumulation of debris. Accidental spillage of hazardous materials. Road maintenance. 	<ul style="list-style-type: none"> Regular cleaning of roadsides;. Clearing of debris after the raining season. Emergency response for accidental spills. Regular maintenance of culverts and drainage channels. 	<ul style="list-style-type: none"> Condition of the drainage channels and culverts, photographic evidence. <p><u>Water quality parameters:</u></p> <ul style="list-style-type: none"> pH, Turbidity, Electrical Conductivity (EC), Color, Total Suspended Solids (TSS), Total Dissolved Solids (TDS), Chemical Oxygen Demand (COD), Biological Oxygen Demand (BOD), Polychlorinated Biphenyls (PCBs). 	<p><u>Surveillance:</u></p> <ul style="list-style-type: none"> Bi-weekly during the rainy season Bi-monthly during the dry season. <p><u>Water testing</u> Once per year during rainy season.</p>	GDRB	Cost of regular cleaning and maintenance.	500 US \$ for testing. No additional cost of environmental monitoring.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Annual Cost of Mitigation	Annual Cost of Monitoring
Soils	<ul style="list-style-type: none"> • Soil erosion. • Soil contamination. 	<ul style="list-style-type: none"> • Alteration of water courses due to debris accumulation. • Accidental spills of hazardous materials. • Accumulation of pollutants from traffic emissions. • Road maintenance. 	<ul style="list-style-type: none"> • Same measures to be applied as for the mitigation of impacts on water resources. • Additionally, provision of protective zone of vegetation. 	<ul style="list-style-type: none"> • Condition of the drainage channels and culverts, photographic evidence. <p><u>Soil parameters:</u> pH, temperature, organic content, poly-aromatic hydrocarbons (PAHs).</p>	<p><u>Surveillance:</u></p> <ul style="list-style-type: none"> • Bi-weekly during the rainy season • Bi-monthly during the dry season. <p><u>Soil testing</u> Once per year during rainy season.</p>	GDRB	<ul style="list-style-type: none"> • Cost of regular cleaning and maintenance. • Cost of trees. 	300 US \$ for testing No additional cost of environmental monitoring.
Biodiversity	Habitat fragmentation Incidents of road kill of wild animals.	Physical separation by road structure.	Ensure the culverts and underpasses are clear .	Condition of culverts and underpasses.	<p><u>Surveillance:</u></p> <ul style="list-style-type: none"> • Bi-weekly during the rainy season • Monthly during the dry season. 	GDRB	Cost of regular cleaning and maintenance.	No additional cost of environmental monitoring.
Ambient Air Quality	Air pollution	<ul style="list-style-type: none"> • Traffic movement. • Traffic congestion due to accidents. • Transporting of the dust generating materials. 	<ul style="list-style-type: none"> • Provision of row of trees alongside of the road alignment. • Ensure all the dust generating materials are transported by covered vehicles. • Monitor vehicles condition. 	<ul style="list-style-type: none"> • Air quality parameters: PM10, PM2.5, SO2, TSP, NOx, CO, Ozone and HC. 	Once a year during dry season – air quality testing. Regular monitoring of traffic movement.	Air quality monitoring – GDRB. Regulating vehicles movement – traffic police.	Cost of trees planting	3 000 US \$ for air quality testing.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Annual Cost of Mitigation	Annual Cost of Monitoring
Public Health and safety	Risk of accidents related to traffic.	Traffic movement	<ul style="list-style-type: none"> • Provision of a median concrete barrier, a New Jersey barrier that will run the full length of the road mainline. • Provision of street lighting to reduce accidents at night and at times of reduced visibility. • Provision of directional and warning road signage. • Provision of the underpass for livestock crossing. • Adequate delineation and demarcation of the road. • Enforcement of proper driver's behavior. • Guardrails barriers on curves and intersections. 	<ul style="list-style-type: none"> • Condition of road signage and markings. • Condition of road lighting. • Regular maintenance of pedestrian crossings and livestock underpasses. • Photographic evidence. 	Bi-weekly	GDRB Traffic Police	Cost of road maintenance.	No additional costs of environmental monitoring.

Parameter	Impacts	Activities	Mitigation Measures	Monitoring Parameters	Monitoring Frequency	Monitoring Responsibility	Annual Cost of Mitigation	Annual Cost of Monitoring
	<ul style="list-style-type: none"> • Soil pollution. • Traffic accidents. 	<ul style="list-style-type: none"> • Use of chemicals for landscape maintenance. • Traffic congestion at areas of highway maintenance. • Increased possibility of traffic accidents. 	<ul style="list-style-type: none"> • Effective advance information and warning signs. • Effective material handling, storage and use. • Provision of fencing in high risk areas. • Site supervision. 	<ul style="list-style-type: none"> • Condition of road signage and markings. • Adequate lighting of the road. • Handling of materials. 	Weekly during maintenance.	GDRB	Cost of fencing and warning signage.	No additional cost of environmental monitoring.
Estimated costs per annum:							None (standard maintenance costs).	11,800 US \$ (3,800 US \$ cost of tests, and 8,000 US \$ input of environmental monitor).

9.1 Environmental Management Principles

The procedures listed below are designed to provide proactive systematic approach for managing the potential environmental consequences and impacts of implementation of the project.

Planning: determines the environmental aspects and impacts of the work conducted throughout the implementation of the project to control and reduce, where possible, the impacts associated with the identified aspects. Environmental aspects are identified by reviewing all project activities, and assessing the possibility each of them have for an environmental impact and recognizing that certain environmental aspects are the subject of certain legal or other requirements. Objectives and targets are set by considering, in part, the legal and other requirements, the views of interested parties, as well as, technological, financial and other operational considerations. This ensures that objectives and targets are robust, that they respond to legitimate concerns.

Monitoring and Evaluation: includes defining roles and responsibilities for each task as well as performance indicators and milestones for completion, including timeframes and frequency of monitoring and evaluation through the implementation of the project.

Reporting: Regular reporting on the status of identified environmental aspects and compliance of implementation with the proposed mitigation measures.

Training, Awareness, and Competence: requires two types of training: general awareness, and competence training. General awareness training for all employees focuses on the importance of the environmental policy, the role of employees, and the potential consequences of failing to provide environmental care. Competence training is prescribed for employees that work in proximity to significant environmental aspects and focuses on the possible significant impacts of those aspects, their specific roles and responsibilities, the objectives and targets for those aspects, and the operational controls in place to avert the actualization of the potential impacts.

Communication: ensures effective integrated environmental management demands effective communications to coordinate staff internally and to liaise with external stakeholders

Emergency Preparedness and Response: despite best efforts there is the possibility of unpredictable accidents and emergencies. It is necessary that measures to be included in the plan to address the environmental consequences of such occurrences. It is expected that such measures work to control and mitigate those possible environmental consequences.

Corrective actions: Upon identification of deviation from the recommended mitigation measures and/or non-compliance with regulations and recommendations the action request should be issued and immediate corrective actions implemented.

9.2 Environmental Monitoring Structure

The proposed structure of supervision of implementation of the project is presented in Figure 9-1.




Figure 9-1: Environmental Monitoring during Construction Phase

Safeguards monitoring will be conducted on two levels:

Internal monitoring will be provided by the HSE expert from contractor's side. The responsibilities should include:

- Preparation of the detailed monitoring plan;
- Conducting water quality, soil quality and air quality tests;
- Conducting monitoring according to the prepared monitoring plan;
- Reporting.

External monitoring and supervision will be provided by the GDRB. The results of monitoring will be disseminated amongst the concerned stakeholders.

9.3 Monitoring Budget Considerations

The estimated budgets for the monitoring of the project compliance with the ESMP during the construction phase and during the operational phase are presented in Table 9-3 and Table 9-4.

Table 9-3: Monitoring Budget for Construction Phase

#	Item	Unit	Number of Units	Cost per Unit (US \$)	Total (US \$)
1	Water Quality Tests	Test	6	500	3000
2	Soil Quality Tests	Test	3	500	1500
3	Environmental Monitoring	Man month	16	4000	64000
4	Noise level equipment	Noise meter	2	500	1000
5	Air quality monitoring	Tests	2	3000	6000
6	Total				75 500


Also preliminary estimates were made for the cost of the ESMP implementation during operational phase per year.



Table 9-4: Monitoring Budget per Year – Operational Phase


#	Item	Unit	Number of Units	Cost per Unit (US \$)	Total (US \$)
1	Water Quality Tests	Test	1	500	500
2	Soil Quality Tests	Test	1	300	300
3	Environmental Monitoring	Man month	2	4000	8000
4	Air quality monitoring	Test	1	3000	3000
5	Total				11 800


Annexes

Annex 1: Road Design









Annex 2: Construction Materials

Part 1					
Items No.	Description	Unit	Quantity	Unit Price (Dinar)	Total (Dinar)
1	Temporary Transformative Works				
1.1	<p>Temporary transformative works: Clean and leveling including cut and fill the carriage way by 11 m in width, using appropriate machines and materials. Watering and compaction to reach 95% of maximum dry density (with maximum vertical slope 6% and the design speed not less than 80 km/hr).</p> <p>Transport and lay approved crushed stone base coarse 25 cm in thickness in two layers including watering and compaction to reach 98% of maximum dry density, through 8.5 m in width.</p> <p>Also supply and lay two layers of binder with 7 cm in thickness, 7.5 m in width.</p> <p>For road shoulder, Spread and lay one layer of Alkhabet gravel (mixed of gravel and sand) type B with 15 cm in thickness, with width of 2.5 m for right side and 1 m for left side including compaction to reach 95% of maximum dry density.</p> <p>The price will include spraying primary coat and tack coat using bitumen emulsion, traffic signs,</p>	L.M	26,500	360,000	9,540,000,000

	Concrete Jersey Barriers, Culverts (precast or cast in site as the same size of main street's culverts), canals, rubble removing and regular maintenance until the end of the project. The work should be according to the coordination with authorities and municipalities, technical specifications and Engineer's instruction and approval.				
2	Soil preparations:				
	Prepare the number and type of machines and equipment needed for implementation according to the schedule of work progress, which will be approved later. The contractor should inquire about any ambiguity for this item before the tender is submitted. No inquiries will be accepted later especially during work implementation. All works implemented according to drawings, technical specification and Engineer's instructions.				
2.1	Scraping works: for all types of soil including the surface soil. Removing works including removal of existing asphalt, curbstone and old casts with thickness not less than 30 cm. Also remove any other obstacles such as roots and transfer it away, in coordination with concerned authorities.	m ³	237,000	4,000	948,000,000
2.2	Cut Works: clean, excavate and cut from natural ground level to the bottom of the sub-grade layer including watering and	m ³	1,575,000	3,500	5,512,500,000

	<p>compaction not less than 95% of maximum dry density.</p> <p>Cut below the sub-grade level if the CBR of the existing soil less than 10%; by cut 50 cm below sub-grade level then compacted it to reach not less than 95% of maximum dry density.</p> <p>The cut work include open runnels, recognize the side slope according to the drawings and remove the excess/unsuitable soil outside the carriageway in coordination with concerned authorities.</p>				
2.3	Fill Works: including fill multilayer using clean and inorganic soil with CBR not less than 4%. Each layer has a thickness of 25 cm including watering and compaction not less than 95% of maximum dry density, to 50 cm below the sub grade level.	m ³	525,000	5,000	2,625,000,000
2.4	Sub-Grade Preparation: including fill multilayer using clean and inorganic soil with CBR not less than 10% and 50 cm in thick. Each layer has a thickness not more than 25 cm including watering and compaction not less than 95% of maximum dry density, to 50 cm below the sub grade level. Also substituted the soil in cutting areas with soil not containing stones with size larger than 2/3 layer thickness.	m ³	278,000	7,000	1,946,000,000
3	Prepare equipment and materials, which are needed to raise columns which crossing the	NO.	150	500,000	75,000,000

	path then reinstalled it in coordination with concerned authorities.				
4	Culverts Works:				
4.1	<p>Including site preparation, excavations and materials supplying (Cement, Gravel, Sand, Steel reinforcement grade 60, sleek wooden mold Fair face from both inside and outside, Plastic concrete cover).</p> <p>The price includes constructed the wings and putting large stones in the exit and entrance.</p> <p>The concrete strength should be not less than 210 kg/cm² in day 28, culvert base should be compacted to reach at least 95% of maximum dry density.</p> <p>The price also includes laying a layer of natural gravel type A with a thickness of 25 cm below the base of culvert and compaction not less than 95% of maximum dry density.</p> <p>Also a layer of lean concrete with a 10 cm in thickness.</p> <p>The work includes refine the water stream to ensure that the water exit and entrance in a streamline according to drawings, technical specifications and Engineer instructions.</p>				
4.1.1	A single, reinforced concrete culvert box (1X1)m.	L.M	400	1,000,000	400,000.000
4.1.2	A double, reinforced concrete culvert box (1 X1)m.	L.M	280	1,300,000	364,000,000
4.1.3	A single, reinforced concrete box (1.5X1.5)m.	L.M	70	1,400,000	98,000,000
4.1.4	A double, reinforced concrete culvert box (1.5X1.5)m.	L.M	105	2,500,000	262,500,000

4.1.5	A single, reinforced concrete culvert box(2X3)m.	L.M	63	3,000,000	189,000,000
4.1.6	A single, reinforced concrete box girders (3X3)m.	L.M	120	3,800,000	456,000,000
4.1.7	A single, reinforced concrete box passage (2X3)m for cattle crossing.	L.M	160	3,800,000	608,000,000
4.2	Use a screened natural gravel type A to fill the aspects of the bridge by 5 m in width on each side to reach the high level of bridge. The fill should be done as multi layer filling with width of 15 cm for each. Including compaction not less than 95% of maximum dry density according to technical specifications, drawings and Engineer's instructions.	m ³	18000	18,000	324,000,000
5	Filters items: Including materials preparation (Horse Shoe Perforated Spirally wounded PVC, Geo-Textile, crushed stone, cement, gravel, wooden mold, plastic concrete covers. etc.) to make filters in cutting areas. The price includes excavations, refilling by crushed stone (5-15)mm inside Geo-textile, cast the base by concrete with strength not less than 210 kg/cm ² in 28 days. Also includes covering the waterwheel by reinforced concrete by a layer of B.R.C (150X150X6) mm, with width of 15 cm and strength not less than 210 kg/cm ² in 28 days above a layer of crushed stone with 10 cm in thickness according to drawings, technical	L.M	17,900	150,000	2,685,000,000

	specifications and Engineer's instructions.				
6	Base and Sub-base Item				
6.1	Sub-Base layer: supply and lay natural screened gravel type A using a sensitive spreader. With thickness of 20 cm after compacted it to reach not less than 95% of maximum dry density, using a sensitive spreader (after watering and reaching the optimum moisture) after installed the wedges (Blue top) according to elevations existed in the drawings.	m ³	110,000	22,000	2,420,000,000
6.2	Base layer: supply and lay three layers of crushed aggregate (gravel and stones), classified as R7.1 according to Iraq specifications for roads and bridges. Each layer thickness after compaction is 36 cm, using a sensitive spreader (after watering and reaching the optimum moisture) after installed the wedges (Blue top) according to elevations existed in the drawings with percent not less than 98% of maximum dry density according to drawings, specifications and Engineer's instructions.	m ³	198,800	30,000	5,964,000,000
7	Tiling Works: Include supply with materials, machines and industries needed for implementation of this item. Using a sensitive spreader after installed the wedges (Blue top) according to elevations existed in the drawings, specifications and Engineer's instructions.				

7.1	<p>Supply, lay and compacted a layer of Alqiri Mix (stabilizer layer) using crushed gravel and crushed sand (crushing percentage not less than 90% two faces or more) with a minimum thickness of 10 cm after compaction.</p> <p>It's classified as (section R9) according to Iraq technical specifications for roads and bridges.</p> <p>The work also includes spraying a prime coat using bitumen emulsion according to Engineer's instructions.</p> <p>Alqiri Mix should be test every single working day or according to the Engineer's instructions.</p> <p>The price includes prepare Alqiri mix and all works needed to complete the item.</p>	m ²	337,000	16,000	5,392,000,000
7.2	<p>Supply, lay and compacted a layer of Alqiri Mix (Binder layer) using crushed gravel and crushed sand (crushing percentage not less than 90% two faces or more) with a minimum thickness of 6 cm after compaction.</p> <p>It's classified as (section R9) according to Iraq technical specifications for roads and bridges.</p> <p>The work also includes spraying a tack coat using bitumen emulsion according to Engineer's instructions.</p> <p>Alqiri Mix should be test every single working day or according to the Engineer's instructions.</p>	m ²	335,000	13,000	4,355,000,000

	The price includes prepare Alqiri mix and all works needed to complete the item.				
7.3	<p>Supply, lay and compacted a layer of Alqiri Mix of (Pavement stone mastic polymer modified asphalt bitumen)(Surface layer) using crushed gravel and crushed sand (crushing percentage not less than 90% two faces or more) with a minimum thickness of 4 cm after compaction.</p> <p>The work also includes spraying a tack coat using bitumen emulsion according to Engineer's instructions.</p> <p>Alqiri Mix should be test every single working day or according to the Engineer's instructions.</p> <p>The price includes prepare Alqiri mix (modified by polymer) and all works needed to complete the item.</p>	m ²	342,000	15,000	5,130,000,000
7.4	<p>Supply and lay natural screened gravel type B for shoulders to the level of tilling. Each side has a width of 4m with a minimum thickness of 20 cm.</p> <p>Each side compacted to reach not less than 95% of maximum dry density, using a sensitive spreader after installed the wedges (Blue top) according to elevations existed in the drawings.</p>	L.M	26,500	18,000	477,000,000
8	Installation and Casting concrete molds				
8.1	Supply needed materials (reinforced steel grade 60, gravel, sand, cement, steel molds and all needed materials) and cast molds (F- Shape Barrier) in	L.M	12,500	85,000	1,062,500,000

	situ with strength not less than 210 kg/cm ² using cast in situ machine and sensitive devices, with a fair face casting. Make expansion joints for every 24 m and contraction joints for every 6 m. Put and install phosphorus reflectors for every 2 m above molds according to drawings, specifications and Engineer's instructions.				
8.2	Median casting: Supply materials (cement, sand, gravel, wooden mold and all needed materials), cast median and the base of concrete molds by a layer of reinforced concrete (B.R.C (150X150X6)mm) with a strength not less than 210 kg/cm ² according to drawings, technical specifications and Engineer's instructions.	m ²	39,000	27,000	1,053,000,000
9	Curbstone and sidewalks Works				
9.1	Curbstone works: supply and install curbstone materials (30cm in height) on a concrete base 10 cm in thickness with strength not less than 210 kg/cm ² in 28th day. The price includes all casts attached to curbstone and phosphoric dye and all works needed to implement the item according to technical specification, drawings and Engineer's instructions.	L.M	3,500	40,000	140,000,000
9.2	Sidewalks: Supply needed materials (cement, sand, gravel, wooden mold and all needed materials), cast sidewalks by normal concrete with strength not less than 210kg/cm ² and thickness of 12 cm, and install contraction joints.	m ²	7,000	24,000	168,000,000

	The price includes: compaction the soil, lay and compacted a layer of natural gravel type A with a thickness of 15 cm below the cast level and compaction not less than 95% of maximum dry density, install contraction joints with a displacement of 3 m, width of 3 mm and thickness of 4 cm according to technical specification, drawings and Engineer's instructions.				
10	Road Signs & Road Marking Supply and install road sign with different indications, also set columns after install two pieces of angular steel below the column with dimension of (50X5X5)cm then cast it by normal concrete with strength not less than 210 kg/cm ² in day 28 according to technical specification, drawings and Engineer's instructions. The price includes: Excavations, Bolts, steel cover for column's head, Welding and all needed materials to install road signs.				
10.1	Warning Road Signs (Triangle) with a side length of 90cm or circular with diameter of 90cm. The sign panel includes: galvanic plate 2 mm thick, white phosphoric glued and a red tape around sign with 6.5cm in width. The tape and all other effective on the sign should be one layer, made in U.S.A and wit a guarantee for 10 years (High Intensity Grade Prismatic	NO.	130	210,000	27,300,000

	<p>Reflective Sheeting ASTM D 4956 type 3 & 4).</p> <p>The column of the sign is a galvanic steel column with diameter of 2.5 inch, 3 mm in thickness and 3 m in length.</p>				
10.2	<p>Square Road Signs (Chevron) with size of (90X90)cm.</p> <p>The sign panel includes: galvanic plate 2 mm thick, white phosphoric glued and a red tape with arrow shape.</p> <p>The tape and all other effective on the sign should be one layer, made in U.S.A and wit a guarantee for 10 years (High Intensity Grade Prismatic Reflective Sheeting ASTM D 4956 type 3 & 4).</p> <p>The column of the sign is a galvanic steel column with diameter of 2.5 inch, 3 mm in thickness and 3 m in length.</p>	NO.	22	225,000	4,950,000
10.3	<p>Square Road Signs (Chevron) with size of (60X180)cm.</p> <p>The sign panel includes: galvanic plate 2 mm thick, white phosphoric glued and a red tape with arrow shape.</p> <p>The tape and all other effective on the sign should be one layer, made in U.S.A and wit a guarantee for 10 years (High Intensity Grade Prismatic Reflective Sheeting ASTM D 4956 type 3 & 4).</p> <p>The column of the sign is a galvanic steel column with diameter of 2.5 inch, 3 mm in thickness and 3 m in length</p>	NO.	14	450,000	6,300,000

10.4	<p>Guiding, Square Road Signs (Chevron) with size of (100X100)cm.</p> <p>The sign panel includes: galvanic plate 2 mm thick, phosphoric glued with a blue background and a white frame with 2cm in width.</p> <p>The tape and all other effective on the sign should be one layer, made in U.S.A and wit a guarantee for 10 years (High Intensity Grade Prismatic Reflective Sheeting ASTM D 4956 type 3 & 4).</p> <p>The column of the sign is a galvanic steel column with diameter of 2.5 inch, 3 mm in thickness and 3 m in length (NO.=2).</p>	NO.	35	300,000	10,500,000
10.5	<p>Guiding, Rectangular Road Signs with size of (40X150)cm.</p> <p>The sign panel includes: galvanic plate 2 mm thick, phosphoric glued with a blue background and a white frame with 2cm in width.</p> <p>The tape and all other effective on the sign should be one layer, made in U.S.A and wit a guarantee for 10 years (High Intensity Grade Prismatic Reflective Sheeting ASTM D 4956 type 3 & 4).</p> <p>The column of the sign is a galvanic steel column with diameter of 2.5 inch, 3 mm in thickness and 3 m in length (NO.=2).</p>	NO.	6	300,000	1,800,000

10.6	<p>Guiding, Rectangular Road Signs with size of (80X150)cm. The sign panel includes: galvanic plate 2 mm thick, phosphoric glued with a blue background and a white frame with 2cm in width. The tape and all other effective on the sign should be one layer, made in U.S.A and wit a guarantee for 10 years (High Intensity Grade Prismatic Reflective Sheeting ASTM D 4956 type 3 & 4). The column of the sign is a galvanic steel column with diameter of 2.5 inch, 3 mm in thickness and 3 m in length (NO.=2).</p>	NO.	10	400,000	4,000,000
10.7	<p>Guiding, Square Road Signs with size of (200X200)cm. The sign panel includes: galvanic plate 2 mm thick, phosphoric glued with a green background and a white frame with 10cm in width. The tape and all other effective on the sign should be one layer, made in U.S.A and wit a guarantee for 10 years (High Intensity Grade Prismatic Reflective Sheeting ASTM D 4956 type 3 & 4). The column of the sign is a galvanic steel column (Shilman) with dimension of (2 inX4 inX6 mm) and 4.5 m in length (NO.=2).</p>	NO.	13	1,200,000	15,600,000
10.8	<p>Guiding Road Signs with size of (200X200)cm. The sign panel includes: galvanic plate, phosphoric glued</p>	NO.	2	50,000,000	100,000,000

	with a green background and a white frame with 10cm in width. The tape and all other effective on the sign should be one layer, made in Italy and wit a guarantee for 10 years (High Intensity Grade Prismatic Reflective Sheeting ASTM D 4956 type 3 & 4). The price includes: galvanic steel , casting the base of columns by reinforced concrete with dimension of (4X1.5)m according to technical specification, drawings and Engineer's instructions.				
10.9	Road Marking: Supply needed materials (Dye needed to layout roads and streets is a free from grained glass, white colored according to American international specifications (A-2886A MAY 1.1.1997-CDI A)). Supply Grained Glass (Phosphoric) (class Bea) type (Low index type 1 Gradation A). The process of marking: layout the streets and roads in a continuous & dashed lines (continuous lines on sides and dashed lines on the middle) with width of 15 cm for the continuous lines and 18 cm for dashed lines. The streets should be cleaned very well before start marking it according to (TT-B-1325C) specifications and Engineer's instructions.	L.M	85,000	3000	255,000,000
	TOTAL				52,619,950,000

Part 2					
---------------	--	--	--	--	--

Items No.	Description	Unit	Quantity	Unit Price (Dinar)	Total (Dinar)
1	Surveying, Soil Tests and Designs				
1.1	Prepare surveying works, soil tests and designs for BATEL interchanges, retaining walls, curvets and canals according to the attached references.	NO.	1	75,000,000	75,000,000
1.2	Prepare surveying works, soil tests and designs for SMILE AVA interchanges, retaining walls, curvets and canals according to the attached references.	NO.	1	75,000,000	75,000,000
	TOTAL				150,000,000

Annex 3: EPA Emissions Standards

Light Duty Vehicles Emission Standards

	Vehicle Type	Emission Category	Vehicle Useful Life												
			5 Years / 50,000 Miles							10 Years / 100,000 Miles					
			NMHC ^a (g/mi)	NMOG (g/mi)	CO _b , ^c (g/mi)	NO _x d (g/mi)	PM (g/mi)	HCH O (g/mi)	THC ^{c, e, f} (g/mi)	NMHC _a (g/mi)	NMOG (g/mi)	CO _g (g/mi)	NO _x (g/mi)	PM (g/mi)	HCHO (g/mi)
Federal ^{h, j}	LDT3	Tier 0	-	-	-	-	-	-	0.8	0.67k	-	10	1.7	0.26l	-
		Tier 1	0.32	-	4.4	0.7	-	-	0.8	0.46	-	6.4	0.98	0.1	-
	LDT4	Tier 0	-	-	-	-	-	-	0.8	0.67k	-	10	1.7	0.13l	-
		Tier 1	0.39	-	5	1.1	-	-	0.8	0.56	-	7.3	1.53	0.12	-
Federal Clean Fuel Vehicle (CFV) Program ^{h, i}	LDT3	LEV	-	0.125n	3.4	0.4	-	0.015	-	-	0.180n	5	0.6	0.08o	0.022
	0-3750	ILEV _m	-	0.125	3.4	0.2	-	0.015	-	-	0.180	5	0.3	0.08o	0.022
	ALVW	ULEV	-	0.075n	1.7	0.2	-	0.008	-	-	0.107n	2.5	0.3	0.04o	0.012
	LDT3	LEV	-	0.160n	4.4	0.7	-	0.018	-	-	0.230n	6.4	1.0	0.10o	0.027
	3751-5750	ILEV _m	-	0.160	4.4	0.4	-	0.018	-	-	0.230	6.4	0.5	0.10o	0.027
	ALVW	ULEV	-	0.100n	2.2	0.4	-	0.009	-	-	0.143n	3.2	0.5	0.10o	0.013
	LDT4	LEV	-	0.195n	5	1.1	-	0.022	-	-	0.280n	7.3	1.5	0.12o	0.032
	5751-8500	ILEV _m	-	0.195	5	0.6	-	0.022	-	-	0.280	7.3	0.8	0.12o	0.032
	ALVW	ULEV	-	0.117n	2.5	0.6	-	0.011	-	-	0.167n	3.7	0.8	0.06o	0.016

LDT: Light duty vehicle

LEV: low emission vehicle

ILEV: Inherently low emission vehicles

ULEV: ultra low emission vehicles.

Notes:

Tests Covered: Federal Test Procedure (FTP), cold carbon monoxide (CO), highway, and idle

Effective Model Year: 1981 - 1993, Tier 0

1994 - 1999, Tier 1

1999 - Present, CFV

- a Total hydrocarbon equivalent (THCE) for Tier 0 methanol vehicles, non-methane hydrocarbon equivalent (NMHCE) for other alcohol vehicles.
- b Cold CO emissions for gasoline fueled vehicles shall not exceed 10.0 grams per mile (g/mi) (light-duty vehicle, light-duty truck 1 [LDT1], LDT2) or 12.5 g/mi (LDT3 & LDT4) at 50,000 miles.
- c Certification short test (CST) emissions from gasoline vehicles shall not exceed 100 parts per million HC or 0.50 percent exhaust gas CO at idle and 2500 revolutions per minute at 4,000 miles; compliance statement allowed in lieu of actual test data.
- d Does not apply to diesel-fueled vehicles.
- e THCE for methanol vehicles.
- f Does not apply to compressed natural gas (CNG) vehicles.
- g Idle CO emissions from gasoline, methanol, CNG and liquefied petroleum gas trucks shall not exceed 0.50 percent exhaust gas at 120,000 miles or 11 years; compliance statement allowed in lieu of actual test data.
- h Federal On-board diagnostics system required beginning with 1994 model year vehicles.
- i Tier 1, National Low Emissions Vehicle (NLEV) & CFV vehicles must meet Tier 1 emissions standards at high altitude; Tier 0 vehicles must meet special high altitude standards; compliance statement allowed in lieu of actual test data.
- j Tier 0 and Tier 1 emission standards do not apply to ethanol vehicles.
- k CNG vehicles only.
- l Diesel-fueled vehicles only.
- m Special evaporative requirements apply (5.0 grams maximum with the evaporative system disconnected).
- n Special non-methane organic gas (NMOG) standards apply to dual and flexible fuel vehicles.
 - Diesel-fueled vehicles only.

	Vehicle Type	Emissions Category	Useful Life Standard	Test Weight (lbs)	NMOG (g/mi)	NOx (g/mi)	CO (g/mi)	Formaldehyde (g/mi)	PM (g/mi) ^b
Federal	LDVs	TLEV	Intermediate	All	0.125	0.4	0	0.015	-
		LEV			0.075 ^c	0.2	3.4 ^c	0.015 ^c	-
		ULEV			0.040	0.2 ^c	1.7	0.008	-
		TLEV	Full		0.156	0.6	4.2	0.018	0.08
		LEV			0.090 ^c	0.3	4.2 ^c	0.018	0.08 ^c
		ULEV			0.055	0.3 ^c	2.1	0.011	0.04
	LLDTs	TLEV	Intermediate	0-3750 LVW	0.0125	0.4	3.4	0.015	-
		LEV			0.075 ^c	0.2	3.4 ^c	0.015 ^c	-
		ULEV			0.040	0.2 ^c	1.7	0.008	-
		TLEV		3751-5750 LVW	0.160	0.7	4.4	0.018 ^c	-
		LEV			0.100 ^c	0.4	4.4 ^c	0.018 ^c	-
		ULEV			0.050	0.4 ^c	2.2	0.009	-
		TLEV	Full	0-3750 LVW	0.156	0.6	4.2	0.018	0.08
		LEV			0.090 ^c	0.3	4.2 ^c	0.018 ^c	0.08 ^c
		ULEV			0.055	0.3 ^c	2.1	0.011	0.04
		TLEV		3751-5750 LVW	0.200	0.9	5.5	0.023	0.08
		LEV			0.130 ^c	0.5	5.5 ^c	0.023 ^c	0.08 ^c
		ULEV			0.070	0.5 ^c	2.8	0.013	0.04
	HLDTs	LEV	Intermediate	0-3750 LVW	0.125 ^c	0.4 ^d	3.4 ^c	0.015 ^c	-
		ULEV		ALVW	0.075	0.2 ^{c, d}	1.7	0.008	-
		LEV		3751-5750	0.160 ^c	0.7 ^d	4.4 ^c	0.018 ^c	-
		ULEV		ALVW	0.100	0.4 ^{c, d}	2.2	0.009	-
		LEV		5751+	0.195 ^c	1.1 ^d	5.0 ^c	0.022 ^c	-
		ULEV		ALVW	0.117	0.6 ^{c, d}	2.5	0.011	-

	LEV	Full	0-3750 LVW	0.180 ^c	0.6	5.0c	0.022 ^c	0.08 ^c
	ULEV		ALVW	0.107	0.3 ^c	2.5	0.012	0.04
	LEV		3751-5750	0.230 ^c	1.0	6.4c	0.027 ^c	0.10 ^c
	ULEV		ALVW	0.143	0.5 ^c	3.2	0.013	0.05
	LEV		5751+	0.280 ^c	1.5	7.3c	0.032 ^c	0.12 ^c
	ULEV		ALVW	0.167	0.8 ^c	3.7	0.016	0.06

LDT: Light duty vehicle

LEV: low emission vehicle

ILEV: Inherently low emission vehicles

TLEV: transitional low emission vehicles

ULEV: ultra low emission vehicles.

a These standards have in effect been superseded by newer, more stringent standards in 40 Code of Federal Regulations (CFR) Part 86.

c Applies to Inherently Low Emission Vehicles.

d Does not apply to diesel vehicles.

Heavy-Duty Highway Engine -- Clean Fuel Fleet Exhaust Emission Standards

	Emissions Category	NMHC+NO _x (g/bhp-hr)	CO (g/bhp-hr)	PM (g/bhp-hr)	Formaldehyde (g/bhp-hr)
Federal	LEV (Federal Fuel)	3.8	b	b	b
	LEV (California Fuel)	3.5	b	b	b
	ILEV	2.5	14.4	0.10	0.05
	ULEV	2.5	7.2	0.05	0.025
	ZEV	0	0	0	0

LDT: Light duty vehicle

LEV: low emission vehicle

ILEV: Inherently low emission vehicles

ULEV: ultra low emission vehicles.

ZEV: zero emission vehicles

Vehicle weight classifications

Gross Vehicle Weight Rating (lbs)									
	6,000	8,500	10,000	14,000	16,000	19,500	26,000	33,000	60,000
Federal	LDV	MDPV	*	*	*	*	*	*	*
	LDT	HDV / HDE							
	LLDT	HLDT	LHDDE			MHDDE		HHDE / Urban Bus	
	LDT 1 & 2 ^a	LDT 3 & 4 ^b	HDV2b	HDV3	HDV4	HDV5	HDV6	HDV7	HDV8a HDV8b

a Light-duty truck (LDT) 1 if loaded vehicle weight (LVW) = 3,750; LDT 2 if LVW > 3,750

b LDT 3 if adjusted loaded vehicle weight (ALVW) = 5,750; LDT 4 if ALVW > 5,750

LHDDE: light heavy duty diesel engine

MHDDE: Medium heavy duty diesel engine

HHDE: heavy heavy-duty diesel engine

MDPV: medium duty passenger vehicles.

Annex 4: List of Attendees

#	Name	Organization
1	Khaled Yassin	Dohuk Municipality
2	Samr Khaled	Dohuk Municipality
3	Mohammad Ahmad	Farmer
4	Mohammad Yousef	Mukhtar of Mazri
5	Hazem Ghazi	Mukhtar of Rizgari
6	Hadija Lak	GDRB
7	Mulla Said	Farmer
8	Norad Khaled	GDRB
9	Diwalli Mohammad	GDRB
10	Caroline Winter	World Bank
11	Mayada Zaki	Department of Antiquities, Dohuk
12	Jwan Jamil Omar	Department of Antiquities, Dohuk
13	Bawer Hussein	GDRB
14	Younis Ali	Environmental Directorate of Dohuk
15	Fuad Sadiq	Farmer
16	Bartlan Abdel Jabbar	Farmer
17	Nawar Bin Taher	Farmer
18	Hanat Ahmad Hussein	Farmer
19	Ismail Khomoza	Mukhtar of Kadia
20	Shaker Abed Abdo	Mukhtar of Kani Kark
21	Foubat Abdo Bintu	Mukhtar of Krowin
22	Rami Hrand	Ibrahim Khalil Municipality
23	Mushir Ahmad	Zakho University
24	Mazen Said	Zakho University
25	Dilshad Rasheed	Zakho University
26	Walid Suleiman	Directorate of Agriculture of Batil
27	Abdel Razaq Suleiman	Directorate of Agriculture of Batil
28	Mohammad Zakari	GDRB
29	Shukri Omar	Department of Statistics of Dohuk
30	Nama'a Said	Investment Board of Dohuk
31	Huzam Mustafa	Department of Health of Dohuk

#	Name	Organization
32	Amal Juma'a	Department of Health of Dohuk
33	Rabia Saadallah	Dohuk University
34	Rashid Haji	Farmer
35	Salem Smou	Kalek Complex
36	Fadel Saleh	Bawarda Complex
37	Aveen Shukri	Farmer
38	Mohammad Hasan	Farmer
39	Salah Ali	Farmer
40	Bilind Kamil	Arabtech Jardaneh Company
41	Haitham Ali	Arabtech Jardaneh Company
42	Adham Abeidat	Arabtech Jardaneh Company
43	Iyad Ashoub	Arabtech Jardaneh Company
44	Khaled Nassar	Arabtech Jardaneh Company
45	Khalil Ankar	Arabtech Jardaneh Company



سمینارا ریشہ ریا گشتی یا ریک و پرا لسہر پروژی - دوریانا گرشین - دوریانا سحیلہ

الجلسة التشاورية المتعلقة بأعمال مشروع إنشاء طريق - إبراهيم الخليل/ديره بون/كرشن/سيميل













الأربعاء 17 تموز 2013

رقم	الاسم	المؤسسة	رقم الهاتف	العنوان / البريد الإلكتروني	التوقيع
No	Name	Organization	Telephone No.	Address / email	Signature
1	فائله سليمان ياسين	مديرية مياه	0750 4558772	khalid_Rekan@yahoo.com	
2	سعيد محمد فائله	مديرية مياه	0750 4505511	Samir Seidly@yahoo.com	
3	محمد سليمان حمد	اتحاد فلاصا / دونا	0750 4505511		
4	فائله محمد يوسف	مختار كان حرس	0750 4505511		
5	طارق فاضل العسقل	مختار ريبيز	0750 4505511		
6	خديجة محمد لاه	مختار ريبيز	0750 4505511	Rbel.duhok@yahoo.com	
7	ملا محمد بن شام	اتحاد فلاصا / دونا	0750 4505511		
8	نور الدين بن شام	مختار ريبيز	0750 4505511	u2013@yahoo.com	
9	ديو الي محمد بن شام	مختار ريبيز	0750 4505511		
10					
11					



الجلسة التشاورية المتعلقة بأعمال مشروع إنشاء طريق - ابراهيم الخليل/ديره بون/كرشين/اسمير

الأربعاء 17 تموز 2013

ردیف	نام	موسسه کاری	شماره تماس	آدرس و نشانی	تیم
ردیف	اسم	المؤسسة	رقم الهاتف	العنوان/ البريد الإلكتروني	التوقيع
No	Name	Organization	Telephone No.	Address / email	Signature
1	بیادۀ نافع زنگی	دائرة آثار دھولک	۰۷۵۰۶۱۹۲۹۹	دھولک	
2	جوان جیل نمر	دائرة آثار دھولک	۰۷۵۰۷۲۲۱۹۹۰	دھولک	
3	ناورنگنا حسن	وامتہ خند و حیر و درک	۰۷۵۰۴۶۰۲۶۴	دھولک	
4	دیار معاصرہ صدیہ	مرکز بحیرہ کربلا اہل حق	۰۶۳۵۰۴۵۲۷۶۲۱۲	حیدرآباد	
5	یونس احمد یار	دفتر اوائیہ شہر زنگی	۰۷۵۰۶۷۴۴۹۳۳۵	زاخو	
6	خواجہ محمد سعید	پبلک ریسرچ سوسائٹی	۰۷۵۰۶۵۸۱۷۷۴	دھولک	
7	برنہ نعل عبدالجبار	پبلک ریسرچ سوسائٹی	۰۷۵۰۴۴۶۰۴۸۹	دھولک	
8	دارالانشاءات محمد منور	پبلک ریسرچ سوسائٹی	۰۷۵۰۶۵۰۵۰۵۰۵۰	دھولک	
9	حنابلہ امیر حسین	پبلک ریسرچ سوسائٹی	۰۶۵۵۴۵۵۷۱۸۹	haval-up@yahoo.com	
10	احسانیل کرو کوو	مختار کونسل کھوئی	۰۶۵۹۶۵۶۵۶۵	پاکستان	
11	شیر عید علی	مختار کونسل کھوئی	۰۶۵۹۶۵۶۵۶۵	پاکستان	
12	خوبان عیدو سنڈو	مختار کونسل کھوئی	۰۶۵۹۶۵۶۵۶۵	پاکستان	

الرقم	الاسم	المؤسسة	رقم الهاتف	العنوان/ البريد الإلكتروني	التوقيع
No.	Name	Organization	Telephone No.	Address / email	Signature
1	رائد صبحي حوز	مستشفى إبراهيم بكلي	07503350191	زاهد / ناشد هوسا	حسين
2	مستشفى احمد	جامعة زاهد	07504398940	دهوك / زاهد	8
3	ماتن ديسه	قاعة سين	07504497404	دهوك / سيل	9
4	ولساد مستر شيد	فيلد الاراب	07508147814	دهوك / احمد	10
5	وليد عيسى سليمان	مستشفى زاهد	07504736653	سيل / يانيل	11
6	عبدالله قوردهان	مستشفى زاهد	07504993989	دهوك / سيل	12
7	محمد زكريا رمضان	المرتبعة العامة للزاهد	07504455494	Mohamed Eng 6722	13
8	دكتور عبد الله عمر	مديرية اضاء دهوك	07504584630	Shukridas@yahoo.com	14
9	نور احمد محمد	مديرية اضاء دهوك	07504506731	mehran-sar	15
10	هزاف عبد الرحمن	مديرية اضاء دهوك	07504919158	hazan-engineer@yahoo	16
11	احمد خير محمد ابي جعة	مديرية اضاء دهوك	07504405558	amalarchitect@yahoo	17
12	د. ربيع عبد الله	كلية الهندسة زاهد	07504506589	yabec.oram.aria@nd.ac	18



الجلسه التشارية المتعلقة باعمال مشروع إنشاء طريق – ابراهيم الخليل/ديره بون/كرشين/سيميل

الأربعاء 17 تموز 2013

الرقم	الاسم	المؤسسة	رقم الهاتف	الغنوان/ البريد الإلكتروني	التوقيع
No.	Name	Organization	Telephone No.	Address / email	Signature
1	بشير سليمان عيسى	مؤسسة بون/كرشين/سيميل	٤٥٠٩٢٩٧		
2	سالم محمد حسن	مجمع كميلك	٤٧٢٨٥٢٤		
3	كامل سليم صالح	مجمع بادرده	٤٧١٤٠٥٩		
4	احمد شكرى عيسى	مؤسسة بون/كرشين/سيميل	٠٧٥٠٦٠١٣١١٨		
5	محمد سالم حسن	مؤسسة بون/كرشين/سيميل	٠٧٥٠٦٠١٣١١٨		
6	محمود محمد عيسى	مؤسسة بون/كرشين/سيميل	٠٧٥٠٦٠١٣١١٨		
7	يونس فاروق خالص	مؤسسة بون/كرشين/سيميل	٠٧٥٠٦٠١٣١١٨		
8	هشام علي	مؤسسة بون/كرشين/سيميل	٠٧٥٠٦٠١٣١١٨		
9	أحمد عيسى	مؤسسة بون/كرشين/سيميل	٠٧٥٠٦٠١٣١١٨		
10	أحمد عيسى	مؤسسة بون/كرشين/سيميل	٠٧٥٠٦٠١٣١١٨		
11	فهد عيسى	مؤسسة بون/كرشين/سيميل	٠٧٥٠٦٠١٣١١٨		
12	فهد عيسى	مؤسسة بون/كرشين/سيميل	٠٧٥٠٦٠١٣١١٨		

Annex 5: Rate of Construction Completion

Directorate of Road and Bridge/Duhok			Monthly Report		Ministry of Construction and Housing		
25/10/2015		Date				23	Report No.
	No.	BATEL-GALIZAKHO 13KM LENGTH,				Project Name	
Duhok	Location	2nd STAGE					
10/12/2013		project start date		Yousif Bahjat Yousif		Supervisor Engineer	
10/12/2013		project start date/ practically		DARIN GROUP COMPANY		Contractor Name	
27/05/2016		Project End date		ID	58,836,892		Cost by1000
16/04/2017		Project End date with Extra time		ID			ExtraCost
41%		Completion rate		Day	900		Project period
45%		Completion rate according to plan		Day	325		Total Extra Time
				Ministry of Finance (KRG), 2013			Financial support
DESCRIPTION							
NOTES	PLAN	Completo n rate	QUANTITY COMPLETED	QUANTITY ACCORDING TO TENDER	UNIT	ITEM	No
						Service Road	1st
	87%	87%	23000	26500	M.L	detour work, for temporary transfers	A
						Soil Work	2nd
	83.0%	82.0%	195000	237000	M3	grubbing work	A
	47.0%	44.0%	700000	1575000	M3	cutting work	B
	68%	66.0%	350000	525000	M3	Embankment work	C
	54%	53.0%	147000	278000	M3	Embankmet work by CBR for sub grade	D
	100%	100.0%	150	150	NO.	Provide necessary equipments to remove and install all existing poles ocated in the highway boundary.	3rd
						Culverts work	4th
	60%	57.0%	40	70	M. L	single reinforced concrete box culvert (1.5x1.5m)	A
	50%	38.0%	40	105	M.L	Double reinforced concrete box culvert (1.5x1.5m)	B
	100%	94%	143	160	M.L	Single reinforced concrete box culvert (3x3m)	C
							6th
	97%	97%	17500	18000	M3	Subbase Course type A	A
	31%	30%	91000	308000	M3	Base Cours	B
						Hot Mix Asphalt work	7th
	40%	38%	128750	335000	M2	Stablizer	A
	15%	14%	5600	39000	M2	Concrete Barriers	8th
						Interchange SMILAWA	
						Soil Work	1st
	83%	83%	26000	31000	M3	grubbing work	A
	99%	99%	84000	85000	M3	cutting work	B
	20%	4%	14000	315000	M3	Embankment work	C
	75%	75%	15	20	NO.	Provide necessary equipments to remove and install all existing poles ocated in the highway boundary.	D
						Culverts work	2nd
	50%	80%	80	100	M.L	single reinforced concrete box culvert (1x1m)	A
						REINFORCE CONCRETE WORK	3d
	80%	22.7%	182	802	M3	Lean Concrete	A
	60%	62%	1000	1627	M3	Reinforce concrete for foundation	B
	60%	60%	900	1500	M3	Reinforce concrete for Abutments	C
41%		Completion rate					

Annex 6: References

- North Iraqi demographic data, June 2001, Habitat-Erbil.
- Settlement and household survey report, Kurdistan Region Statistics Office, 2011
- http://www.krso.net/documents/192/FactSheet4_Services_21072012.pdf
- http://www.krso.net/documents/189/FactSheet1_Demography_21072012.pdf
- http://www.krso.net/documents/190/FactSheet2_Education_21072012.pdf
- World Bank: Involuntary Resettlement Sourcebook: Planning and Implementation in Development Projects
- Fair, G.M., J. C. Geyer. Water Supply and Waste-Water Disposal. John Wiley & Sons, Inc, London.
- FAO: Iraq Country Pasture/Forage Resource Profile
- ESCWA-BGR based on Aghanabati, 1993; Stevanovic and Markovic, 2004.
- National Report on Biodiversity in Iraq July 2010
- <http://www.epa.gov/otaq/models/moves/>
- <http://data.worldbank.org/indicator/NY.GDP.MKTP.CD> | The World Bank Group
- Regional Development Strategy for Kurdistan Region 2012-2016
- <https://www.cia.gov/library/publications/the-world-factbook/geos/iz.html>
- *Settlement and household survey report, Kurdistan Region Statistics Office, 2011*
- <http://cosit.gov.iq/en/rtl-support>
- <http://cosit.gov.iq/en/living-conditions-statistics/surveys>
- <http://cosit.gov.iq/en/population-manpower-statistics/manpower>
- Comprehensive food security and vulnerability survey of Iraq, 2007
- <http://www.fao.org/countryprofiles/index/en/?iso3=IRQ>
- World Bank: Involuntary Resettlement Sourcebook: Planning and Implementation in Development Projects
- Leopold et al., 1971
- R.F. Porter et al, Birds of the Middle East, First Princeton Field Guide Edition, 2004